



2020 Standard Specifications for Construction

Warranty No FHWA Oversight No
DBE % Yes NHS Yes

ITEM NUMBER
2311 022

STATE OF MICHIGAN DEPARTMENT OF TRANSPORTATION

PROPOSAL

3.60 mi of hot mix asphalt cold milling and resurfacing, intersection improvements and pavement markings on Saginaw Road from Pinesboro Drive to the west city limits of Midland, Midland County. This is a Local Agency project.

BIDS WILL BE ELECTRONICALLY DOWNLOADED AT 10:30 AM LOCAL TIME, ON 11/3/23

<u>CONTRACT ID</u>	<u>CONTROL SECTION</u>	<u>PROJECT</u>	<u>FEDERAL NUMBER</u>
56000-214571	STUL 56000	214571A	23A0865

The bidder has downloaded and examined the plans, specifications, special provisions, and related materials in the proposal, as well as the location of the work described in the proposal for this project, has obtained all addenda issued for this project, is fully informed as to the nature of the work and the conditions relating to its performance and understands that the quantities shown are approximate only and are subject to either increase or decrease.

The bidder hereby proposes to furnish all necessary machinery, tools, apparatus, and other means of construction, do all the work, furnish all the materials except as otherwise specified and, for each unit price, lump sum, or one each named in the itemized bid, to complete the work in strict conformity with the plans therefore and the entire proposal which is incorporated by reference in these pages, and in strict conformity with the requirements of the 2020 Standard Specifications for Construction, Michigan Department of Transportation and such other special provisions and supplemental specifications as may be a part of the proposal for this project.

The bidder further proposes to do such extra work as may be authorized by the Department, prices for which are not included in the itemized bid. Compensation shall be made on the basis agreed upon before such extra work is begun.

The bidder hereby certifies that if it is not prequalified in all classifications required by the advertisement for this project, it has taken such preparatory steps as may be necessary and will within the time specified in Subsection 102.14 of the 2020 Standard Specifications for Construction, designate subcontractor(s) that are fully prequalified in the classification(s) to perform the work.

THE BIDDER UNDERSTANDS AND AGREES THAT THE DEPARTMENT RESERVES THE RIGHT TO REJECT ANY AND ALL BIDS AND NO CONTRACTUAL RELATIONSHIP SHALL EXIST BETWEEN THE BIDDER AND THE DEPARTMENT FOR THE WORK DESCRIBED HEREIN UNTIL SUCH TIME AS THE CONTRACT HAS BEEN FORMALLY EXECUTED BY BOTH THE BIDDER AND THE DEPARTMENT.

The bidder agrees upon submitting this bid that its agents, officers or employees have not directly or indirectly entered into any agreements, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal for the above project.

Unless the bidder gives MDOT advance written notice, MDOT may correspond directly with the insurance agencies concerning questions and problems with the insurance certificates, bonds and related materials. It is the obligation of the bidder to monitor the filing of the insurance certificates, bonds, and related materials with MDOT and the bidder is responsible for any failure to provide MDOT with the required materials, on a timely basis and in proper form.

Subject to Subsection 102.16 of the 2020 Standard Specifications for Construction, the bidder agrees to pay to the Michigan Department of Transportation the bid guaranty sum of **\$50,000.00** if the bidder fails to provide the required materials and/or execute the contract in accordance with Subsection 102.14 of the 2020 Standard Specifications for Construction.

Bay City TSC



Schedule of Items

Report v1

Proposal ID: 56000-214571

Project(s): 214571A

Letting Number: 231103

Call Number: 022

Contractor: _____

Section Information

Section ID	Section Description	Section Total	Alt. Set ID	Alt. Member ID
1	Road Work			

Item Prices

Proposal Line Number	Item ID - Description	Approximate Quantity and Units	Unit Price	Bid Amount
0005	1100001 - Mobilization, Max\$104,200.00	1.000 LSUM		
0010	2040020 - Curb and Gutter, Rem	108.000 Ft		
0015	2050010 - Embankment, CIP	36.000 Cyd		
0020	2050016 - Excavation, Earth	260.000 Cyd		
0025	2080036 - Erosion Control, Silt Fence	500.000 Ft		
0030	3010002 - Subbase, CIP	28.000 Cyd		
0035	3077031 - _Approach, CI I, Modified	166.000 Ton		
0040	3077031 - _Shld, CI II, Modified	810.000 Ton		
0045	4030005 - Dr Structure Cover, Adj, Case 1	1.000 Ea		
0050	5010002 - Cold Milling HMA Surface	90,370.000 Syd		
0055	5010005 - HMA Surface, Rem	678.000 Syd		
0060	5010025 - Hand Patching	100.000 Ton		
0065	5010061 - HMA Approach	522.000 Ton		
0070	5012037 - HMA, 5EML	7,817.000 Ton		



Schedule of Items

Report v1

Item Prices

Proposal Line Number	Item ID - Description	Approximate Quantity and Units	Unit Price	Bid Amount
0075	8020016 - Curb and Gutter, Conc, Det B2	192.000 Ft		
0080	8020056 - Shld Gutter, Conc, Det 2	1.000 Ea		
0085	8020057 - Shld Gutter, Conc, Det 3	1.000 Ea		
0090	8020075 - Spillway, Conc	9.000 Ft		
0095	8070095 - Post, Mailbox	1.000 Ea		
0100	8100371 - Post, Steel, 3 pound	45.000 Ft		
0105	8100402 - Sign, Type III, Erect, Salv	4.000 Ea		
0110	8100616 - Reflective Panel for Permanent Sign Support, 6 foot	2.000 Ea		
0115	8102003 - Sign, Type III, Rem, Salv	4.000 Ea		
0120	8102010 - Ground Mtd Sign Support, Rem	2.000 Ea		
0125	8110045 - Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	45.000 Ft		
0130	8110063 - Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	4.000 Ea		
0135	8110071 - Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	3.000 Ea		
0140	8110231 - Pavt Mrkg, Waterborne, 4 inch, White	37,578.000 Ft		
0145	8110232 - Pavt Mrkg, Waterborne, 4 inch, Yellow	20,545.000 Ft		
0150	8110251 - Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	37,578.000 Ft		



Schedule of Items

Report v1

Item Prices

Proposal Line Number	Item ID - Description	Approximate Quantity and Units	Unit Price	Bid Amount
0155	8110252 - Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	20,545.000 Ft		
0160	8110351 - Witness, Log, \$1,250.00	1,250.000 Dlr	\$1.00	\$1,250.00
0165	8120012 - Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8.000 Ea		
0170	8120013 - Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8.000 Ea		
0175	8120035 - Channelizing Device, 42 inch, Fluorescent, Furn	250.000 Ea		
0180	8120036 - Channelizing Device, 42 inch, Fluorescent, Oper	250.000 Ea		
0185	8120140 - Lighted Arrow, Type C, Furn	2.000 Ea		
0190	8120141 - Lighted Arrow, Type C, Oper	2.000 Ea		
0195	8120170 - Minor Traf Devices	1.000 LSUM		
0200	8120245 - Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	33.000 Ft		
0205	8120246 - Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	2,827.000 Ft		
0210	8120310 - Sign Cover	5.000 Ea		
0215	8120350 - Sign, Type B, Temp, Prismatic, Furn	804.000 Sft		
0220	8120351 - Sign, Type B, Temp, Prismatic, Oper	804.000 Sft		
0225	8120352 - Sign, Type B, Temp, Prismatic, Spec, Furn	10.000 Sft		



Schedule of Items

Report v1

Item Prices

Proposal Line Number	Item ID - Description	Approximate Quantity and Units	Unit Price	Bid Amount
0230	8120353 - Sign, Type B, Temp, Prismatic, Spec, Oper	10.000 Sft		
0235	8120370 - Traf Regulator Control	1.000 LSUM		
0240	8130010 - Riprap, Plain	11.000 Syd		
0245	8162002 - Slope Restoration, Non-Freeway, Type B	180.000 Syd		
0250	8210001 - Monument Box	1.000 Ea		
0255	8210005 - Monument Box Adj	1.000 Ea		
0260	8227001 - _Sinusoidal Corrugations, Milled, HMA Centerline	13,403.000 Ft		
0265	8230431 - Gate Box, Adj, Case 1	1.000 Ea		

Section 1 Total:
Total Bid:

Letting Date:

Item No:

Contract ID:

DESIGNATED and SPECIALTY ITEMS

Designated Items:

Company Name of Prequalified Subcontractor:

(Company Name)

(Company Name)

(Company Name)

(Company Name)

(Company Name)

(Company Name)

Specialty Items:

(Company Name)

(Company Name)

See next page for information on completing this page

Rev. (12/22)

INFORMATION ON COMPLETION OF DESIGNATED AND SPECIALTY ITEMS PAGE

The contractor may sublet the item(s) of work stipulated on the DESIGNATED and SPECIALTY ITEMS page in this bid in accordance with Section 108.01 of the 2020 Standard Specifications, Section VII of the required provisions for Federal-Aid Contracts (with the exception noted in the following paragraph), and the following instructions.

The percentage of contract work performed by a contractor's own organization shall comply with Section 108.01 of the 2020 Standard Specifications, rather than the lower percentage allowed by Section VII of FHA required contract provisions (form FHWA 1273). Section 108.01 of the 2020 Standard Specifications requires thirty-five percent (35%) performance by a contractor's own organization.

If the contractor **IS NOT** prequalified in EITHER the DESIGNATED or SPECIALTY ITEMS noted in this bid, the contractor MUST, prior to contract award, indicate the company name of a prequalified subcontractor in the space provided. If such company name is provided, the contractor MUST sublet the appropriate items to the prequalified subcontractor named, **unless the subcontractor is not prequalified at the time the work is to be performed, or the subletting of the item to another prequalified subcontractor is agreed to in writing by both the contractor and the named subcontractor.**

If the contractor **IS** prequalified in EITHER the DESIGNATED or SPECIALTY ITEMS noted in this bid and does not intend to do the work with its own forces, the contractor may indicate the company name of a prequalified subcontractor in the space provided. If such company name is provided, the contractor MUST sublet the appropriate items to the prequalified subcontractor named, **unless the subcontractor is not prequalified at the time the work is to be performed, or the subletting of the item to another prequalified subcontractor is agreed to in writing by both the contractor and the named subcontractor.**

If the contractor **IS** prequalified in the DESIGNATED or SPECIALTY ITEMS noted and NO subcontractor is named, any later decision to subcontract said items of work is subject to the sixty-five percent (65%) limitation of subcontracting.

At the time that a subcontractor is named in a bid to perform any of the DESIGNATED or SPECIALTY ITEMS, that subcontractor must be prequalified for the classification which includes the work it is to perform. In selecting a subcontractor, the prime contractor shall assure itself that the prospective subcontractor has sufficient equipment, working force, and supervision to complete the designated or specialty items to be subcontracted within the specified time limit.

It is understood and agreed that the prequalification of the subcontractor by the Department pursuant to 1933 P.A. 170 is not a guarantee or warranty of the subcontractor's ability to perform or complete the work contained herein.

Rev. (3/22)

Table of Contents

Cover Page	1
Schedule of Items	2
Subcontract Provisions	7
Table of Contents	
Advertising Notice	12
Progress Clause	13
Maintaining Traffic incl. Details	14
WACKERLY ROAD DETOUR DETAIL	20
100-GEN-KEY	21
101-GEN-SPACING-CHARTS	22
102-GEN-NOTES	25
103-GEN-SIGN	27
104-GEN-AB	32
107-GEN-SPEED	33
110-TR-NFW-2L	35
122-NFW-SHL-(R)	36
WZD-100-A	37
WZD-125-E	48
Unique Special Provisions	51
Div 1 General Provisions	51
20TM107(A145) INSURANCE	51
Div 3 Bases	52
APPROACH, CL I, MODIFIED	52
SHLD, CL II, MODIFIED	53
Div 5 Hot Mix Asphalt Pavements & Surface Treatments	54
20TM501-A270-03 HOT MIX ASPHALT PRICES FOR ADJUSTMENTS	54
Div 8 Incidental Construction	55
20TM816(A385) SLOPE RESTORATION, NON-FREEWAY	55
20TM822(A380) NON-FREEWAY CENTERLINE SINUSOIDAL CORRUGATIONS	60
Special Provisions for this Project	63
20SP-1001A-01 MIXING PORTLAND CEMENT CONCRETE	63
20SP-1002A-01 ALKALI SILICA REACTIVITY OF FINE AGGREGATE USED IN PORTLAND CEMENT CONCRETE	64
20SP-1003B-01 QUALITY INDEX FOR PORTLAND CEMENT CONCRETE (FOR LOCAL AGENCY PROJECTS ONLY)	66
20SP-102C-01 DISSEMINATION OF PUBLIC RELATIONS INFORMATION	70
20SP-104A-01 VALUE ENGINEERING CHANGE PROPOSAL	71
20SP-104C-02 CONSTRUCTION DOCUMENT MANAGEMENT	75

20SP-104D-01 PREVAILING WAGE AND LABOR COMPLIANCE SYSTEM	78
20SP-105A-04 SOURCE OF STEEL AND IRON (BUY AMERICA)	80
20SP-105B-02 SOURCE OF CONSTRUCTION MATERIALS	82
20SP-107C-01 E-VERIFY	83
20SP-107D-01 LABOR COMPLIANCE	84
20SP-107F-01 EASTERN MASSASAUGA RATTLESNAKE	87
20SP-108C-02 UTILIZING DISADVANTAGED BUSINESS ENTERPRISE TRUCKING VENDORS	89
20SP-109A-01 PROMPT PAYMENT	90
20SP-208A-01 NON-COMPLIANCE WITH SOIL EROSION AND SEDIMENTATION CONTROL REQUIREMENTS	94
20SP-501A-01 SAMPLING ASPHALT BINDER ON LOCAL AGENCY PROJECTS	96
20SP-501F-01 RECYCLED HOT MIX ASPHALT MIXTURE ON LOCAL AGENCY PROJECTS	97
20SP-501I-01 ACCEPTANCE OF HOT MIX ASPHALT MIXTURE ON LOCAL AGENCY PROJECTS	99
20SP-802A-02 CONCRETE CURB, AND GUTTER, WITH __ FIBER REINFORCED POLYMER, DETAIL __	106
20SP-802B-01 BACKFILL FOR CONCRETE CURB, GUTTER, AND DIVIDERS	110
20SP-810F-02 GROUND MOUNTED SIGN SUPPORTS, REMOVE	111
20SP-811C-01 PAVEMENT MARKING EQUIPMENT	112
20SP-812A-02 MOBILE ATTENUATOR	114
20SP-816B-01 EXCAVATED TOPSOIL OR SALVAGED TOPSOIL	118
20SP-900A-01 INDUSTRIAL BY-PRODUCTS AND BENEFICIAL RE-USE	119
20SP-901A-01 PORTLAND CEMENT (TYPE II)	120
20SP-902A-01 AGGREGATE, 46G	122
20SP-912A-01 MICRONIZED COPPER WATER BASED WOOD PRESERVATIVE SYSTEMS	123
20SP-920A-01 WET REFLECTIVE PAVEMENT MARKINGS	124
20SP-922A-02 TEMPORARY PAVEMENT MARKING, TYPE R TAPE REVISION	125
Notice to Bidders for this Project	126
20NB01-02 MULTIPLE DAVIS-BACON WAGE DECISIONS	126
20NB02 BID RIGGING	127
20NB03 FRAUD AND ABUSE HOTLINE	128
20NB04-05 USE OF CRUSHED CONCRETE FOR DENSE- AND OPEN-GRADED AGGREGATES	129
Utility Coordination	130
Supplemental Specifications	132
20SS-001A-14 ERRATA TO THE 2020 STANDARD SPECIFICATIONS	132
Log of Project (Title Sheet)	142
Project Log	143
General Plan Notes	146
Standard Plan Notes	148

Typical Sections	149
Miscellaneous Detail	155
Plan Sheets	169
Special Detail Sheets	173
R-100-I	173
R-112-J	177
PAVE-904-B	187
Notice of Bidders - Contact Person	189
Labor Rates	190



Notice of Advertisement

Report v1

Letting of: 231103

10:30 AM, Local Time 425 W. OTTAWA ST., LANSING, MI 48933

Call Number	Contract ID	Control Section	Project Number	Federal Project Number
022	56000-214571	STUL 56000	214571A	23A0865

Description: 3.60 mi of hot mix asphalt cold milling and resurfacing, intersection improvements and pavement markings on Saginaw Road from Pinesboro Drive to the west city limits of Midland, Midland County. This is a Local Agency project.

Required DBE Participation: 4.00%

Net Classification Required For This Project: ** 1146 Cb **

Estimated Pages For Plans: 0

Completion Date: 6/14/2024

In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N9-3A. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

Date Advertised: 10/6/2023

See proposal for bidder guaranty information.

Proposal and plans, if applicable, are available for examination online at <<http://mdotcf.state.mi.us/public/eprop/login/index.cfm>>

PROGRESS CLAUSE

The Engineer anticipates that construction can begin no earlier than **April 15, 2024**.

In no case, may any work be commenced prior to receipt of formal notice of award by the Michigan Department of Transportation.

The Contractor shall prepare and submit a complete, detailed, signed Progress Schedule to the Engineer. The Engineer for this project is as follows:

Jonathan Myers, P.E.
Midland County Road Commission
2334 North Meridian Road
Sanford, MI 48657
(989) 687-9060
jon@midlandroads.com

The progress schedule submittal must include, as a minimum, the controlling work items for the completion of the project and the planned dates (or work days for a work day project) that the work items will be the controlling operations. All contract dates including open to traffic, project completion, interim completion and any other controlling dates in the contract must be included in the progress schedule.

The road must fully open to traffic no later than the interim completion date of **May 24, 2024**. All work items except Slope Restoration and the second application of pavement markings shall be completed by this date.

The entire project must be completed on or before the final project completion date of **June 14, 2024**.

Unless specific pay items are provided in the contract any extra costs incurred by the Contractor due to cold-weather protection and winter grading will not be paid for separately but will be included in the payment of other pay items in the contract.

After award and prior to the start of work, the Contractor must attend a preconstruction meeting with the Engineer. The Engineer will determine the day, time and place for the preconstruction meeting. The meeting will be conducted after project award and may be rescheduled if there are delays in the award of the project.

The named subcontractor(s) for Designated and/or Specialty Items, as shown in the Proposal, should attend the preconstruction meeting if such items materially affect the work schedule.

Failure by the Contractor to meet interim completion, open to traffic, and/or final completion dates will result in the assessment of liquidated damages in accordance with subsection 108.10 of the Standard Specifications for Construction.

The Contractor may be required to meet with Department representatives for a post-construction review meeting, as directed by the Engineer. The Engineer will schedule the meeting.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
MAINTAINING TRAFFIC

MCRC: ROWE

1 of 6

AUGUST 2023

a. Description. This special provision consists of requirements and restrictions to maintain traffic on Saginaw Road in Lincoln and Homer Townships, Midland County.

b. General. Maintain traffic throughout the project in accordance with the standard specifications, typicals, and supplemental specifications in the contract and as described on the plans for this project.

c. Construction Influence Area (CIA). The CIA includes the right-of-way of the following roadways, within the approximate limits described below:

1. On Saginaw Road from approximately 0.6 mile west of Pinesboro Drive to 1.0 mile east of Dublin Road.

2. In addition, the CIA includes the right-of-way of any intersecting roads adjacent to the work zone for a distance of approximately 1/4 mile in advance of the work zone or as far as the construction or detour signing extends. The roads include but are not limited to Pinesboro Drive, 5 Mile Road, Wackerly Road, Hope Road, Tittabawassee River Road and Stark Road.

d. Traffic Restrictions. Maintain traffic in accordance with the Maintaining Traffic Typicals contained herein, except as noted below. Changes or adjustments to the Maintaining Traffic Typicals may be necessary to fit field conditions, subject to approval of the Engineer or as determined by the Engineer.

1. Utilize the following Maintaining Traffic Typicals:

A. 100-GEN-KEY

B. 101-GEN-SPACING-CHARTS

C. 102-GEN-NOTES

D. 103-GEN-SIGN

E. 104-GEN-AB

F. 107-GEN-SPEED

G. 110-TR-NFW-2L

H. 122-NFW-SHL-(R)

I. WZD-100-A

J. WZD-125-E

2. Do not work, deliver material, or close lanes (other than approved stage closures) during the holiday periods as defined in Table 1.

Table 1: 2024 Holiday Periods

Holiday	Start Date and Time	End Date and Time
Memorial Day	3:00 p.m. Friday, May 24 th	6:00 a.m. Tuesday, May 28 th

3. Perform work and lane closures within the allowable time frames as shown in Table 2, unless otherwise approved by the Engineer.

Table 2: Saginaw Road Traffic Restrictions

Closure Type	Start Time	End Time	M	Tu	W	Th	F	Sa	Su
Shoulder Closures	00:00	24:00	∞	∞	∞	∞	∞	∞	∞
Single Lane Closures	00:00	08:00	0	0	0	0	0	0	0
	08:00	18:00	∞	∞	∞	∞	∞	∞	0
	18:00	24:00	0	0	0	0	0	0	0
∞ = Closure is allowed, and the frequency is not limited during the project timeframe # = The number of times closures can take place during the project timeframe.									

4. Maintain a minimum of one lane of bi-directional traffic at all times on Saginaw Road using shoulder closures or traffic regulator control. One lane of traffic in each direction must be open in accordance with the restrictions in Table 2.

5. Maintain a minimum of one lane of traffic in each direction at all times on all signalized side roads.

6. No more than 1 closure is allowed at the same time.

A. The maximum closure length is 1 mile unless otherwise approved by the Engineer.

7. Close any dedicated lanes (turn, etc.) prior to the location under construction.

8. When a lane is closed, place channelizing devices at cross streets and major drives to form a radius that clearly defines the approaches to the through and turning traffic.

9. Restrict access to and from side roads for short durations at specific locations as the Engineer directs or approves. Where an intersection is closed or partially closed, allow the adjacent intersections one block to the east and west to remain open to traffic, unless otherwise approved by the Engineer. The following work items listed are eligible to take place under a traffic stoppage, HMA approach paving. Additional work items can be allowed as approved by the Engineer.

7. Maintain access to all driveways as directed by the Engineer unless prior agreements are made with the respective property owners. The cost of constructing driveways part width

will not be paid for separately but will be considered included in the cost of other driveway pay items.

e. Traffic General.

1. For any lane open to traffic, provide a minimum lane width of 11 feet with 1 feet of shy distance on both sides unless identified otherwise on plans.

2. Do not close lanes or utilize traffic regulation sequences where work can be accomplished with a shoulder closure. Do not occupy any part of the active traffic lane with personnel or equipment when utilizing a shoulder closure.

3. Prior to shifting traffic onto shoulders or opening any lanes/shoulders, remove, by sweeping all accumulated debris that has collected within the shoulder and/or within the closed lane/shoulder.

4. A speed reduction will be used. Set the work zone speed limit on Saginaw Road to 45 miles per hour (mph).

5. Protect the work area at the end of each day. Close all open access points on the project to traffic with Type III barricades or other devices approved by the Engineer.

6. The Engineer will be responsible for notifying emergency services, transit agencies, law enforcement and schools prior to any lane closures, detours or major traffic shifts. In addition, the Contractor will be responsible for working with and complying with any coordination that is necessary with the Department and emergency services, transit agencies, law enforcement and schools. All costs associated with these coordination efforts will be considered included in the pay item "Minor Traf Devices".

7. Remove all temporary traffic control devices from the Midland County Road Commission and City of Midland right-of-way during any shut down periods unless needed for directly maintaining or channelizing traffic. No additional payment will be made for removal and/or redeployment of these devices except for in the case of an approved extension of time.

8. Cover or remove construction signing that refers to work zone speed when work at a location is planned to be inactive for a period greater than 2 days, unless otherwise specified on the plans or as directed by the Engineer.

9. Once work is initiated that includes any lane restrictions, that work must be continued daily until completed.

f. Traffic Regulator Control.

1. Maintain two-way traffic at all times on Saginaw Road using traffic regulator control. A traffic regulator sequence is allowed to cover a maximum closure length of 1.0 mile. Place the arrow panel, signs and channelizing taper for the traffic regulator operation at locations approved by the Engineer for adequate visibility by oncoming traffic.

2. Do not utilize more than (1) traffic regulator operation(s) at one time on Saginaw Road.

3. Crossroads must remain open to traffic at all times. Use intermediate traffic regulators at each intersection approach and commercial driveways within the closure limits, as directed by the Engineer. Use traffic regulator control as directed by the Engineer for cross street traffic while paving through intersections.

4. Follow the [Michigan Traffic Regulator's Instruction Manual](#) for operations at signalized intersections. Contact the maintaining agency prior to work on traffic signals. Only the maintaining agency may make changes to the traffic signal controllers.

g. Stage Construction. Maintain traffic in accordance with the restrictions listed in section d. Traffic Restrictions and the sequence of operations contained herein. Use of an alternate traffic control plan is subject to review and approval by the Engineer.

1. Stage 1.

A. Complete right turn lane taper reconstruction at the Stark Road intersection and Wackerly Road intersection approach realignment.

B. Close East Wackerly Road between Saginaw Road and Tittabawassee River Road and detour traffic in accordance with the plans.

C. Close the westbound shoulder on Saginaw Road in accordance with Maintaining Traffic Typical 122-NFW-SHL-(R). Traffic regulator control in accordance with Maintaining Traffic Typical 110-TR-NFW-2L following the time restrictions in Table 2 may be used to maintain traffic on Saginaw Road as approved by the Engineer.

2. Stage 2.

A. Complete all milling, paving, and aggregate shoulder work.

B. Place signing for a two-lane two-way roadway where one lane is closed utilizing traffic regulator control in accordance with Maintaining Traffic Typical 110-TR-NFW-2L following the time restrictions in Table 2.

h. Earthwork and Excavation.

1. Restore undercuts or excavations in the work areas within 3 feet of the active traffic lanes to no steeper than a 1 on 4 slope from the edge of the roadway at the end of each work day. If this condition is not met, provide a nighttime closure.

2. Delineate excavated areas located within 3 feet of traffic with channelizing devices at 20 feet spacing along the excavated area, and 100 feet before the area, or as shown on the maintaining traffic plans.

i. Hot Mix Asphalt (HMA) Work.

1. Resurface all HMA milled areas within 48 hours of the HMA cold milling operation. All HMA milled areas must be resurfaced prior to end of day Friday unless Saturday work is approved by the Engineer.

2. Provide transverse and longitudinal HMA tapers at all grade changes greater than 1.5 inches caused by cold milling and overlay. Place W8-1 (“BUMP”) signs in advance of transverse HMA tapers. Place W8-11 (“UNEVEN LANES”) signs in advance of longitudinal HMA tapers. Place W8-9 (“LOW SHOULDER”) signs in advance of and every mile within the shoulder drop off.

j. Traffic Control Devices. Ensure all traffic control devices are in accordance with the *MMUTCD* and must meet the “acceptable” criteria as defined in the *ATSSA* publication entitled “*Quality Guidelines for Temporary Traffic Control Devices and Features*” at the time of initial deployment and after each major stage change.

1. During non-working periods, place applicable advance signs and channelizing devices at specific locations, as directed by the Engineer, at no additional cost to the Department.

2. Notify the Engineer 24 hours in advance of when traffic control devices are being delivered to the project site, to allow for initial inspection of devices to take place.

3. Remove from the project site all traffic control devices (including detour signing) no longer needed for a particular operation and equipment for construction within 14 calendar days of reopening the shoulder/lane/roadway.

4. Channelizing Devices.

A. Ensure all devices have sufficient ballast to prevent moving or tipping. If moving or tipping occurs, place additional ballast, as directed by the Engineer, at no additional cost to the Department. No more than two ballasts are allowed on each channelizing device.

B. Do not use caution tape on this project.

5. Temporary Signs.

A. Additional W20-1 (ROAD WORK AHEAD) signs are included in the quantities to be placed on all intersecting or adjacent roads where construction activities may be encountered.

B. Fabricate, install, and remove temporary sign overlays on existing signs with the pay item for Sign, Type B, Temp, Prismatic, Furn. Attach the overlay in accordance with subsection 812.03.D.2 of the Standard Specifications for Construction.

k. Temporary Pavement Markings.

1. Quantities for temporary tape to be placed during paving operations are based on the MDOT PAVE 900 Series standard plans.

2. When Type R or NR tape is used, ensure that all temporary pavement markings adhere to the pavement surface until permanent markings are installed.

3. Replace all existing pavement markings that are removed for traffic control or obliterated during construction.


I. Measurement and Payment. Payment will be in accordance with the standard specifications unless otherwise specified. No additional payment will be made for the following activities:

1. Transporting traffic control items from site to site.
2. Providing sufficient vehicles and staff to make changes as-needed on site during work.
3. Providing sufficient vehicles and staff to remove closures from the roadway.
4. Providing additional traffic control devices required to expedite the construction for the convenience of the Contractor.





NOTES:

1. SIGN SPACING TO BE IN ACCORDANCE WITH MDOT MAINTAINING TRAFFIC TYPICAL 103-GEN-SIGN.
2. COORDINATE PLACEMENT OF TEMPORARY TRAFFIC CONTROL DEVICES WITH OTHER LANE CLOSURES IN PLACE, INCLUDING, BUT NOT LIMITED TO, TRAFFIC REGULATOR CONTROL OPERATIONS.




INTERSECTION DETAIL





ERECT R11-4 BEHIND BARRICADE ON SEPARATE SIGN SUPPORTS. PLACE TYPE III BARRICADE, R11-4 AND M4-10L ON THE SHOULDER.

(A)



ERECT R11-2 BEHIND BARRICADE ON SEPARATE SIGN SUPPORTS. SUPPLY ENOUGH TYPE III BARRICADES TO COMPLETELY CLOSE ROAD BETWEEN SHOULDER EDGES OR CURB FACES.

(B)



DESIGN UNIT: MIDLAND CRC
 CS: 56000
 JN: 214571

TSC: MT. PLEASANT
 SAGINAW ROAD RESURFACING
 WACKERLY ROAD DETOUR


DATE: 08/21/23
 DRAWING SHEET
 SECT 1

FILE:

TYPICAL NUMBER KEY

CODES

AB = ARROW BOARD AW = ADVANCE WARNING C = CLOSURE CLT = CENTER LEFT TURN LANE CROSS = CROSSOVER CruSha = CRUSH AND SHAPE EM = EARLY MERGE EnR = ENTRANCE RAMP ExR = EXIT RAMP FW = FREEWAY GEN = GENERAL INFORMATION GORE = FREEWAY GORE AREA IN = INSIDE INT = INTERSECTION L = LANE (L) = LEFT LC = LANE CLOSURE LD = LONG DURATION	LO = LANE OPEN O = OUTSIDE (LANE CLOSURE) OUT = OUTSIDE OF SHOULDER MID = MIDDLE OF INTERSECTION OR ROAD NFW = NON-FREEWAY PARK = PARKING LANE PCMS = PORTABLE CHANGEABLE MESSAGE SIGN (R) = RIGHT ROLL = ROLLING ROADBLOCK RUM = RUMBLE STRIP SD = SHORT DURATION SHL = SHOULDER CLOSURE SIGN = SIGN SP = SPECIAL SPEED = SPEED STA = STOPPED TRAFFIC ADVISORY TR = TRAFFIC REGULATOR TS = TEMPORARY SIGNAL ZIP = ZIPPER MERGE
--	---



- 100 - GENERAL NOTES
- 110 - TRAFFIC REGULATORS
- 120 - NON-FREEWAY
- 130 - CENTER LEFT TURN (CLT) LANES
- 140 - PARKING LANES
- 150 - CLT 7 LANE SECTIONS
- 160 - SIGNAL WORK
- 200 - FREEWAY CLOSURES
- 210 - FREEWAY LANE SHIFTS
- 220 - FREEWAY ENTRANCE RAMPS
- 230 - FREEWAY EXIT RAMPS
- 300 - ADVANCE WARNINGS
- 310 - CROSSOVER CLOSURE
- 320 - CRUSH AND SHAPE
- 340 - MERGE SYSTEMS
- 350 - GORE LOCATIONS
- 360 - ROLLING ROADBLOCK
- 4000 - MAINTENANCE
- 5000 - SURVEY

EXAMPLE TYPICAL

CODE: 152-CTL(7)-3(1R+2L)LC-2(L)SHIFT

152 - TYPICAL NUMBER

CTL(7) = CENTER LEFT TURN LANE, 7 LANES TOTAL.

3(1R+2L)LC = 3 LANES CLOSED, (1 RIGHT LANE AND 2 LEFT LANES).

2(L)SHIFT = 2 LANES SHIFTED TO THE LEFT.

NOT TO SCALE

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	TYPICAL NUMBERING KEY	DATE: DECEMBER 2021
		NO: 100-GEN-KEY		SHEET: 1 OF 1

FILE: 100-GEN-KEY.dgn

DISTANCE BETWEEN TRAFFIC SIGNS, "D"

"D" DISTANCES	POSTED SPEED LIMIT, MPH (PRIOR TO WORK AREA)										
	25	30	35	40	45	50	55	60	65	70	75
D (FEET)	250	300	350	400	450	500	550	600	650	700	750

GUIDELINES FOR LENGTH OF LONGITUDINAL BUFFER SPACE, "B"

"B" LENGTHS	SPEED*, MPH (PRIOR TO WORK AREA)											
	20	25	30	35	40	45	50	55	60	65	70	75
B (FEET)	33	50	83	132	181	230	279	329	411	476	542	625

* POSTED SPEED, OFF-PEAK 85TH PERCENTILE SPEED PRIOR TO WORK STARTING, OR THE ANTICIPATED OPERATING SPEED.

MINIMUM MERGING TAPER LENGTH, "L" (FEET)

OFFSET (FEET)	POSTED SPEED LIMIT, MPH (PRIOR TO WORK AREA)										
	25	30	35	40	45	50	55	60	65	70	75
1	11	15	21	27	45	50	55	60	65	70	75
2	21	30	41	54	90	100	110	120	130	140	150
3	32	45	62	80	135	150	165	180	195	210	225
4	42	60	82	107	180	200	220	240	260	280	300
5	53	75	103	134	225	250	275	300	325	350	375
6	63	90	123	160	270	300	330	360	390	420	450
7	73	105	143	187	315	350	385	420	455	490	525
8	84	120	164	214	360	400	440	480	520	560	600
9	94	135	184	240	405	450	495	540	585	630	675
10	105	150	205	267	450	500	550	600	650	700	750
11	115	165	225	294	495	550	605	660	715	770	825
12	125	180	245	320	540	600	660	720	780	840	900
13	136	195	266	347	585	650	715	780	845	910	975
14	146	210	286	374	630	700	770	840	910	980	1050
15	157	225	307	400	675	750	825	900	975	1050	1125

NOT TO SCALE

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	"B", "D" AND "L" TABLES CHANNELIZING DEVICE SPACING, SIGN BORDER KEY, AND ROLL-AHEAD SPACING	DATE: MAY 2021
		NO: 101-GEN-SPACING-CHARTS		SHEET: 1 OF 3

FILE: 101-GEN-SPACING-CHARTS.dgn

THE FORMULAS FOR THE MINIMUM LENGTH OF A MERGING TAPER IN DERIVING THE "L" VALUES SHOWN IN THE ABOVE TABLES ARE AS FOLLOWS:

"L" = $\frac{W \times S^2}{60}$ WHERE POSTED SPEED PRIOR TO THE WORK AREA IS 40 MPH OR LESS

"L" = W X S WHERE POSTED SPEED PRIOR TO THE WORK AREA IS 45 MPH OR GREATER

L = MINIMUM LENGTH OF MERGING TAPER
 S = POSTED SPEED LIMIT IN MPH PRIOR TO WORK AREA
 W = WIDTH OF OFFSET

TYPES OF TAPERS

UPSTREAM TAPERS

- MERGING TAPER
- SHIFTING TAPER
- SHOULDER TAPER
- 2 TO 1 LANE ROAD TAPER

TAPER LENGTH

- L - MINIMUM
- 1/2 L - MINIMUM
- 1/3 L - MINIMUM
- 100' - MAXIMUM

DOWNSTREAM TAPERS
 (USE IS RECOMMENDED)


100' (PER LANE)

MAXIMUM SPACING FOR CHANNELIZING DEVICES

WORK ZONE SPEED LIMIT	DRUM AND 42" DEVICE SPACING (FT)		NIGHTTIME 42" DEVICE SPACING (FT)	
	TAPER	TANGENT	TAPER	TANGENT
< 45 MPH	1 x SPEED LIMIT	2 x SPEED LIMIT	25 FEET	50 FEET
≥ 45 MPH	50 FEET	100 FEET	25 FEET	50 FEET

SIGN OUTLINE KEY

DASHED OUTLINES INDICATE A SIGN THAT EXISTS ON SITE, AND NEEDS TO BE COVERED.



SOLID OUTLINES INDICATE A SIGN THAT IS TO BE PLACED ON THE PROJECT



NOT TO SCALE

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	"B", "D" AND "L" TABLES CHANNELIZING DEVICE SPACING SIGN BORDER KEY AND ROLL-AHEAD SPACING	DATE: MAY 2021
		NO: 101-GEN-SPACING-CHARTS		SHEET: 2 OF 3

FILE: 101-GEN-SPACING-CHARTS.dgn

GUIDELINES FOR ROLL-AHEAD DISTANCES FOR TMA VEHICLES – TEST LEVEL 2

WEIGHT OF TMA VEHICLE	PREVAILING SPEED (POSTED SPEED PRIOR TO WORK ZONE)	ROLL-AHEAD DISTANCE* (DISTANCE FROM FRONT OF TMA VEHICLE TO WORK AREA)
5.5 TONS (STATIONARY)	40 MPH OR LESS	25 FT

* ROLL-AHEAD DISTANCES ARE CALCULATED USING A 4,410 POUND IMPACT VEHICLE WEIGHT.

GUIDELINES FOR ROLL-AHEAD DISTANCES FOR TMA VEHICLES – TEST LEVEL 3

WEIGHT OF TMA VEHICLE	PREVAILING SPEED (POSTED SPEED PRIOR TO WORK ZONE)	ROLL-AHEAD DISTANCE* (DISTANCE FROM FRONT OF TMA VEHICLE TO WORK AREA)
5 TONS (MOBILE)	45 MPH	100 FT
	50-55 MPH	150 FT
	60-75 MPH	175 FT
12 TONS (STATIONARY)	45 MPH	25 FT
	50-55 MPH	25 FT
	60-75 MPH	50 FT

* ROLL-AHEAD DISTANCES ARE CALCULATED USING A 10,000 POUND IMPACT VEHICLE WEIGHT.



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO: 101-GEN-SPACING-CHARTS

"B", "D" AND "L" TABLES
CHANNELIZING DEVICE SPACING
SIGN BORDER KEY AND ROLL AHEAD SPACING

DATE: MAY 2021

SHEET: 3 OF 3

THE FOLLOWING NOTES APPLY IF CALLED FOR ON THE TRAFFIC TYPICAL

GENERAL NOTES

- G1: SEE GEN-SPACING-CHARTS FOR COMMON VALUES INCLUDING:
 D = DISTANCE BETWEEN TRAFFIC CONTROL DEVICES
 L = MINIMUM LENGTH OF TAPER
 B = LENGTH OF LONGITUDINAL BUFFER
 ROLL AHEAD DISTANCE
- G2: DISTANCE BETWEEN SIGNS, "D", THE VALUES FOR WHICH ARE SHOWN IN TYPICAL GEN-KEY ARE APPROXIMATE AND MAY NEED ADJUSTING AS DIRECTED BY THE ENGINEER.
- G3: ALL TEMPORARY SIGNS, TYPE III BARRICADES, THEIR SUPPORT SYSTEMS AND LIGHTING MUST MEET NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM REPORT 350 (NCHRP 350) TEST LEVEL 3, OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) TL-3 AS WELL AS THE CURRENT EDITION OF THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE CURRENT EDITION OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE STANDARD PLANS AND APPLICABLE SPECIAL PROVISIONS. ONLY DESIGNS AND MATERIALS APPROVED BY MDOT WILL BE ALLOWED.
- G4: DO NOT STORE EQUIPMENT, MATERIALS OR PERFORM WORK IN ESTABLISHED BUFFER AREAS.
- G5: ALL EXISTING PAVEMENT MARKINGS WHICH ARE IN CONFLICT WITH EITHER PROPOSED CHANGES IN TRAFFIC PATTERNS OR PROPOSED TEMPORARY TRAFFIC MARKINGS SHALL BE REMOVED BEFORE ANY CHANGE IS MADE IN THE TRAFFIC PATTERN. EXCEPTION WILL BE MADE FOR TRAFFIC PATTERNS FOR WORK LESS THAN THREE DAYS THAT ARE ADEQUATELY DELINEATED BY OTHER TRAFFIC CONTROL DEVICES.

SIGN NOTES

- S1: ALL NON-APPLICABLE SIGNING WITHIN THE CIA MUST BE MODIFIED TO FIT CONDITIONS, COVERED, OR REMOVED. FOR GUIDANCE SEE THE WORK ZONE SAFETY AND MOBILITY MANUAL, SECTIONS 6.01.09 AND 6.01.10.
- S2: R5-18b SIGNS ARE ONLY REQUIRED ON FREEWAY PROJECTS WITH A DURATION OF 15 DAYS OR LONGER OR NON-FREEWAY PROJECTS WITH A DURATION OF 90 DAYS OR LONGER. TO APPLY THIS TYPICAL WITHOUT R5-18b SIGNS, REMOVE THE SIGNS AND CONSOLIDATE THE SEQUENCE AS APPROPRIATE.
- S3: R5-18c IS ONLY REQUIRED IN THE INITIAL SIGNING SEQUENCE IN THE WORK ZONE. OMIT THIS SIGN IN SUBSEQUENT SEQUENCES IN THE SAME WORK ZONE.
- S4: ADDITIONAL SIGNING AND/OR ELONGATED SIGNING SEQUENCES SHOULD BE USED WHEN TRAFFIC VOLUMES ARE SIGNIFICANT ENOUGH TO CREATE BACKUPS BEYOND THE W20-5 SIGNS.
- S5: PLACE ADDITIONAL SPEED LIMIT SIGNS REFLECTING THE WORK ZONE SPEED AFTER EACH MAJOR CROSSROAD THAT INTERSECTS THE WORK ZONE, OR AFTER EACH ENTRANCE RAMP THAT COMES ONTO THE FREEWAY WHERE THE REDUCED SPEED IS IN EFFECT. PLACE ADDITIONAL SPEED LIMIT SIGNS AT INTERVALS ALONG THE ROADWAY SUCH THAT NO SPEED LIMIT SIGNS ARE MORE THAN 2 MILES APART. WHEN REDUCED SPEED LIMITS ARE UTILIZED IN THE WORK AREA, PLACE ADDITIONAL SPEED LIMIT SIGNS RETURNING TRAFFIC TO ITS NORMAL SPEED BEYOND THE LIMITS OF THE WORK AREA AS INDICATED. IF PERMANENT SIGNS DISPLAYING THE CORRECT SPEED LIMIT ARE POSTED, OMIT ALL W3-5b AND R2-1 SIGNS AND REDUCE SPACING ACCORDINGLY.
- S6: FABRICATE SPECIAL SIGNS IN ACCORDANCE WITH CURRENT SIGNING DESIGN STANDARDS.
- S7: PLACE ADDITIONAL R8-3 SIGNS AT A MAXIMUM 500' SPACING THROUGHOUT THE WORK ZONE.
- S8: WHEN SPEED LIMIT SIGNS CANNOT BE PLACED SIDE BY SIDE AS SHOWN, PLACE THEM "D" DISTANCE APART.
- S9: STOP SIGNS NOT REQUIRED IF SIGNALS ARE ON 4-WAY FLASHING RED. STOP AHEAD SIGNS ARE NOT REQUIRED IF THERE IS ADEQUATE VISIBILITY OF THE STOP SIGN OR IF SIGNALS ARE BEING USED TO CONTROL TRAFFIC.
- S10: PLACE REDUCED SPEED ZONE AHEAD SIGN (W3-5b) HERE WHEN USING A SPEED REDUCTION IN THIS DIRECTION.
- S11: THE NUMBER OF W1-6 SHIFT SIGNS TO PLACE FOR A SHIFT IS AS FOLLOWS:
 SHIFTS 4FT OR LESS, PLACE ONE W1-6(R)(L)
 SHIFTS 5FT TO 12FT, PLACE TWO W1-6(R)(L)
 SHIFTS MORE THAN 12FT, PLACE THREE OR MORE W1-6(R)(L) SIGNS DEPENDING UPON LENGTH OF SHIFT AND AS PER THE ENGINEER.
- S12: PLACE R2-1 SIGNS AS DETAILED IN NOTE S5 WHEN THERE IS A SPEED REDUCTION IN THIS DIRECTION

TRAFFIC REGULATOR NOTES

- TR1: TRAFFIC REGULATORS MUST FOLLOW ALL THE REQUIREMENTS IN THE STANDARD SPECIFICATIONS, THE STANDARD PLANS AND APPLICABLE SPECIAL PROVISIONS, THE CURRENT VERSIONS OF THE TRAFFIC REGULATOR'S INSTRUCTION MANUAL AND THE VIDEO "HOW TO SAFELY REGULATE TRAFFIC IN MICHIGAN". THE MAXIMUM DISTANCE BETWEEN THE TRAFFIC REGULATORS IS DETERMINED BY THE ROADWAY ADT, GEOMETRICS, AND AS DIRECTED BY THE ENGINEER.
- TR2: PROVIDE APPROPRIATE BALLOON LIGHTING TO SUFFICIENTLY ILLUMINATE TRAFFIC REGULATOR'S STATIONS WHEN TRAFFIC REGULATING IS ALLOWED DURING THE HOURS OF DARKNESS.
- TR3: PROVIDE EITHER A STOP/SLOW AFAD OR A RED/YELLOW LENS AFAD, MEETING THE REQUIREMENTS OF THE MMUTCD

TEMPORARY TRAFFIC CONTROL DEVICE NOTES

- TCD1: THE MAXIMUM DISTANCE IN FEET BETWEEN CHANNELIZING DEVICES IN A TAPER SHOULD NOT EXCEED 1.0 TIMES THE WORK ZONE SPEED LIMIT IN MPH FOR ROADWAYS WITH A POSTED WORK ZONE SPEED LIMIT LESS THAN 45 MPH AND SHOULD NOT EXCEED 50 FEET ON ROADWAYS WITH A POSTED WORK ZONE SPEED LIMIT OF 45 MPH OR GREATER. THE SPACING FOR 42 INCH CHANNELIZING DEVICE TAPERS ARE NOT TO EXCEED 25 FEET AT NIGHT.
- TCD2: THE MAXIMUM DISTANCE IN FEET BETWEEN CHANNELIZING DEVICES IN A TANGENT SHOULD NOT EXCEED TWICE THE WORK ZONE SPEED LIMIT IN MPH FOR ROADWAYS WITH A POSTED WORK ZONE SPEED LIMIT LESS THAN 45 MPH AND SHOULD NOT EXCEED 100 FEET ON ROADWAYS WITH A POSTED WORK ZONE SPEED LIMIT OF 45 MPH OR GREATER. THE SPACING FOR 42 INCH CHANNELIZING DEVICE TANGENTS ARE NOT TO EXCEED 50 FEET AT NIGHT.
- TCD3: TYPE III BARRICADES MUST BE LIGHTED FOR OVERNIGHT CLOSURES.
- TCD4: WHEN THE HAUL ROAD IS NOT IN USE, PLACE LIGHTED TYPE III BARRICADES WITH "ROAD CLOSED" EXTENDING COMPLETELY ACROSS THE HAUL ROAD.
- TCD5: USE OBJECT MARKER SIGNS IN LIEU OF THE TYPE B HIGH INTENSITY LIGHT SHOWN IN THE STANDARD PLAN FOR TEMPORARY CONCRETE BARRIER (R-53, AND R-126) WHEN USED WITH A TEMPORARY SIGNAL SYSTEM. THE OBJECT MARKERS MUST BE A MINIMUM OF 12 INCHES IN WIDTH AND 36 INCHES IN HEIGHT AND HAVE ORANGE AND WHITE RETROREFLECTIVE SHEETING. THE RETROREFLECTIVE SHEETING MUST HAVE ALTERNATING DIAGONAL ORANGE AND WHITE STRIPES SLOPING DOWNWARD AT AN ANGLE OF 45 DEGREES IN THE DIRECTION VEHICULAR TRAFFIC IS TO PASS.
- TCD6: PLACE LIGHTED ARROW PANELS AS CLOSE TO THE BEGINNING OF TAPERS AS PRACTICAL, BUT NOT IN A MANNER THAT WILL OBSCURE OR CONFUSE APPROACHING MOTORISTS WHEN PHYSICAL LIMITATIONS RESTRICT PLACEMENT. IN CURBED SECTIONS, IF ARROW BOARD CANNOT BE PLACED BEHIND CURB, PLACE ARROW BOARD IN THE CLOSED LANE AS CLOSE TO THE BEGINNING OF TAPER AS POSSIBLE.
- TCD7: ADDITIONAL TYPE III BARRICADES MAY BE REQUIRED TO COMPLETELY CLOSE OFF ROAD FROM EDGE OF PAVEMENT TO EDGE OF PAVEMENT.
- TCD8: WHERE THE SHIFTED SECTION IS SHORTER THAN 600 FEET, A DOUBLE REVERSE CURVE SIGN (W24-1) CAN BE USED INSTEAD OF THE FIRST REVERSE CURVE SIGN, AND THE SECOND REVERSE CURVE SIGN CAN BE OMITTED.
- TCD9: RUMBLE STRIPS ARE TO BE PLACED AS SPECIFIED IN THE CONTRACT. IF NOT SPECIFIED IN THE CONTRACT, PLACE RUMBLE STRIPS AS SHOWN, AND IN ACCORDANCE WITH THE RUMBLE STRIP MANUFACTURER'S RECOMMENDATIONS. AN ARRAY OF RUMBLE STRIPS CONTAINS THREE RUMBLE STRIPS. PLACE THE RUMBLE STRIPS IN THE ARRAY AT A CONSISTENT DISTANCE, BETWEEN 10' AND 20' APART.
- TCD10: SEE THE WORK ZONE SAFETY AND MOBILITY MANUAL, PORTABLE CHANGEABLE MESSAGE SIGN GUIDELINES FOR RECOMMENDED AND CORRECT PCMS MESSAGING. STAGGER PCMS THAT ARE ON OPPOSING SIDES OF THE ROAD 1000 FEET FROM EACH OTHER.

RAMP NOTES

- RMP1: WHEN CONDITIONS ALLOW, E5-1 SIGNS MUST BE REMOVED OR COVERED AND CHANNELIZING DEVICES MUST BE POSITIONED TO ENABLE RAMP TRAFFIC TO DIVERGE IN A FREE MANNER
- RMP2: STOP AND YIELD CONDITIONS SHOULD BE AVOIDED WHENEVER PRACTICAL. WHEN CONDITIONS WARRANT, R1-1 SIGNS MAY BE USED IN PLACE OF R1-2 SIGNS. WHEN R-1 SIGNS ARE USED, W3-1 SIGNS MUST BE USED IN PLACE OF W3-2 SIGNS. CONSIDERATION SHOULD BE GIVEN TO CLOSING THE RAMP TO COMPLETE WORK TO ALLOW AN ADEQUATE MERGE DISTANCE. WORK SHOULD BE EXPEDITED TO AVOID THE STOP AND/OR YIELD CONDITIONS.

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	TRAFFIC TYPICALS NOTE SHEET	DATE: MAY 2022
		NO: 102-GEN-NOTES		SHEET: 1 OF 2
FILE: 102-GEN-NOTES.dgn				

THE FOLLOWING NOTES APPLY IF CALLED FOR ON THE TRAFFIC TYPICAL

SIGNAL NOTES

- SIG1: EXISTING SIGNAL MUST BE EITHER 4-WAY FLASHING RED, BAGGED, OR TURNED OFF.
- SIG2: SIGNAL IS IN OPERATION.
- SIG3: DELINEATE THE WORK ZONE AREA WITH 28 INCH CONES FOR DAYTIME WORK, OR 42 INCH CHANNELIZING DEVICES FOR NIGHTTIME WORK.
- SIG4: THE CONTRACTOR MUST HAVE A DESIGNATED SPOTTER IF THE AERIAL BUCKET TRUCK IS LOCATED OVER ACTIVE TRAVEL LANES.
- SIG5: THE LOWEST POINT OF THE BUCKET MAY NOT TRAVEL BELOW 14 FOOT VERTICAL CLEARANCE. THE CONTRACTOR MUST UTILIZE AN ALTERNATE SET UP, OR PLACE THE INTERSECTION IN A 4 WAY STOP IF THE 14 FOOT VERTICAL CLEARANCE IS COMPROMIZED. USE TRAFFIC REGULATORS TO CONTROL TRAFFIC THROUGH THE INTERSECTION WHEN TRAFFIC IS PLACED IN A 4 WAY STOP.
- SIG6: DELINEATE THE TRUCK WITH CHANNELIZING DEVICES. THE POSITION OF THE TRUCK MAY BE MOVED TO FACILITATE WORK.

MAINTENANCE AND SURVEYING NOTES

- MS1: WHENEVER STOPPING SIGHT DISTANCE EXISTS TO THE REAR, THE SHADOW VEHICLES SHOULD MAINTAIN THE RECOMENDED DISTANCE FROM THE WORK AREA AND PROCEED AT THE SAME SPEED. THE SHADOW VEHICLE SHOULD SLOW DOWN AND TRAVEL AT A FARTHER DISTANCE TO PROVIDE ADEQUATE SIGHT DISTANCE IN ADVANCE OF VERTICAL OR HORIZONTAL CURVES.
- MS2: WORKERS OUTSIDE OF VEHICLES SHOULD WORK WITHIN 150' OF WORK VEHICLES WITH AN ACTIVATED BEACON, BETWEEN THE "BEGIN WORK CONVOY" SIGN AND THE "END WORK CONVOY" SIGN, OR BETWEEN THE "WORK ZONE BEGINS" AND "END ROAD WORK" SIGN.
- MS3: WORK OR SHADOW VEHICLES WITH OR WITHOUT A TMA MAY BE USED TO SEPARATE THE WORK SPACE FROM TRAFFIC. IF USED, THE VEHICLES SHOULD BE PARKED ACCORDING TO THE ROLL AHEAD DISTANCE TABLES.
- MS4: WORK AND SHADOW VEHICLES SHALL BE APPROPRIATELY EQUIPPED WITH AN ACTIVATED AMBER BEACON.
- MS5: WHEN WORKERS ARE OUTSIDE THEIR VEHICLES IN AN EXISTING LANE WHILE A MOBILE OPERATION IS OCCURRING DURING THE NIGHTTIME HOURS, CHANNELIZING DEVICES TO DELINEATE OPEN OR CLOSED LANES AT 50 FT SPACING MUST BE USED. AN EXAMPLE OF AN OPERATION (BUT NOT LIMITED TO) IS THE LAYOUT OF CONCRETE PATCHES.
- MS6: W21-6 AND W20-1 SIGNS MAY BE SUBSTITUTED AS DETERMINED BY THE TYPE OF WORK TAKING PLACE AS PER THE ENGINEER.

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	TRAFFIC TYPICALS NOTE SHEET	DATE: MAY 2022
		NO: 102-GEN-NOTES		SHEET: 2 OF 2
FILE: 102-GEN-NOTES.dgn				

SIGN NUMBER KEY

 E5-1f 48" x 48" 60" x 48"	 E5-2 48" x 36"	 E5-2a 48" x 36"	 E5-3 48" x 36"	 E13-1P VAR x 24"	 E13-1aP 36" x 24"	 G20-1 60" x 24"	 G20-2 48" x 24"
 G20-4 36" x 18"	 I-6a 18" x 18" 24" x 24" 30" x 30"	 M1-1 18" x 18" 24" x 24" 36" x 36" 48" x 48"	 M1-1 22.5" x 18" 30" x 24" 45" x 36" 60" x 48"	 M1-2 18" x 18" 24" x 24" 36" x 36" 48" x 48"	 M1-2 22.5" x 18" 30" x 24" 45" x 36" 60" x 48"	 M1-3 18" x 18" 24" x 24" 36" x 36" 48" x 48"	 M1-3 22.5" x 18" 30" x 24" 45" x 36" 60" x 48"
 M1-4 18" x 18" 24" x 24" 36" x 36" 48" x 48"	 M1-4 22.5" x 18" 30" x 24" 45" x 36" 60" x 48"	 M1-5 18" x 18" 24" x 24" 30" x 30" 36" x 36"	 M1-5a 18" x 18" 24" x 24"	 M1-6 18" x 18" 24" x 24" 36" x 36"	 M1-6 22.5" x 18" 30" x 24" 45" x 36"	 M3-1 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M3-2 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"
 M3-3 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M3-4 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-1 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-1a 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-2 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-3 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-4 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-5 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"
 M4-6 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-7 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-7a 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"	 M4-8 12" x 6" 18" x 9" 24" x 12" 30" x 15"	 M4-8a 24" x 18"	 M4-8b 24" x 12"	 M4-9L 30" x 24" 48" x 36" 60" x 48"	 M4-9R 30" x 24" 48" x 36" 60" x 48"
 M4-9j 30" x 24" 48" x 36" 60" x 48"	 M4-9kL 30" x 30" 48" x 42" 60" x 54"	 M4-9kR 30" x 30" 48" x 42" 60" x 54"	 M4-9mL 30" x 30" 48" x 42" 60" x 54"	 M4-9mR 30" x 30" 48" x 42" 60" x 54"	 M4-9dL 12" x 18"	 M4-9dR 12" x 18"	 M4-9e 12" x 18"
 M4-9f 12" x 18"	 M4-9gL 12" x 18"	 M4-9gR 12" x 18"	 M4-9h 12" x 24"	 M4-9i 12" x 18"	 M4-10L 48" x 18"	 M4-10R 48" x 18"	 M4-11a 12" x 6" 18" x 9" 24" x 12" 30" x 15" 36" x 18"
 M5-1L 12" x 9" 21" x 15" 30" x 21"	 M5-1R 12" x 9" 21" x 15" 30" x 21"	 M5-2L 12" x 9" 21" x 15" 30" x 21"	 M5-2R 12" x 9" 21" x 15" 30" x 21"	 M5-3 12" x 9" 21" x 15" 30" x 21"	 M6-1L 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-1R 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-2L 12" x 9" 18" x 12" 21" x 15" 30" x 21"
 M6-2R 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-3 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-4 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-5 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-6L 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-6R 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-7L 12" x 9" 18" x 12" 21" x 15" 30" x 21"	 M6-7R 12" x 9" 18" x 12" 21" x 15" 30" x 21"

SEE MDOT SHS 13-WORK ZONE FOR SIGN DETAILS



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO: 103-GEN-SIGN

TRAFFIC TYPICALS
SIGN SHEET



















DATE:
JUNE 2021

SHEET:

1 OF 5

FILE: 103-GEN-SIGN.dgn

SIGN NUMBER KEY



SEE MDOT SHS 13-WORK ZONE FOR SIGN DETAILS



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO: 103-GEN-SIGN

TRAFFIC TYPICALS SIGN SHEET

DATE: JUNE 2021
SHEET:

2 OF 5

FILE: 103-GEN-SIGN.dgn

SIGN NUMBER KEY



W1-1L
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-1R
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-2L
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-2R
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-2bL
36" x 36"
48" x 48"



W1-2bR
36" x 36"
48" x 48"



W1-3L
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-3R
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4L
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4R
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4bL
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4bR
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4cL
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W1-4cR
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W24-1L
30" x 30"
36" x 36"
48" x 48"

ALL LANES

W24-1cP
24" x 18"
30" x 24"



W24-1R
30" x 30"
36" x 36"
48" x 48"



W24-1aL
30" x 30"
36" x 36"
48" x 48"




W24-1aR
30" x 30"
36" x 36"
48" x 48"



W24-1bL
30" x 30"
36" x 36"
48" x 48"



W24-1bR
30" x 30"
36" x 36"
48" x 48"



W1-6L
24" x 12"
36" x 18"
48" x 24"
60" x 30"
96" x 48"



W1-6R
24" x 12"
36" x 18"
48" x 24"
60" x 30"
96" x 48"



W1-8L
12" x 18"
18" x 24"
24" x 30"
30" x 36"
36" x 48"




W1-8R
12" x 18"
18" x 24"
24" x 30"
30" x 36"
36" x 48"



W3-1
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W3-2
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W3-3
18" x 18"
30" x 30"
36" x 36"
48" x 48"



W3-4
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W3-4b
30" x 30"
36" x 36"
48" x 48"



W3-5
36" x 36"
48" x 48"



W3-5a
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W3-5b
30" x 30"
36" x 36"
48" x 48"



W4-1L
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-1R
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-2L
30" x 30"
36" x 36"
48" x 48"



W4-2R
30" x 30"
36" x 36"
48" x 48"



W4-3L
30" x 30"
36" x 36"
48" x 48"



W4-3R
30" x 30"
36" x 36"
48" x 48"



W4-5L
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-5R
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-5P
18" x 24"
24" x 30"



W4-6L
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-6R
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W4-7L
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W4-7R
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W5-1
30" x 30"
36" x 36"
48" x 48"



W5-2
18" x 18"
30" x 30"
36" x 36"
48" x 48"



W5-3
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W5-4
30" x 30"
36" x 36"
48" x 48"




W6-1
30" x 30"
36" x 36"
48" x 48"



W6-2
30" x 30"
36" x 36"
48" x 48"



W6-3
30" x 30"
36" x 36"
48" x 48"



W6-4
12" x 18"



W7-1
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W7-1a
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-1
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"

SEE MDOT SHS 13-WORK ZONE FOR SIGN DETAILS



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO:

103-GEN-SIGN

TRAFFIC TYPICALS
SIGN SHEET

DATE:
JUNE 2021

SHEET:

3 OF 5

FILE: 103-GEN-SIGN.dgn

SIGN NUMBER KEY



W8-2
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-3
18" x 18"
30" x 30"
36" x 36"
48" x 48"



W8-4
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-5
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-5P
24" x 18"
30" x 24"
36" x 30"



W8-7
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-8
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-9
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-11
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-12
30" x 30"
36" x 36"
48" x 48"



W8-14
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-15
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-15P
24" x 18"
30" x 24"
36" x 30"



W8-17L
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-17R
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-17P
24" x 18"
30" x 24"
36" x 30"



W8-18
24" x 24"
36" x 36"
48" x 48"



W8-23
24" x 24"
36" x 36"
48" x 48"



W8-24
30" x 30"
36" x 36"
48" x 48"



W8-25
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W8-26
36" x 36"
48" x 48"



W9-1L
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W9-1R
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W9-2L
30" x 30"
36" x 36"
48" x 48"



W9-2R
30" x 30"
36" x 36"
48" x 48"



W9-3C
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W9-3L
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W9-3R
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W9-3a
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W9-3b
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W11-10
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W11-10a
30" x 30"
36" x 36"
48" x 48"



W11-24
36" x 36"
48" x 48"



W12-1
24" x 24"
30" x 30"
36" x 36"
48" x 48"




W12-2
18" x 18"
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W13-1P
18" x 18"
24" x 24"
30" x 30"



W13-2
24" x 30"
36" x 48"
48" x 60"



W13-3
24" x 30"
36" x 48"
48" x 60"




W13-4P
24" x 24"
36" x 36"




W13-6
24" x 42"
36" x 60"
48" x 84"



W13-6a
24" x 42"
36" x 60"
48" x 84"



W13-7
24" x 42"
36" x 60"
48" x 84"



W13-7a
24" x 42"
36" x 60"
48" x 84"



W14-3
36" x 24"
40" x 30"
48" x 36"
64" x 48"



W16-2P
18" x 12"
24" x 18"
30" x 24"



W16-4aP
18" x 12"
24" x 18"
30" x 24"
36" x 30"



W16-12P
24" x 18"



W16-13P
24" x 18"
30" x 24"



W20-1
24" x 24"
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W20-1a
24" x 24"
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W20-1b
24" x 24"
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W20-1c
24" x 24"
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W20-1d
24" x 24"
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W20-2
30" x 30"
36" x 36"
48" x 48"



W20-3
30" x 30"
36" x 36"
48" x 48"



W20-3a
30" x 30"
36" x 36"
48" x 48"

SEE MDOT SHS 13-WORK ZONE FOR SIGN DETAILS



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO:

103-GEN-SIGN

TRAFFIC TYPICALS
SIGN SHEET

DATE:
JUNE 2021

SHEET:

4 OF 5

FILE: 103-GEN-SIGN.dgn

SIGN NUMBER KEY



W20-3b
30" x 30"
36" x 36"
48" x 48"



W20-4
30" x 30"
36" x 36"
48" x 48"



W20-4c
36" x 36"
48" x 48"



W20-5C
30" x 30"
36" x 36"
48" x 48"



W20-5L
30" x 30"
36" x 36"
48" x 48"



W20-5L1
30" x 30"
36" x 36"
48" x 48"



W20-5L2
30" x 30"
36" x 36"
48" x 48"



W20-5R
30" x 30"
36" x 36"
48" x 48"



W20-5R1
30" x 30"
36" x 36"
48" x 48"



W20-5R2
30" x 30"
36" x 36"
48" x 48"



W20-5aL2
30" x 30"
36" x 36"
48" x 48"



W20-5aL3
30" x 30"
36" x 36"
48" x 48"



W20-5aR2
30" x 30"
36" x 36"
48" x 48"




W20-5aR3
30" x 30"
36" x 36"
48" x 48"



W20-7a
30" x 30"
36" x 36"
48" x 48"



W20-8
24" x 18"



W20-9
54" x 48"



W20-10
48" x 24"
66" x 30"



W20-11
12" x 18"



W20-12P
VARIABLE x 12"




W20-13P
VARIABLE x 12"



W20-14L
36" x 36"
48" x 48"



W20-14R
36" x 36"
48" x 48"



W20-14dP
36" x 12"
48" x 12"



W20-14bP
36" x 12"
48" x 12"



W20-15
36" x 36"
48" x 48"



W20-15a
36" x 36"
48" x 48"



W20-15c
48" x 54"



W20-15d
48" x 54"



W20-16
36" x 36"
48" x 48"



W20-17
36" x 36"
48" x 48"



W21-1
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-2
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-2
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-3
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-4
36" x 18"



W21-5
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-5aL
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W21-5aR
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W21-5bL
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W21-5bR
30" x 30"
36" x 36"
48" x 48"
60" x 60"



W21-6
24" x 24"
30" x 30"
36" x 36"
48" x 48"



W21-7
30" x 30"
36" x 36"
48" x 48"



W21-8
30" x 30"
36" x 36"
48" x 48"



W22-1
30" x 30"
36" x 36"
48" x 48"



W22-2
42" x 36"



W22-3
36" x 30"
42" x 36"



W23-1
48" x 24"



W23-2
36" x 36"
48" x 48"

SEE MDOT SHS 13-WORK ZONE FOR SIGN DETAILS



NOT TO SCALE

MAINTAINING TRAFFIC TYPICAL

NO:

103-GEN-SIGN




TRAFFIC TYPICAL
SIGN SHEET

DATE:
JUNE 2021

SHEET:

5 OF 5

FILE: 103-GEN-SIGN.dgn




NOTE:


ENSURE THE ARROW REMAINS CLEARLY LEGIBLE AT DISTANCES FROM 2,500 FEET TO 200 FEET, FROM ALL TRAFFIC LANES AND ROADWAY ENTRANCES. DO NOT PLACE THE LIGHTED ARROW ON A HORIZONTAL OR VERTICAL CURVE THAT MIGHT INTERFERE WITH THIS LEGIBILITY REQUIREMENT.

	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	USE OF ARROW BOARD ON HILL OR CURVE AND WORK ZONE LAYOUT	DATE: MAY 2021
		NO: 104-GEN-AB		SHEET: 1 OF 1


NO SPEED REDUCTION THROUGH WORK ZONE



REDUCED SPEED THROUGH WORK ZONE



REDUCED SPEED THROUGH WORK ZONE USING "WHERE WORKERS PRESENT"










NOT TO SCALE

 MDOT Michigan Department of Transportation	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	SPEED LIMIT LAYOUT	DATE: MAY 2021
		NO: 107-GEN-SPEED		

FILE: 107-GEN-SPEED.dgn


KEY

-  TRAFFIC REGULATOR
-  CHANNELIZING DEVICES
-  LIGHTED ARROW PANEL (CAUTION MODE)
-  TRAFFIC FLOW
-  REFLECTS EXISTING SPEED LIMIT
-  PLACE SIGN AS INDICATED IN NOTE S5
-  PLACE SIGN AS INDICATED IN NOTE S2

STANDARD NOTES


(SEE GEN-NOTES)

GENERAL: G1, G2, G3, G4
 SIGNING: S1, S2, S3, S4, S5
 TRAF REG: TR1, TR2
 DEVICES: TCD1, TCD2, TCD6




	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	LANE CLOSURE UTILIZING TRAFFIC REGULATORS ON A 2-LANE UNDIVIDED ROADWAY	DATE: MAY 2021
		NO: 110-TR-NFW-2L		SHEET: 1 OF 1

FILE: 110-TR-NFW-2L.dgn



- KEY**
- CHANNELIZING DEVICES
 - ⚡ LIGHTED ARROW PANEL (CAUTION MODE)
 - ← TRAFFIC FLOW
 - REFLECTS EXISTING SPEED LIMIT
 - PLACE SIGN AS INDICATED IN NOTE S2

STANDARD NOTES
 (SEE 102-GEN-NOTES)
 GENERAL: G1, G2, G3, G4
 SIGNING: S1, S2, S3, S5
 DEVICES: TCD1, TCD2, TCD6, TCD7



	NOT TO SCALE	MAINTAINING TRAFFIC TYPICAL	SHOULDER CLOSURE ON A 2-LANE, UNDIVIDED ROADWAY	DATE: MAY 2021
		NO: 122-NFW-SHL-(R)		SHEET: 1 OF 1

FILE: 122-NFW-SHL-(R).dgn

SIGN MATERIAL SELECTION TABLE

SIGN SIZE	SIGN MATERIAL TYPE		
	TYPE I	TYPE II	TYPE III
≤ 36" X 36"		X	X
>36" X 36" ≤ 96" TO WIDE		X	
> 96" WIDE TO 144" WIDE	X	X	
> 144" WIDE	X		


TYPE I ALUMINUM EXTRUSION
 TYPE II PLYWOOD
 TYPE III ALUMINUM SHEET

ROUNDING OF CORNERS IS NOT REQUIRED FOR TYPE I OR II SIGNS.
 VERTICAL JOINTS ARE NOT PERMITTED.
 HORIZONTAL JOINTS THROUGH SIGN LEGEND OR SYMBOLS ARE NOT PERMITTED.


POST SIZE REQUIREMENTS TABLE

SIGN AREA (ft ²)	POST TYPE		
	U-CHANNEL STEEL	SQUARE TUBULAR STEEL	WOOD
≤ 9	1 - 3 lb/ft*	1 - 2" 12 or 14 GA*	N/A
9 ≤ 20	2 - 3 lb/ft	2 - 2" 12 or 14 GA	1 - 4" X 6"*
> 20 ≤ 30	N/A	N/A	2 - 4" X 6"
> 30 ≤ 60	N/A	N/A	2 - 6" X 8"
> 60 ≤ 84	N/A	N/A	3 - 6" X 8"


*SIGNS 4 FEET AND GREATER IN WIDTH REQUIRE 2 POSTS.
 SIGNS GREATER THAN 8 FEET IN WIDTH REQUIRE 2 OR 3 WOOD
 POSTS DEPENDING ON AREA OF SIGN.
 A MAXIMUM OF 2 POSTS WITHIN A 7' PATH IS PERMITTED.

 PREPARED BY DESIGN DIVISION	DEPARTMENT DIRECTOR Kirk T. Steudle APPROVED BY: _____ DIRECTOR, BUREAU OF FIELD SERVICES	MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR GROUND DRIVEN SIGN SUPPORTS FOR TEMP SIGNS		
	DRAWN BY: <u>CON/ECH</u> CHECKED BY: <u>AUG</u>	APPROVED BY: _____ DIRECTOR, BUREAU OF DEVELOPMENT	_____ F.H.W.A. APPROVAL	<u>11/2/2017</u> PLAN DATE

2 POST SIGN SUPPORT SPACING



3 POST SIGN SUPPORT SPACING



* FOR ALL 11' AND 12' LONG SIGNS ON 3 WOOD SUPPORTS, SPREAD POSTS SO AS TO HAVE A 8' MIN. TO 9' MAX. DISTANCE BETWEEN OUTSIDE POSTS.

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN


F.H.W.A. APPROVAL

11/2/2017
PLAN DATE


WZD-100-A

SHEET
2 OF 11


NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



RURAL




RURAL WITH ADVISORY SPEED PLATE



URBAN

WALKWAY

(CURBED AREAS OR WHERE WALKWAYS ARE PRESENT)



URBAN

WALKWAY

(CURBED AREAS OR WHERE WALKWAYS ARE PRESENT)

BOTTOM HEIGHT AND OFFSET

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN




F.H.W.A. APPROVAL

11/2/2017
PLAN DATE

WZD-100-A

SHEET
3 OF 11

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



WEIGHT = 3 lbs/ft
 SECT. MOD. X.-X. = 0.31 CUBIC INCHES MIN.


3 lb. U - CHANNEL STEEL POST
 (NO SPLICE)

MOUNT SIGN ON OPEN FACE OF
 U - CHANNEL STEEL POST

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN	F.H.W.A. APPROVAL	11/2/2017 PLAN DATE	WZD-100-A	SHEET 4 OF 11
--	-------------------	------------------------	-----------	------------------

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



UPPER SPLICE

LOWER SPLICE

3 lb. U - CHANNEL STEEL POST
(WITH SPLICE)

MOUNT SIGN ON OPEN FACE OF
UPPER U - CHANNEL STEEL POST

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN


F.H.W.A. APPROVAL

11/2/2017
PLAN DATE

WZD-100-A


SHEET
5 OF 11

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



SECTION A-A

7/16" SPACER
 REQUIRED FOR ALL BOLTS
 O.D. 3/4" MIN., I.D. 3/8" MAX.



NOTES:


1. THE SPACER THICKNESS SHALL BE 1/16" LESS THAN THE GAP BETWEEN THE POST WHEN POSITIONED IN THE UNBOLTED CONFIGURATION.
2. THE EXTERIOR BOLT (CLOSEST TO LAP), SPACER, WASHER, AND NUT SHALL BE INSTALLED IN A PREPUNCHED HOLE 1" TO 2" FROM THE END OF THE LAP.
3. THE INTERIOR BOLT (FARTHEST FROM LAP), SPACER, WASHER, AND NUT SHALL BE INSTALLED IN THE NEXT PREPUNCHED HOLE.
4. THE DRIVEN POST SHALL ALWAYS BE MOUNTED IN FRONT OF THE UPPER POST WITH RESPECT TO THE ADJACENT ONCOMING TRAFFIC, REGARDLESS OF THE DIRECTION THE SIGN IS FACING.
5. THE SPLICE LAP SHALL BE FASTENED BY FOUR-5/16" DIA. GALVANIZED A449 BOLTS (SAE J429 GRADE 5) OR GALVANIZED A325 BOLTS.

3 lb. U - CHANNEL STEEL POST
 (WITH SPLICE)


NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN	F.H.W.A. APPROVAL	11/2/2017 PLAN DATE	WZD-100-A	SHEET 6 OF 11
--	-------------------	------------------------	-----------	------------------

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



SIGN TO 3 lb. POST CONNECTION



NOTES: (FOR STEEL SIGN REINF' PLATE)

1. MATERIAL: 12 GAUGE CARBON STEEL.
2. TOLERANCE ON ALL DIMENSIONS $\pm 0.0625"$
3. FINISH-AFTER STAMPING AND PUNCHING, GALVANIZE ACCORDING TO CURRENT SPECIFICATIONS FOR ZINC (HOT GALVANIZE) COATINGS ON PRODUCTS FABRICATED FROM PLATES OR STRIPS

STEEL SIGN REINFORCING PLATE
REQUIRED FOR TYPE III SIGNS ONLY

3 lb. U - CHANNEL STEEL POST SIGN CONNECTION

NOT TO SCALE


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL


11/2/2017
PLAN DATE

WZD-100-A

SHEET
7 OF 11



**WOOD POST BREAKAWAY HOLES/
 DIRECT EMBEDMENT DETAILS**



**SAW CUT DETAIL
 (MULTIPLE POST INSTALLATIONS)**

WOOD POST DETAILS

NOT TO SCALE


MICHIGAN DEPARTMENT OF TRANSPORTATION
 BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL


11/2/2017
 PLAN DATE

WZD-100-A


SHEET
 8 OF 11



TYPE II AND TYPE III SIGNS



**TOP VIEW
TYPE I SIGN**



TYPE I SIGN - ERECTION DETAILS

WOOD POST CONNECTIONS

NOT TO SCALE


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL

11/2/2017
PLAN DATE

WZD-100-A

SHEET
9 OF 11



SQUARE TUBULAR STEEL POST

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL

11/2/2017
PLAN DATE

WZD-100-A

SHEET
10 OF 11

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.


GENERAL NOTES:

1. A MAXIMUM OF TWO POSTS WITHIN A 7 FOOT PATH IS PERMITTED.
2. ALL SIGN POSTS SHALL COMPLY WITH NCHRP 350.
3. ALL POSTS SHALL BE EMBEDDED A MINIMUM OF 42".
4. BRACING OF POST IS NOT PERMITTED.
5. SIGN SHALL BE LEVEL, AND UPRIGHT FOR THE DURATION OF INSTALLATION.
6. ERECT POSTS SO THE SIGN FACE AND SUPPORTS DO NOT VARY FROM PLUMB BY MORE THAN 3/16" IN 3'. PROVIDE A CENTER-TO-CENTER DISTANCE BETWEEN POSTS WITHIN 2 PERCENT OF PLAN DISTANCE.
7. NO MORE THAN ONE SPLICE PER POST, AS SHOWN, WILL BE PERMITTED.
8. POST TYPES SHALL NOT BE MIXED WITHIN A SIGN SUPPORT INSTALLATION.
9. NO VERTICAL JOINTS ARE PERMITTED IN SIGN. NO HORIZONTAL JOINTS THROUGH SIGN LEGEND OR SYMBOLS ARE PERMITTED IN SIGN
10. REMOVE SIGN POSTS AND/OR POST STUBS IN THEIR ENTIRETY WHEN NO LONGER REQUIRED.
11. ALL LABOR, MATERIALS, AND EQUIPMENT, INCLUDING TEMPORARY SUPPORTS REQUIRED TO INSTALL, MAINTAIN, RELOCATE, AND/OR REMOVE THE TEMPORARY SIGN, INCLUDING SUPPORTS, ARE CONSIDERED TO BE INCLUDED IN THE COST OF THE TEMPORARY SIGN.
12. SAW CUTS IN WOOD POSTS ARE TO BE PARALLEL TO THE BOTTOM OF THE SIGN.
13. POSTS SHALL NOT EXTEND MORE THAN 4" ABOVE TOP OF SIGN.
14. TEMPORARY WOOD SUPPORTS DO NOT REQUIRE PRESERVATIVE TREATMENT.


NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN	F.H.W.A. APPROVAL	11/2/2017 PLAN DATE	WZD-100-A	SHEET 11 OF 11
--	-------------------	------------------------	-----------	-------------------


NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



FRONT ELEVATION SIDE VIEW
PERFORATED SQUARE STEEL TUBE OPTION



FRONT ELEVATION SIDE VIEW
ANGLE IRON OPTION



**BARRICADE RAIL SHEETING OPTIONS
 TYPE III BARRICADES**

Other Type III Barricades meeting current NCHRP crash worthy criteria can be found on the FHWA Safety website at http://safety.fhwa.dot.gov/roadway_dept/road_hardware/wzd.htm

MDOT
 Michigan Department of Transportation

PREPARED BY
 OPERATIONS
 FIELD SERVICES

DRAWN BY: ECH

CHECKED BY: MWB

DEPARTMENT DIRECTOR
 Paul C. Ajegba

APPROVED BY: _____
 DIRECTOR, BUREAU OF FIELD SERVICES

APPROVED BY: _____
 (SPECIAL DETAIL)
 DIRECTOR, BUREAU OF HIGHWAY DEVELOPMENT 48

MICHIGAN DEPARTMENT OF TRANSPORTATION
 BUREAU OF FIELD SERVICES SPECIAL DETAIL FOR


Temporary
 Traffic Control Devices

F.H.W.A. APPROVAL _____

6/16/22
 PLAN DATE

WZD-125-E

SHEET
 1 OF 3



- REFLECTORIZED ORANGE
- REFLECTORIZED WHITE
- NON REFLECTORIZED ORANGE

NOTE:
 DRUMS SHALL HAVE AT LEAST 4 HORIZONTAL REFLECTORIZED STRIPES (2 ORANGE AND 2 WHITE) OF 6" UNIFORM WIDTH, ALTERNATING IN COLOR WITH THE TOPMOST REFLECTORIZED STRIPE BEING ORANGE. NON REFLECTORIZED SPACES BETWEEN THE HORIZONTAL REFLECTORIZED ORANGE AND WHITE STRIPES SHALL BE ORANGE IN COLOR AND EQUAL IN WIDTH.

PLASTIC DRUM

NOTES:

2" PERFORATED SQUARE STEEL TUBES MAY BE USED TO FABRICATE THE HORIZONTAL BASE OF THE TYPE III BARRICADE.

WARNING LIGHTS SHALL BE PLACED ACCORDING TO THE CURRENT STANDARD SPECIFICATIONS FOR CONSTRUCTION AND ALL OTHER PROVISIONS IN THE CONTRACT ON TYPE III BARRICADES.

SEE ROAD STANDARD PLANS R-113-SERIES FOR TEMPORARY CROSSOVERS FOR DIVIDED ROADWAY, AND R-126-SERIES FOR TYPICAL LOCATION AND SPACING OF PLASTIC DRUMS FOR PLACEMENT OF TEMPORARY CONCRETE BARRIER.

SIGNS, BARRICADES, AND PLASTIC DRUMS SHALL BE FACED WITH PRESSURE-SENSITIVE REFLECTIVE SHEETING ACCORDING TO THE CURRENT STANDARD SPECIFICATIONS FOR CONSTRUCTION.

SANDBAGS SHALL BE USED WHEN SUPPLEMENTAL WEIGHTS ARE REQUIRED TO ACHIEVE STABILITY OF THE BARRICADE. THE SANDBAGS SHALL BE PLACED SO THEY WILL NOT COVER OR OBSTRUCT ANY REFLECTIVE PORTION OF THE TRAFFIC CONTROL DEVICE.

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF FIELD SERVICES SPECIAL DETAIL	50	(SPECIAL DETAIL) F.H.W.A. APPROVAL	6/16/22 PLAN DATE	WZD-125-E	SHEET 3 OF 3
--	----	---------------------------------------	----------------------	-----------	-----------------

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
INSURANCE

CSD:LFS

1 of 1

APPR:CM:DBP:11-19-20

Add the following after the first paragraph in subsection 107.10.C.4, of the Standard Specifications for Construction:

In addition to the above insurance requirements, the following agencies must be listed as additional insured:

Midland County
Midland County Road Commission
City of Midland

MIDLAND COUNTY ROAD COMMISSION

SPECIAL PROVISION
FOR
APPROACH, CL I, MODIFIED

MCRC:ROWE

1 of 1

AUGUST 2023

a. Description. This work consists of installing aggregate approaches in accordance with Sections 307 and 902 of the Standard Specifications for Construction except as modified herein.

b. Materials. Provide material in accordance with Sections 307 and 902 of the Standard Specifications for Construction consisting of 100% crushed limestone meeting the gradation requirements for MDOT Dense Graded Aggregate 21AA.

c. Construction. Place Approach, CL I, Modified in accordance with Section 307 of the Standard Specifications for Construction.

d. Measurement and Payment. The completed work, as described, will be measured and paid as specified in Section 307 of the Standard Specifications for Construction at the contract unit price using the following pay item:

Pay Item	Pay Unit
Approach, CL I, Modified	Ton

Approach, CL I, Modified includes all materials, labor, and equipment necessary to complete the work as described.

MIDLAND COUNTY ROAD COMMISSION

SPECIAL PROVISION
FOR
SHLD, CL II, MODIFIED

MCRC:ROWE

1 of 1

AUGUST 2023

a. Description. This work consists of installing aggregate shoulders in accordance with Sections 307 and 902 of the Standard Specifications for Construction except as modified herein.

b. Materials. Provide materials in accordance with Sections 307 and 902 of the Standard Specifications for Construction consisting of 100% crushed limestone meeting gradation requirements for MDOT Dense Graded Aggregate 23A.

c. Construction. Place Shld, Cl II, Modified in accordance with Section 307 of the Standard Specifications for Construction.

d. Measurement and Payment. The completed work, as described, will be measured, and paid as specified in Section 307 of the Standard Specifications for Construction at the contract unit price using the following pay item:

Pay Item	Pay Unit
Shld, Cl II, Modified	Ton

Shld, Cl II, Modified includes all materials, labor, and equipment necessary to complete the work as described.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
HOT MIX ASPHALT PRICES FOR ADJUSTMENTS

MCRC:ROWE

1 of 1

APPR:MAS:NDM:02-16-23

a. Description. This special provision identifies the price(s) that will be used in all payment adjustments for work related to HMA item(s) used in conjunction with this contract.

If the Contractors bid is lower than the established base price any positive adjustment will use the Contractors bid in the calculation for the adjustment. If the Contractors bid is lower than the established base price any negative adjustment will use the base price established herein in the calculation for the adjustment.

If the Contractors bid is higher than the established base price any positive adjustment will use the Contractors bid in the calculation for the adjustment. If the Contractors bid is higher than the established base price any negative adjustment will use the Contractors bid in the calculation for the adjustment.

b. Base Unit Prices. The base price(s) shown below will be used as specified above in calculating adjustments for the pay item(s) listed herein:

Pay Item Code	Pay Item Name	Unit	Base Price
5010025	Hand Patching	Ton	\$113.82
5010061	HMA Approach	Ton	\$115.90
5012037	HMA, 5EML	Ton	\$78.10

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SLOPE RESTORATION, NON-FREEWAY

RSD:NJM

1 of 5

APPR:DMG:JJG:04-05-23

a. Description. This work consists of preparing all lawns and slopes on non-freeway projects designated for slope restoration on the plans or as directed by the Engineer and applying topsoil, fertilizer, seed, mulch with mulch anchor, mulch blanket, high velocity mulch blanket, permanent turf reinforcement mat (TRM), bonded fiber matrix (BFM), or modified mulch blanket to those areas. Ensure turf establishment is in accordance with section 816 and 917 of the Standard Specifications for Construction and Standard Plan R-100 Series, except as modified herein or otherwise directed by the Engineer.

b. Materials. The materials, application rates, and construction methods specified in sections 816 and 917 of the Standard Specifications for Construction apply unless modified by this special provision or otherwise directed by the Engineer. Furnish the following materials on this project:

1. Seeding mixture as called for on the plans.
2. Chemical fertilizer nutrient, Class A.
3. Topsoil. The following percentages of furnished and salvaged topsoil are estimated for this project and provided for informational purposes only.

Topsoil Furnished: 95 percent

Topsoil Salvaged: 5 percent

4. Mulching material.
5. Permanent Turf Reinforcement Mat (TRM) must be 100 percent synthetic and consist of 100 percent ultraviolet (UV) stabilized polyolefin fibers sewn between two layers of black UV stabilized polypropylene netting with polyolefin thread. The TRM must meet the following "minimum average roll value" requirements:

<u>Property</u>	<u>Test Method</u>	<u>Requirement</u>
Mass/Unit Area	ASTM D6566	10 oz/syd
UV Stability @ 1000 hrs	ASTM D4355/D4355M	80 percent
Tensile Strength (MD)	ASTM D6818	165 lbs/ft

Acceptance. Supply a general certification for the permanent TRM from one of the following manufacturers or approved equal:

Recyclex TRM	American Excelsior Co., Arlington, TX	(800) 777-7645
P300 TRM	North American Green, Poseyville, IN	(800) 772-2040
Landlok 450 TRM	Propex, Inc., Chattanooga, TN	(800) 621-1273

Excel PP5-10 TRM	Western Excelsior, Evansville, IN	(866) 540-9810
Vmax P550 TRM	North American Green, Poseyville, IN	(800) 772-2040

6. Bonded Fiber Matrix (BFM). Furnish a product from the list below or an approved equal.

Soil Guard	Mat Inc., Floodwood, MN	(888) 477-3028
HydroStraw BFM	HydroStraw, LLC, Rockford, WA	(800) 545-1755
HydraMax	North American Green, Poseyville, IN	(800) 772-2040
Bindex BFM	American Excelsior Co., Arlington, TX	(800) 777-7645
ProMatrix EFM	Profile Products LLC, Buffalo Grove, IN	(800) 508-8681

If multiple grades of the selected product are available, use the grade appropriate for the application as approved by the Engineer.

Approved equal BFM must consist of long strand, virgin wood fibers (90 percent by weight) bound together by a pre-blended, high-strength polymer adhesive (10 percent by weight). The virgin wood fibers will be thermally refined from clean whole wood chips. Ensure the organic binders are a high-viscosity colloidal polysaccharide tackifier with activating agents to render the resulting matrix insoluble upon drying.

7. Modified Mulch Blanket. Where modified mulch blanket is required, provide an excelsior mulch blanket free of chemical additives. Ensure the netting thread is 100 percent biodegradable and manufactured with non-plastic materials such as jute, sisal, or coir fiber. Degradable, photodegradable, UV-degradable, oxo-degradable, or oxo-biodegradable plastic netting including polypropylene, nylon, polyethylene, and polyester is not an acceptable alternative. All netting materials must have a loose weave design with movable junctions between the machine and cross-machine direction twines that move independently and reduce the potential for wildlife entanglement.

For Slope Restoration, Non-Freeway, Type F, provide a single net modified mulch blanket from the list below or an approved equal.

Premier Straw Single Net Fibrenet	American Excelsior Co.	(800) 777-7645
Curlex NetFree 100% Biodegradable	American Excelsior Co.	(800) 777-7645
ECS-1B Biodegradable Single Straw	East Coast Erosion Control	(800) 582-4005
S1000BD Single Net	Enviroscape ECM, Ltd.	(888) 550-1999
Excel SR-1 All Natural	Western Excelsior Corp.	(866) 540-9810

For Slope Restoration, Non-Freeway, Type G, provide a double net modified mulch blanket from the list below or an approved equal.

Premier Straw Double Net Fibrenet	American Excelsior Co.	(800) 777-7645
Curlex II Fibrenet	American Excelsior Co.	(800) 777-7645
ECX-2B Double Net Biodegradable	East Coast Erosion Control	(800) 582-4005
S2000BD Double Net	Enviroscape ECM, Ltd.	(888) 550-1999
Excel R-2 All Natural	Western Excelsior Corp.	(866) 540-9810

c. Construction. Ensure construction methods are in accordance with subsection 816.03 of the Standard Specifications for Construction. Begin this work as soon as possible after final grading of the areas designated for slope restoration but no later than the maximum time frames

specified in subsection 208.03 of the Standard Specifications for Construction. It may be necessary, as directed by the Engineer, to place materials by hand.

Shape, compact, and ensure all areas to be seeded are weed-free prior to placing topsoil. Place topsoil to the minimum depth as detailed herein and in accordance with the plans and standard specifications to meet proposed finished grade. If the area being restored requires more than the minimum depth of topsoil to meet finished grade, fill this additional depth using topsoil or, at the Contractor's option, embankment. Furnishing and placing this additional material is included in this item of work.

Ensure topsoil is weed and weed seed free and friable prior to placing seed. Remove any stones greater than 1/2-inch in diameter or other debris. Apply seed mixture and fertilizer to prepared soil surface. Incorporate seed into top 1/2-inch of topsoil.

Spread mulch at a rate of two tons per acre. If the Engineer allows dormant seeding spread mulch at a rate of 3 tons per acre. Place mulch anchoring over the mulch at a rate in accordance with subsection 816.03.F of the Standard Specifications for Construction. Place mulch blanket and high-velocity mulch blanket in accordance with subsection 816.03.G of the Standard Specifications for Construction and Standard Plan R-100 Series.

Install areas constructed with the TRM on prepared (seeded) grades as shown on the plans in accordance with the manufacturer's published installation guidelines. Anchor the top edge of the TRM in a minimum six-inch deep trench. Operation of equipment on the slope is prohibited after placement of the TRM. No credit for splices, overlaps, tucks, or wasted material will be made.

Mix the BFM and organic binders thoroughly at a rate of 40 pounds for each 100 gallons of water or as otherwise recommended by the manufacturer. Hydraulically apply the BFM slurry in successive layers, from two or more directions, to fully cover 100 percent of the soil surface. Ensure the minimum application rate is at least 3000 pounds of BFM for each acre or otherwise apply in accordance with the manufacturer's recommendations as appropriate depending on site conditions.

Do not apply BFM on saturated soils or immediately before, during, or after rainfall.

Install modified mulch blanket in accordance with the manufacturer's published guidelines and as directed by the Engineer.

If an area washes out after this work has been properly completed and approved by the Engineer, make the required corrections to prevent future washouts and replace the topsoil, fertilizer, seed, and mulch treatment. This replacement will be paid for as additional work using the applicable pay items.

If an area washes out for reasons attributable to the Contractor's activity or failure to take proper precautions, replacement will be at no cost to the contract.

The Engineer will inspect the seeded turf to ensure it is well-established, in a vigorous growing condition, and contains the species called for in the seeding mixture.

If the seeded turf is not well-established at the end of the first growing season, the Contractor is responsible to re-seed until the turf is well established and approved by the Engineer.

Provide weed control, if weeds are determined by the Engineer to cover more than 10 percent of the total area of slope restoration, in accordance with subsection 816.03.I of the Standard Specifications for Construction. Weed control will be at no additional cost to the contract.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

Pay Item	Pay Unit
Slope Restoration, Non-Freeway, Type __	Square Yard

1. Place **Slope Restoration, Non-Freeway, Type A** in all areas not described in the other types of slope restoration and will be measured by area in square yards in place. **Slope Restoration, Non-Freeway, Type A** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; Mulch; and Mulch Anchoring.

2. Place **Slope Restoration, Non-Freeway, Type B** parallel (8 feet minimum) to the edge of the roadway, in areas that have a 1 on 3 slope and in any ditch with a grade less than 1.5 percent, as shown on the plans, or as directed by the Engineer. **Slope Restoration, Non-Freeway, Type B** will be measured by area in square yards in place. **Slope Restoration, Non-Freeway, Type B** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and Mulch Blanket.

3. Place **Slope Restoration, Non-Freeway, Type C** in areas that have a 1 on 2 slope, any ditch with a grade of 1.5 percent to 3 percent as shown on the plans, or as directed by the Engineer. **Slope Restoration, Non-Freeway, Type C** will be measured by area in square yards in place. **Slope Restoration, Non-Freeway, Type C** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and Mulch Blanket, High Velocity.

4. Place **Slope Restoration, Non-Freeway, Type D** in areas that have a slope steeper than 1 on 2, any ditch with a grade steeper than 3 percent as shown on the plans, or as directed by the Engineer. **Slope Restoration, Non-Freeway, Type D** will be measured by area in square yards in place. **Slope Restoration, Non-Freeway, Type D** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and Turf Reinforcement Mat.

5. Place **Slope Restoration, Non-Freeway, Type E** as shown on the plans, or as directed by the Engineer and measured by area in square yards in place. **Slope Restoration, Non-Freeway, Type E** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and Bonded Fiber Matrix.

6. Place **Slope Restoration, Non-Freeway, Type F** parallel (8 feet minimum) to the edge of the roadway, in areas that have a 1 on 3 slope and in any ditch with a grade less than 1.5 percent. **Slope Restoration, Non-Freeway, Type F** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and single net modified Mulch Blanket.

7. Place **Slope Restoration, Non-Freeway, Type G** in areas that have a 1 on 2 slope and in any ditch with a grade of 1.5 percent to 3 percent. **Slope Restoration, Non-Freeway, Type G** includes installing Topsoil Surface, Furn, LM or Topsoil Surface, Salv, 4 inch; Fertilizer, Chemical Nutrient, Class A; seeding mixture; and double net modified Mulch Blanket.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
NON-FREEWAY CENTERLINE SINUSOIDAL CORRUGATIONS

PMK:MKB

1 of 3

APPR:KPK:LLR:09-28-22

a. Description. Mill 1/2 inch deep sinusoidal corrugations into the centerline of bituminous pavements at the locations shown on the plans. Complete this work in accordance with section 822 of the Standard Specifications for Construction, Standard Plan R-112 Series, and this special provision.

b. Equipment. Use equipment that can continuously mill the required pattern and is able to provide a smooth cut depression with up to 1/8 inch between peaks and valleys within the cut depression. Use cutting head(s) independently suspended from the power unit to allow the cutting tool to self-align with the pavement slope. Equip the cutting tool with guides to provide consistent alignment of each cut in relation to the centerline.

Demonstrate the ability to achieve the desired surface inside each depression without snagging the bituminous surface or spalling the concrete surface prior to production cutting. The use of diamond blades is required for installations on concrete.

c. Construction. Corrugations must be 14 inches ($\pm 1/2$ inch) long parallel to the direction of travel; the width as shown in the included details for the specified corrugation type ($\pm 1/2$ inch) perpendicular to the direction of travel; and have a cross section depth of 1/16 to 1/2 inch ($+1/8$ inch) at the edge of the rumble (and increasing towards the center of the rumble on a crowned section). Ensure the cross slope at the bottom of the depression is level on crowned pavements or in the same direction as the superelevated pavement cross slope. The distance from the corrugation to any transverse joint must be at least 6 inches but less than 12 inches. Mill the corrugations in a continuous, repeating sinusoidal pattern as shown in the included details. Gaps in the corrugations should be made in accordance with what is shown for the corresponding standard corrugations in Standard Plan R-112 Series, with edgeline sinusoidal corrugations following the standards for non-freeway shoulder corrugations.

Remove the grinding spoils or waste from the roadway surface immediately. Do not permit the spoils or waste to be scattered, blown, tracked by traffic, or blown by the wind.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

Pay Item	Pay Unit
Sinusoidal Corrugations, Milled, HMA Centerline.....	Foot

Payment for the above pay items includes disposal of spoils necessary to complete the work as described. The completed work will be measured in feet along the corrugation alignment from the center of the first corrugation placed to the center of the last corrugation placed, excluding sections gapped for intersections, bridges, rail crossings or other locations, as directed by the






Figure 1


Cross-section
Details



Concrete
Centerline



HMA
Centerline



Concrete & HMA
Edgeline

Figure 2

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
MIXING PORTLAND CEMENT CONCRETE

CFS:JFS

1 of 1

APPR:CPM:TEB:12-17-21
FHWA:APPR:12-20-21

Add the following paragraph to subsection 1001.03.E.1 of the Standard Specifications for Construction:

Weigh and batch each material into its respective weighing device within the tolerance from the individual batch weights or quantities documented in the approved JMF as follows:

- a. Cementitious Materials. Provide cementitious materials within -2.0 percent to +5.0 percent of the required weight.
- b. Aggregates. Provide aggregate within ± 3.0 percent of the required weight.
- c. Water. Provide net water to not exceed the required water quantity and the required maximum water/cementitious ratio (w/cm).
- d. Air Entraining Admixtures. Provide the necessary quantity or dosage rate per 100 pounds of cementitious material to achieve the required air content of fresh concrete.
- e. Other Admixtures. Provide water-reducing and other admixtures within ± 3.0 percent of the required quantity.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
**ALKALI SILICA REACTIVITY OF FINE AGGREGATE USED IN PORTLAND
CEMENT CONCRETE**

CFS:CPM

1 of 2

APPR:TES:JFS:05-19-20
FHWA:APPR:05-27-20

a. Description. This special provision sets out the requirements for all fine aggregate used in Portland cement concrete (PCC) mixtures to be tested by an independent testing laboratory and determined to be resistant to the potential for deleterious expansion caused by alkali-silica reactivity (ASR). ASR testing is not required for concrete pavement repairs, temporary concrete pavements, and other items covered by the contract.

Except as explicitly modified by this special provision, all materials, test methods, and PCC mixture requirements of the standard specifications and the contract apply.

b. Definition. ASR is a chemical reaction which occurs over time within concrete between highly alkaline cement paste and reactive forms of silica found in some aggregates. In the presence of moisture, an expansive ASR gel is formed which can exert pressure within the concrete, causing random cracking and premature deterioration of the concrete.

c. Laboratory Requirements. The independent laboratory, including all associated testing equipment and staff performing ASR testing of aggregates, must be proficient in ASR testing in accordance with the applicable test methods and procedures. The laboratory must provide documentation to the Regions that they are qualified and proficient to conduct ASR testing in accordance with the required test procedures.

d. Laboratory Testing Requirements. Perform testing on fine aggregate proposed to be used in any PCC Job Mix Formula (JMF). The Contractor must ensure the testing is conducted in accordance with a designated standard test procedure described herein. Test results must conform to the specified criterion for one of the following standard test methods. The Rounding Method described in *ASTM E29* must be used when reporting expansion test results.

(1) Method 1. *ASTM C1293*. Concrete Prism Test. If the expansion of concrete prisms is not greater than 0.040 percent (rounded to the nearest 0.001 percent) after 1 year, the fine aggregate is considered non-deleterious to ASR and may be used in the JMF.

(2) Method 2. *ASTM C1567*. Mortar Bar Test. If no previous test data are available for the fine aggregate that shows it is resistant to ASR using Method 1, above, replace 25 to 40 percent of the Portland cement in the concrete mixture with a supplementary cementitious material (slag cement or fly ash). A blended cement meeting the requirements of *ASTM C595/C595M* containing the above Portland cement and supplementary cementitious material proportions may also be used.

Demonstrate the ability of the supplementary cementitious material to control the deleterious expansion caused by ASR by molding and testing mortar bars in accordance with the standard

test method described in *ASTM C1567* using the mix proportions and constituent sources for both the aggregates and the cementitious materials that will be used for the project. Make at least three test specimens for each cementitious materials-aggregate combination. If the average of three mortar bars for a given cementitious materials-aggregate combination produces an expansion less than 0.10 percent (rounded to the nearest 0.01 percent) at 14 days of immersion, the JMF associated with that combination will be considered non-deleterious to ASR. If the average expansion is 0.10 percent (rounded to the nearest 0.01 percent) or greater, the JMF associated with that combination will be considered not sufficient to control the deleterious expansion caused by ASR and the JMF will be rejected.

(3) Method 3. *ASTM C1260*. Mortar Bar Test. If the expansion of the mortar bars is less than 0.10 percent (rounded to the nearest 0.01 percent) at 14 days of immersion, the fine aggregate is considered non-deleterious to ASR and may be used in the concrete without the need for ASR mitigation.

The Engineer will not approve the use of the JMF if the expansion exceeds the threshold limits for the respective *ASTM* test method used. The test results and report are valid for 2 years from the completion of testing.

e. Submittals. A current ASR test report for the fine aggregate proposed to be used in the Job Mix Formula (JMF) must accompany each JMF. Ensure the ASR test report is accompanied by a certification stating which test procedure was followed and that all testing was conducted in accordance with the designated standard test procedure.

f. Measurement and Payment. All materials, labor, equipment, and laboratory facilities necessary to complete the work in accordance with this special provision is included in other contract pay items and no additional compensation will be permitted.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
**QUALITY INDEX FOR PORTLAND CEMENT CONCRETE (FOR LOCAL AGENCY
PROJECTS ONLY)**

CFS:CPM

1 of 4

APPR:TES:JFS:05-28-20

FHWA:APPR:06-04-20

a. Description. This special provision establishes pay factor and price adjustments for Portland cement concrete (PCC) based on Quality Assurance (QA) testing of 28-day compressive strength and fresh concrete air content of PCC. Perform all work in accordance with the standard specifications and this special provision.

b. Materials. Mixture requirements will be in accordance with section 1004 of the Standard Specifications for Construction, unless otherwise specified in the contract.

c. Sampling. Sampling will be in accordance with subsections 1003.03.H and 1003.03.L of the Standard Specifications for Construction, except as modified herein. A sample is defined as a representative quantity of concrete taken during production which is used to measure the quality characteristics for the concrete. Compressive strength specimens for each sample consist of two cylinders, either 4-inch by 8-inch or 6-inch by 12-inch. A random number will be generated for each respective subplot. The sampling frequency for a production lot is one QA sample per subplot.

See subsection 1003.03.J in the Standard Specifications for Construction for reduced sampling and testing for small incidental quantities.

d. Quality Index Analysis. The Engineer's QA test results will be used to determine the pay factor (PF) and price adjustment (ADJ). The Contractor QC test results will be not used for PF and ADJ analysis. The Engineer will complete PF and ADJ analysis within 7 working days after completion of all 28-day compressive strength testing for the represented production lot or quantity of concrete. All values of PF and OLPF in these formulas are decimal, not percent. All values of PF and OLPF are rounded to two decimal places.

Table 1: Quality Index Parameter Specification Limits

Quality Characteristic	Specification Limits
Air Content of Fresh Concrete (percent)	5.5 – 8.5
Rejection Limit (percent)	<5.0 or >9.0
Conc. Temp. (deg. F)	45 - 90 at time of placement
Slump (max.) (inch)	See footnotes a through l in Table 1004-1 of the Standard Specifications for Construction
28-day Compressive Strength (psi)	For LSL see Table 2
Rejection Limit - 28-day Compressive Strength	See Table 2

Table 2: Quality Index Parameter Specification Limits for 28-Day Compressive Strength

Parameter	Grade of Concrete						
	3000	3500	3500HP	4000	4000HP	4500	4500HP
Lower Specification Limit (psi)	3000	3500	3500	4000	4000	4500	4500
Rejection Limit for an Individual Strength Sample Test Result (psi)	2500	3000	3000	3500	3500	4000	4000

1. Pay Factor for 28-Day Compressive Strength (PF_s). (not to exceed 1.00)

$$PF_s = (\text{QA Test Strength})/\text{LSL}$$

Where:

QA Test Strength = QA 28-day compressive strength sample test result.

LSL = Lower specification limit (see Table 2).

If the tested strength does not meet the rejection limit specified in Table 2, the Engineer will require additional evaluation as described in section e of this special provision.

2. Pay Factor for Air Content of Fresh Concrete (PF_{ac}). The pay factor for air content of fresh concrete (PF_{ac}) will be in accordance with Table 3.

Table 3: Air Content of Fresh Concrete Pay Factor (PF_{ac})

Air Content of Fresh Concrete (percent)	Pay Factor (PF_{ac})
5.5 – 8.5	1.00
5.0 – 5.4	0.50
Below 5.0	Rejection
8.6 – 9.0	0.75
Above 9.0	Rejection

If the air content of fresh concrete is below 5.0 or above 9.0 percent, the Engineer will elect to do one of the following:

A. Require removal and replacement of the entire quantity of concrete represented by the test with new testing conducted on the replacement concrete and repeat the evaluation procedure.

B. Allow submittal of a corrective action plan for the Engineer's approval. If the Engineer does not approve the plan for corrective action, subsection d.2.A. will be applied. All costs associated with plan submittal and corrective action under this subsection will be borne by the Contractor.

3. Overall Lot Pay Factor (OLPF). Use the following formula to determine the OLPF and ADJ. The OLPF will not exceed 1.00:

$$\text{OLPF} = (0.60 \times \text{PF}_s) + (0.40 \times \text{PF}_{ac})$$

Where:

PF_{ac} = Pay factor for Air Content (see Table 3)

4. Price Adjustment (ADJ). Use the following formula to determine the ADJ.

$$\text{ADJ} = (\text{OLPF} - 1)(\text{Price})$$

5. Price Adjustment for Small Incidental Quantities. Price adjustment for 28-day compressive strength deficiencies will be based on test results for the corresponding weekly QA test specimens and the pay factor (PF_s) calculated in accordance with the formula defined in subsection d.1. The price adjustment is calculated by the following equation:

$$(\text{ADJ}) = (\text{PF}_s - 1)(\text{Price})$$

Where:

ADJ = Price adjustment per pay unit to be applied to the quantity represented by the QA test.

PF_s = Pay Factor for 28-day compressive strength (not to exceed 1.00).

Price = Base price when established for the pay item or the Contractors unit price bid when concrete is included in another pay item without a base price.

e. Evaluation of Rejectable Concrete. The Engineer will require additional evaluation to decide what further action may be warranted. Acceptance for air content of fresh concrete will be based on QA test results reported at the time of concrete placement.

If the Engineer determines that non-destructive testing (NDT) is appropriate, this work will be done by the Contractor in the presence of the Engineer within 45 calendar days of concrete placement. All costs associated with this work will be borne by the Contractor. Ensure complete set of non-destructive tests is conducted (in accordance with the respective standard test method) at a minimum three randomly selected locations. If NDT is used to estimate the in-situ strength, a calibrated relationship between the project job mix formula (JMF) under evaluation and the NDT apparatus must have been established prior to NDT testing in accordance with its respective standard test method.

If the 28-day compressive strength QA test results show that the rejection limit (as specified in Table 2) has not been achieved, the quantity of concrete under evaluation will be rejected and the Engineer will require additional evaluation to decide what further action may be warranted.

Propose an evaluation plan and submit it to the Engineer for approval before proceeding. The results from NDT will be used only to decide what further action is required. This determination will be made by the Engineer, as follows:

1. For Non-structural Concrete. If no test result from non-destructive testing falls below the lower specification limit (LSL) 28-day compressive strength, the represented quantity of

concrete under evaluation will remain in place and a pay factor for 28-day compressive strength (PF_s) of 1.00 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations in accordance with section d of this special provision.

2. For Structural Concrete (including overhead sign foundations). If no test result from non-destructive testing falls below the lower specification limit (LSL), the represented quantity of concrete under evaluation will remain in place and a pay factor for 28-day compressive strength (PF_s) of 0.85 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations will be in accordance with section d of this special provision.

3. If one or more of the non-destructive test results fall below the lower specification limit (LSL) 28-day compressive strength, the Engineer may elect to do one of the following:

A. Require removal and replacement of the entire rejected quantity of concrete, including new initial tests for quality index analysis conducted in accordance with section d of this special provision.

B. Allow the Contractor to submit a plan for corrective action, for the Engineer's approval, to address the disposition of the rejected concrete. If the Engineer does not approve the plan for corrective action, subsection e.3.A of this special provision will be applied. All costs associated with plan submittal and corrective action under this subsection will be borne by the Contractor.

C. Allow the in-situ quantity of concrete under evaluation to remain in place and a pay factor (PF_s) of 0.50 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations will be in accordance with section d of this special provision.

f. Measurement and Payment. If a price adjustment is made for reasons included in this special provision, that adjustment will be made using the base price established for the specific item. If a contract unit price requires adjustment for other reasons not described in this special provision, the adjustments will be made using the original unit price and the adjustments will be cumulative.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
DISSEMINATION OF PUBLIC RELATIONS INFORMATION

CFS:JGG

1 of 1

APPR:LFS:MRB:04-14-21
FHWA:APPR:04-14-21

a. Description. This special provision establishes the requirements for dissemination of any public relations communications and/or products intended for an external audience pertaining to this contract. Dissemination must not be made without prior written approval from the Department's Office of Communications, and then only in accordance with explicit instructions by the Department. This includes the use of the Michigan Department of Transportation (MDOT) logo.

A violation of this provision may be considered a default of contract and the Department may exercise its rights in accordance with subsection 108.11 of the Standard Specifications for Construction.

b. Public Relations Information. Examples of communications and/or products may include, but are not limited to: brochures, flyers, invitations, programs, postings on social media sites or web sites, new or updated video, digital versatile disk (DVD) productions, or video sharing productions, exhibits, presentations, or any other printed materials intended for an external audience.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
VALUE ENGINEERING CHANGE PROPOSAL

COS:MRB

1 of 4

APPR:CJB:JJG:04-30-20
FHWA:APPR:05-06-20

a. Description. A value engineering change proposal (VECP) modifying plans, specifications, or other contract requirements may be submitted for this project if the proposed change results in reduced construction cost, a higher quality product, improved safety, or a shorter contract time. The estimated cost savings must be quantifiable in relation to the contract cost. No work can begin before written authorization. The proposed change must not alter the essential functions or characteristics of the project or significantly delay the completion of the project. A VECP or conceptual VECP will only be considered after project award. Essential functions and characteristics include, but are not limited to, service life, operating costs, ease of maintenance, desired appearance, impact on utilities and right-of-way, mobility and safety of the motorist, bicyclist and pedestrian; safety of all onsite workers (construction, inspection, testing, etc.) in the progress of the work, design standards, and safety standards. This special provision does not restrict the Contractor from proposing improvements to the project that may not result in net cost savings. A conceptual VECP stating the basic concept and approximate cost savings may be submitted for preliminary consideration.

b. Submittal of Conceptual VECP. Submit a conceptual proposal for the preliminary evaluation. Upon review by the Engineer, one of the following actions will be taken:

- Conceptual approval and a request for the Contractor to submit a VECP.
- Request for additional information.
- Denial of the VECP.

Preliminary review of a conceptual proposal reduces the Contractor risk of subsequent denial and does not commit the Department to eventual approval. Submit the following information for each conceptual VECP using the Value Engineering Change Proposal Form (Form # 1962) marked Conceptual VECP.

1. A description of the difference between the existing pay items and the proposed changes, and expected benefits.
2. A set of conceptual plans and a description of proposed changes to the pay items.
3. An estimate of the anticipated cost savings or increase.
4. A date by which the Department must make a decision to avoid delays to the existing contract and obtain the cost savings. Also include information on the amount of time necessary to develop the full proposal and impacts to the progress schedule.
5. If impacting maintenance of traffic provisions, identify proposed changes and impacts to the Special Provision for Maintaining Traffic.

After approval of conceptual VECP, the Contractor must follow section c of this special provision for the final VECP.

c. Submittal of Final VECP. Submit the following information for each VECP using Value Engineering Change Proposal Form (Form # 1962) marked Final VECP.

1. A description of the difference between the existing contract and the proposed change, and the advantages and disadvantages of each, including effects on service life, operating costs, ease of maintenance, desired appearance, impact on utilities and right of way, mobility and safety of the motorist, bicyclist and pedestrian; design standards, and safety standards.

2. A complete set of plans, if necessary, and specifications showing the revisions relative to the original contract. This portion of the submittal must include design notes and construction details. If the proposal has plans, these must be signed and sealed by the Contractor's Professional Engineer licensed in the State of Michigan.

3. All costs and proposed unit prices must be documented by the Contractor and must include a cost comparison summarizing all the items the VECP replaces, reduces, eliminates, adds, or otherwise changes from the original contract on a spreadsheet.

4. A date by which the Department must make a decision to avoid delays to the existing contract and to obtain the proposed cost savings.

5. If impacting maintenance of traffic provisions, identify proposed changes and impacts to the Special Provision for Maintaining Traffic. If the submitted revisions to the maintaining traffic provision are approved and require any corrections, the Contractor is responsible for all additional costs related to corrective measures.

6. A statement detailing the affect the proposal will have on the time for completing the contract and impacts to the critical path and progress schedule.

7. A description of any known uses or testing of the proposed changes and the conditions and the results.

8. If the VECP submittal includes pay items associated with a warranty, include the latest version of the warranty specification.

d. Evaluation. By submitting the VECP, the Contractor agrees not to hold the Department liable for its decision or for any delays to the work attributable to the VECP. Decisions on VECP's are not subject to appeal. Work on the project will continue in accordance with the requirements of the contract until a work order is issued which incorporates the VECP changes. The Department has final authority of the acceptability of a VECP and of the estimated net savings attributable to the adoption of all or any part of the VECP. If, in the judgment of the Engineer, contract prices do not represent a fair measure of the value of work to be performed or to be deleted, the Engineer will use other means to determine the estimated net savings.

The Department may modify a VECP, with the concurrence of the Contractor, in order to make it acceptable. The Contractor's share of the savings will be based on the modified VECP.

If the VECP is accepted, in whole or in part, the written acceptance will be issued by a work order

and followed with a contract modification. The work order and contract modification will include the necessary changes in the plans and specifications and any conditions upon which the approval is based. Acceptance of the VECP will not extend the time of contract completion unless specifically provided for in the work order and contract modification.

A VECP will be evaluated in accordance with the following:

1. The Engineer will determine if a VECP qualifies for consideration and evaluation. The Engineer may deny any VECP that requires excessive time or costs for review, evaluation or investigation. The Engineer may deny any VECP that is not consistent with the Department's design policies and criteria for the project.

2. The Department will not accept a VECP that is similar to a change in the plans or specifications under consideration by the Department for the project at the time the proposal is submitted; nor will the Department accept a proposal based upon, or similar to, standard specifications, general use special provisions or standard drawings adopted by the Department after the advertisement for the contract. The Department reserves the right to make such changes without compensation to the Contractor under the provisions of subsection 103.02 of the Standard Specifications for Construction.

3. The Contractor will have no claim against the Department for additional costs or delays resulting from denial or untimely acceptance of a VECP. These costs include but are not limited to: development costs, loss of anticipated profits, increased material or labor costs, or untimely response.

4. A VECP will be denied if equivalent options are already provided in the contract.

5. A saving resulting solely from the elimination or reduction in quantity of a contract pay item will not be considered as a VECP. A saving resulting from the elimination or reduction in quantity of a pay item specified as part of a VECP may be considered.

6. In calculating the value of cost savings, the Department has the right to disregard the Contract bid prices, if such prices do not represent the value of the work to be performed or to be deleted, and has the right to calculate the savings based on reasonable cost for such work.

7. A VECP cannot be used to alter incentive and disincentive rates and maximum payments on A + B and/or lane rental projects.

8. A VECP will be denied if the design consultant for the contractor is also the design consultant for the Department or other apparent conflicts of interest exist.

9. A VECP may be denied if it was rejected as a Value Engineering alternative during the development phase.

e. Time Frame for VECP Evaluation. The Contractor will be notified of the Department's decision to approve or deny a conceptual or final VECP within 14 calendar days of receipt of the VECP. If a written acceptance has not been received within this time frame, and the date has not been extended by mutual agreement of both parties, the VECP is denied. The Department's decision is final and there is no appeal.

f. Future Use of VECP. The Department reserves the right to use all or any part of a VECP on other contracts without obligation or compensation to the Contractor. If the VECP is accepted, the Department may use or disclose any information necessary to incorporate the VECP on future projects.

g. Payment for Work under the VECP. The Engineer may reject all or any portion of work performed under an approved VECP if results are unsatisfactory. The Engineer will direct the removal of rejected work and construction will proceed under the original contract requirements. There will be no payment for work performed under the proposal, or for its removal.

No work related to a VECP will be performed under force account. Agreed prices must be reached for any new or modified contract pay items related to the VECP before the VECP is approved.

The changes will be incorporated into the Contract by changes in quantities of unit bid items, new agreed unit price items, lump sum or any combination, as appropriate, under the Contract. Unless there is a differing site condition as described in subsection 103.02 of the Standard Specifications for Construction, the Contractor will not receive additional compensation for quantity overruns, design errors, supplemental surveys, geotechnical investigations, additional items or other increases in cost that were not foreseen in the accepted VECP, unless otherwise approved by the Engineer.

The work order and authorization will include the price for performing all affected items of work and the estimated net savings in the cost of performing the work directly attributable to the VECP. VECP payments only involve direct savings or costs. Indirect savings or costs (time, user delay, contract delay, etc) are not included in VECP payment calculations. The calculations of VECP payments are independent from the payments or penalties for contract time related issues. The Contractor will be paid 50 percent of this net savings based on as constructed or plan quantities whichever is in the best interests of the Department. The amount specified in the work order and authorization constitutes full compensation to the Contractor for the VECP and the performance of that work.

$(\text{Cost of Deleted Work}) - (\text{Cost of Added Work}) = \text{Net Savings}$

$\text{Payment} = (\text{Net Savings})/2$

Note: Approved VECP's will be paid using the pay item code "1200000", item description of "Value Engineering" and a unique secondary descriptor differentiating each VECP with the pay unit of "Dollar" for the contract modification.

The Contractor's development costs for the proposed VECP, including all costs associated with design, are not reimbursable.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
CONSTRUCTION DOCUMENT MANAGEMENT

COS:RJC

1 of 3

APPR:JJG:LFS:01-19-23
FHWA:APPR:01-19-23

a. Description. This work consists of meeting MDOT's construction document management (CDM) system requirements. Submit all project documentation for this contract in electronic format and place it in MDOT's CDM system, unless otherwise noted in this special provision. No paper documents, in printed format (faxes, letters, etc.) are permitted except as allowed by this special provision or specifically approved by the Engineer. The Contractor is responsible for keeping all information in the CDM system up to date throughout the execution of the contract.

b. Digitally Encrypted Electronic Signatures. All documents that require Contractor or subcontractor signatures or signed authorizations by the Contractor or subcontractor must be signed using an MDOT issued digitally encrypted electronic signature. The MDOT approved digital signature tool is the OneSpan Sign ID Verification & Acceptance Electronic signature Solution (OneSpan), and OneSpan Sign Mobile Applications. Digital signature software is provided by MDOT for use only on MDOT projects at no cost to the Contractor. Instructions on how to use MDOT's digitally encrypted electronic signature can be obtained at the following website. The website also provides support for users.

www.michigan.gov/MDOT-esign

Scanned signatures, cursive fonts or other non-conforming signatures are not permitted in lieu of digitally encrypted electronic signatures.

The OneSpan signature appliance creates a digital envelope that is distributable for signature by email. OneSpan workflow does not allow changes to be made to the original document after the first signature is placed and uploaded to the document host location. It is the responsibility of the Contractor to provide all individual signatory names and email addresses at the preconstruction meeting to expedite document processing and payment.

Failure to submit documents utilizing OneSpan will result in the documents being rejected by the Engineer and returned to the Contractor. No payment will be made for any affected work items until all required documents are received with validated digitally encrypted signatures.

c. Contractor Access to MDOT's Construction Document Management System (ProjectWise). The Contractor must use MDOT's current CDM system (ProjectWise). ProjectWise access and software is available at no cost to all contractors, suppliers and other vendors associated with the project. User account setup, installation details, and access to ProjectWise may be requested by sending an e-mail request to:

MDOT-ProjectWiseConst@michigan.gov

d. Contractor Authorized Requestors. Designate two authorized requestors at the

preconstruction meeting. The authorized requestors are:

1. The only individuals that can request the Engineer to provide or withdraw ProjectWise access for this contract.
2. Responsible to designate contract roles in ProjectWise (submitter or read only).
3. Responsible for promptly notifying the Engineer of any ProjectWise user access changes for this contract.

e. Training. Additional documentation and training for CDM system processes, details of scheduled classes, and methods for requesting training are available at the following website:

<https://mdotjboss.state.mi.us/SpecProv/projectwisesupport.htm>

f. Technical Issue Resolution. Upon discovery of a ProjectWise access issue immediately notify the Engineer with a copy sent to the following e-mail resource:

MDOT-ProjectWiseConst@michigan.gov.

g. Document Format and Naming Standards. The Engineer may reject documents that are deemed to be unsuitable. This includes documents submitted that are named incorrectly, illegible, unreadable, locked, etc. Re-submit any corrected documents via ProjectWise. Failure to address rejected documents may delay progress payments.

Use the document naming conventions as documented by the Department and maintained on the Department's website:

https://www.michigan.gov/documents/mdot/MDOT_Contractor_Standard_Naming_Conventions_for_Document_Submittals_653665_7.pdf

h. Document Workflows. Electronic review/approval of documents will be accomplished through ProjectWise workflows and e-mail notifications. A workflow is an ordered group of milestones, or states, through which a document passes on its way to completion.

Documents placed in the ProjectWise Contractor In-Box folders will initially have a state of "Pending." Once the Contractor has finalized the document, change the state from "Pending" to "Submitted."

Complete the following actions:

1. Upload all documents into the corresponding Contractor In-Box folder.
 - A. Ensure all documents are named correctly per the document naming conventions.
2. Select the "Change State" option and then select "Next" to submit the document.
3. When the email message appears please send to the Engineer, or their approved representative, providing notification that there are new documents submitted.

The Engineer will review all documents added to these folders and move them to the appropriate

document folder for further review, processing, or records storage.

Furnish paper bills of lading/delivery tickets to the Engineer on the jobsite for any material that is paid based on weight or shipping volume, unless utilizing a Department approved e-ticketing process. Scanning of other manifests, seed tickets, or delivery confirmations will be as directed by the Engineer.

i. File/Document Retention. The electronic files stored in ProjectWise are the official project documentation and will be retained per the Department's document retention schedule.

j. Measurement and Payment. The work included in this special provision will not be paid for separately and is considered to be included in other items of work in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
PREVAILING WAGE AND LABOR COMPLIANCE SYSTEM

COS:AS

1 of 2

APPR:RJC:MRB:03-24-20
FHWA:APPR:03-30-20

a. Description. This work consists of the required use of a prevailing wage and labor compliance (PWLC) system for all prevailing wage documentation as directed by the Engineer. Input all required certified payroll documentation into the PWLC system (LCPtracker) and update this documentation throughout the execution of the contract. Certified payroll information is to be submitted in the PWLC system per the time requirements in the 20SP-107D - Labor Compliance.

b. Contractor Responsibility. Coordinate all electronic document submittals including documentation supplied by other companies (e.g. subcontractors, suppliers, fabricators, etc.) as detailed in this special provision. All companies will directly submit their certified payroll information into the PWLC system.

c. General Requirements. Submit all certified payroll information as required in this special provision and the 20SP-107D - Labor Compliance. Provide employee zip codes as part of the certified payroll submission. This information will be redacted from any certified payroll reports to protect worker anonymity. Zip code information will be anonymized and used for federal, state, and legislative prevailing wage and labor reporting.

All data entry will be submitted through the following program and website:

Program: LCPtracker

Login Website: <http://www.lcptracker.net>

General Information website: www.lcptracker.com

A tutorial for this system can be found though the website provided.

d. Condition of Payment. Post all documents electronically into the PWLC system. Electronic posting and submittal of documents is a condition of payment for this contract. Documents submitted in any other manner, unless required otherwise in this special provision or directed by the Engineer, will not be accepted and will delay payment.

e. Digitally Encrypted Electronic Signatures. Ensure all documents that require signature authorizations are signed using a digitally encrypted electronic signature. Further information regarding how to obtain a digital signature can be found at the following website:

www.michigan.gov/mdot-esign

f. Contractor Preparation for Tracking Software:

1. Information about LCPtracker is available to the Contractor and other project companies (e.g. subcontractors, suppliers, etc.) at the following website:

www.lcptracker.com.

2. Access to the PWLC system is provided at no cost to the Contractor. The project office will setup the project in LCPtracker and assign the Contractor. The Contractor will setup other project companies to submit certified payrolls and prevailing wage/labor compliance documents. Once setup in the system the Contractor and other project companies may access the software at the following website:

www.lcptracker.net

3. Use Internet Explorer to access the PWLC system. The Department has tested and will support Internet Explorer versions 8, 9, 10 and 11.

g. Document Format. The Engineer reserves the right to electronically reject documents that are deemed to be unsuitable. This may include documents submitted that are illegible or unreadable or contain inappropriate information. The submitting company must re-submit the corrected documents into the PWLC system. Failure to do so will be considered noncompliance and may delay progress payments.

h. Training. LCPtracker offers biweekly contractor training sessions, user support manuals, quick start guides, e-Training videos, and a software support staff available Monday thru Friday 8 a.m. to 8 p.m. EST accessible through the online interface.

i. File/Document Retention. The electronic files submitted in the PWLC system are the official contract documents and must follow all Department document retention schedules.

j. Technical Issue Resolution. Upon discovery of an LCPtracker issue immediately notify the Engineer with a copy sent to the following e-mail resource:

MDOT-LCPtracker@Michigan.gov

k. Measurement and Payment. The work included in this special provision will not be paid for separately and is considered to be included in other items of work in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SOURCE OF STEEL AND IRON (BUY AMERICA)

CFS:JGG

1 of 2

APPR:LLR:AG:10-13-22
FHWA:APPR:10-16-22

Delete subsection 105.10, on page 1-60 of the Standard Specifications for Construction, in its entirety and replace with the following:

105.10. Source of Steel and Iron. Provide steel and iron materials and products for permanent incorporation into the work that were produced only in the United States per Title 23 of the CFR Section 635.410, Buy America Requirements.

All steel and iron products and manufacturing processes of the steel and iron material in a product, including but not limited to the following steps; smelting, melting, rolling, extruding, machining, bending, grinding, drilling, welding, galvanizing, and coating, must occur within the United States. Provide manufacturer and/or fabricator certifications that all steel and iron products and manufacturing processes of the steel and iron material are compliant with Buy America requirements unless noted otherwise in this special provision.

Examples of products that are subject to Buy America coverage include, but are not limited to, the following:

- A. Steel or iron products used in pavements, bridges, tunnels, or other structures, which include, but are not limited to, the following: fabricated structural steel, hot or cold rolled structural steel shapes, reinforcing steel, piling, high strength bolts, anchor bolts, dowel bars, permanently incorporated sheet piling, bridge bearings, cable wire/strand, pre-stressing/post-tensioning wire, motor/machinery brakes and other equipment for moveable structures.
- B. Guardrail, guardrail posts, end sections, terminals, cable guardrail.
- C. Steel fencing material, fence posts.
- D. Steel or iron pipe, conduit, grates, manhole covers, risers.
- E. Mast arms, poles, standards, trusses, supporting structural members for signs, luminaires, or traffic control systems.
- F. Steel or iron components of precast concrete products, such as reinforcing steel, wire mesh and pre-stressing or post-tensioning strands or cables.
- G. Left-in-place structural steel formwork, falsework, and earth retaining system elements.

Manufactured products that are predominantly (90 percent or greater) steel and/or iron

must comply with this special provision.

Provide step certification for all steel and iron related pay items, materials, products, and components as specified on the Department website. The Department will maintain a list of these pay items, materials, products, and/or components on the following website.

<https://www.michigan.gov/mdot/-/media/Project/Websites/MDOT/Business/Construction/Standard-Specifications-Construction/CFS-Reference/BuyAmericaStepCertPayItems.pdf>

Step certification is defined as the certification by the respective manufacturer or fabricator for their specific process (step) that the product, material, or component was fabricated, manufactured, and/or processed in the United States. The step certification documentation for these pre-defined pay items, materials, products, and/or components is to be submitted to the Engineer in a package covering each step prior to delivery or concurrent with material delivery on-site. Approved certification is required prior to incorporation of the materials into the project.

The above requirements do not preclude a minimal use of foreign steel and iron, provided the total invoice cost of foreign steel and iron permanently incorporated into the project does not exceed 0.1 percent of the total contract amount or \$2,500 whichever is greater. The Department defines the total invoice cost as the total value of the foreign steel and iron materials delivered to the project. The Department defines the total contract amount to be the original contract amount at time of award plus any cost increases during construction with the exception of incentive payments.

MDOT/Consultant fabrication facility inspectors are not responsible for approving the incorporation of foreign steel/iron prior to fabrication. It is the responsibility of the fabricator to notify and coordinate with the Contractor for all potential inclusion of foreign steel/iron in fabricated products.

For each item subject to meeting Buy America requirements, that doesn't fully meet Buy America requirements, the following documentation must be provided by the Contractor to verify the foreign steel value. This documentation is to be placed in the project files to ensure that the threshold is not exceeded:

- Pay Item,
- Description of associated foreign steel/iron material, product, or component,
- Cost of associated foreign steel/iron material, product, or component, and
- Cumulative list of all non-compliant Buy America items with the total dollar amount.

The minimal use of foreign steel/iron under the minimal usage amount will be approved by the Engineer. The use of foreign steel/iron under the minimal usage amount does not need to be approved by the FHWA. This amount is not considered a waiver to the Buy America requirements. The Contractor must ensure that the minimal usage amount is not exceeded.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SOURCE OF CONSTRUCTION MATERIALS

CFS:JJG

1 of 1

APPR:LLR:KAS:10-13-22
FHWA:APPR:10-16-22

Add Subsection 105.11 after subsection 105.10, on page 1-60 of the Standard Specifications for Construction:

105.11. Source of Construction Materials. Provide construction materials for permanent incorporation into the work that were produced in the United States.

The final manufacturing process for construction materials and the immediately preceding manufacturing stage for construction materials must occur within the United States.

Construction materials include an article, material, or supply that is or consists primarily of the following:

- A. Non-ferrous metals;
- B. Plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables);
- C. Glass (including optic glass);
- D. Lumber; or
- E. Drywall.

Items that consist of two or more of the listed construction materials that have been combined together through a manufacturing process, and items that include at least one of the listed materials combined with a material that is not listed (including steel/iron) through a manufacturing process are treated as manufactured products, rather than as construction materials.

Manufactured products that are predominantly (90 percent or greater) steel and/or iron must comply with 20SP-105A - Source of Steel and Iron (Buy America) and are not subject to this special provision. All other manufactured products are exempt from this special provision.

Cement and cementitious materials; asphalt cements; aggregates such as stone, sand, or gravel; and aggregate binding agents or additives are not subject to this special provision.

Provide documented certification that the applicable construction materials are produced and/or manufactured in the United States per this special provision.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
E-VERIFY

CSD:LFS

1 of 1

APPR:JJG:RJC:04-10-20
FHWA:APPR:04-13-20

a. Description. E-Verify is an Internet-based system that allows an employer, using information reported on an employee's Form I-9, Employment Eligibility Verification, to determine the eligibility of that employee to work in the United States. There is no charge to employers to use E-Verify. The E-Verify system is operated by the Department of Homeland Security (DHS) in partnership with the Social Security Administration. E-Verify is available in Spanish.

The State of Michigan is requiring all Contractors, and Subcontractors, to verify that new employees are legally present and authorized to work in the United States, using the E-Verify System.

Information on registration for and use of the E-Verify program can be obtained via the Internet at the DHS Web site: <http://www.dhs.gov/E-Verify>.

It is the responsibility of the Contractor to include this specification in all tiers of subcontracts.

Verification of the Contractors' use of E-verify will be a part of the random review of subcontract information performed by the Department.

The required use of the E-Verify system will not be paid for separately as part of the contract but is considered included in the costs for other pay items in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
LABOR COMPLIANCE

COS:AS

1 of 3

APPR:JJG:RJC:03-24-20
FHWA:APPR:03-30-20

a. Description. Ensure all levels of contracting (prime, sub, sub-sub, etc.) comply with all labor compliance requirements in this contract. The Contractor is responsible for subcontractors and lower tier subcontractor labor compliance. Job site poster requirements apply to state and federally funded projects. All Contractors must insert this special provision in each subcontract and further require its inclusion in lower tier subcontracts for federal prevailing wage projects.

b. Requirements.

1. Jobsite Posters. All jobsite posters and employment notices required by State and Federal regulations and the contract are to be posted on the jobsite in a conspicuous area prior to the commencement of work. Ensure jobsite postings are accessible at all times.

2. Federal Prevailing Wage Projects. The Davis-Bacon Related Acts apply to all Contractors, and subcontractors (all tiers) performing work on federally funded or assisted construction contracts where the total construction contract price is in excess of \$2,000. Contractors and subcontractors are required to comply with *29 Code of Federal Regulations Parts 1, 3, and 5*.

The Contractor must advise subcontractors of the requirement to pay the prevailing wage rates prior to commencement of work and that all employees must cooperate during wage rate interviews.

A. Certified Payroll Submittal Requirements. Contractors (all tiers) must submit their certified payrolls to the prime Contractor. The submitted payrolls must accurately and completely include all information required on MDOT Form CP-347, Certified Payroll. The required weekly payroll information may be submitted on a contractor generated form but must contain all information required on Form CP-347. The first certified payroll is to be received by the Engineer within 3 weeks from the week ending in which work is performed. The 3 week period is to allow for the processing and review of the certified payrolls by the prime Contractor. The review must ensure the certified payroll is complete and contains all information required on Form CP-347. Form CP-347 is available on the MDOT forms webpage. Certified payroll information must meet the requirements of this special provision unless the contract requires payroll to be submitted through the prevailing wage and labor compliance (PWLC) system. Payroll submitted via the PWLC system must be entered into the system, certified, and approved by the prime Contractor to be considered received by the Department.

Labor compliance issues must be resolved within 60 calendar days of receiving the Departments first documented notice. The 60-day requirement may be extended based on documented mutual agreement between the Department and the Contractor.

(1) Fringe Benefit Statements. Contractors making payments or incurring cost to provide bona fide benefits must submit an hourly breakdown of fringe benefits paid each worker, or work classification where applicable, that must accompany the first certified payroll where fringe benefits are credited towards the prevailing wage. The Contractor must update these documents as necessary to ensure they are current throughout the working life of the contract. Failure to submit or maintain the required fringe benefit statement will constitute a payroll deficiency.

(2) Delinquent Payroll. Certified payrolls not submitted per subsection b.2.A of this special provision will be considered delinquent.

(3) Deficient Payroll. Certified payrolls that are found to be incomplete, inaccurate, or inconsistent with other project records are considered deficient.

(4) Non-compliance Damages. A Contractor found to be in non-compliance with the requirements of this special provision will be assessed non-compliance damages listed in Table 1, proportional to the value of their work on the contract (including subcontract, purchase order (P.O.) or invoice amount).

Table 1: Schedule of Non-Compliance Damages

Contract/Subcontract/P.O./Invoice Amount (a)	Non-compliance damages per calendar day
\$0 to 49,999	\$200
50,000 to 99,999	400
100,000 to 499,999	600
500,000 to 999,999	900
1,000,000 to 1,999,999	1,300
2,000,000 to 4,999,999	1,550
5,000,000 to 9,999,999	2,650
10,000,000 and above	3,000
Trucker	\$200
a. "Contract" amount if offending contractor is the prime contractor. "Subcontract/P.O./Invoice" amount if offending contractor is a subcontractor/vendor.	

B. Record Keeping. Maintain payrolls and basic records relating thereto (i.e. employee names, occupation, hours worked, W2, canceled checks, bank statements, etc.) by all levels of contractors during the course of work and retain for a 3-year period from the date of final estimate for all employees working on the site of work. Make these records available for inspection, copying, or transcription by the Department or its representative.

C. Short Duration Projects. The following modifications apply if the project is less than 75 calendar days in duration.

(1) Submittal Requirements. On short duration projects the first certified payroll is to be received by the Engineer within 2 weeks from the week ending in which work is

performed. The 2-week period is to allow for the processing and review of the certified payrolls by the Contractor. The 2-week period allows the first estimate to be paid assuming the Contractor will submit certified payrolls in a timely manner. Ensure subsequent certified payroll submissions are made weekly. Payroll submissions failing to meet the above requirements will be considered delinquent.

Labor compliance issues are to be resolved within 30 days after receiving the Department's first documented notice. The 30-day requirement may be extended based on documented mutual agreement between the Department and the Contractor.

- c. Materials.** None specified.
- d. Construction.** None specified.
- e. Measurement and Payment.** Payment for compliance with this special provision will not be made separately. Payment will be considered as part of all other pay items in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
EASTERN MASSASAUGA RATTLESNAKE

ENV:JDG

1 of 2

APPR:DWS:MJO:03-18-20
FHWA:APPR:03-18-20

a. Description. Contractors are advised that the project area has a known population of the Eastern Massasauga Rattlesnake or is within its known range. This species is listed as federally threatened under the U. S. Endangered Species Act of 1973 (Act). Taking (killing, harming, or disturbing in any manner) of Eastern Massasauga Rattlesnake without a federal permit from the U.S. Fish and Wildlife Service is prohibited under federal law. The Act provides enforcement authority to the U.S. Fish and Wildlife Service and contains severe penalties for violations. The Contractor is liable to the Department for any penalties imposed for violations to the Act due to the Contractor's failure to comply with this special provision. Fines and penalties range up to \$50,000 and 1 year in prison. Violation of any requirement listed below can lead to an immediate work stoppage in Eastern Massasauga Rattlesnake habitat. FHWA is required under federal law to assure MDOT is compliant with these provisions or risk losing federal funding for the project. This special provision addresses education, notification and intentional take requirements of the Contractor and their workers to protect the Eastern Massasauga Rattlesnake as required under the Act.

b. Materials. None specified.

c. Construction. Adhere to the following requirements:

1. Prior to construction, all Contractor staff working onsite must read the attached fact sheet (2 of 2). The purpose of the fact sheet is to provide the Contractor easy identification tips, notification that a venomous snake may be onsite, and raise awareness regarding its protected legal status.


2. Immediately report any possible Eastern Massasauga Rattlesnake sightings to the Engineer.

3. Intentionally 'take' is prohibited.

d. Measurement and Payment. All costs associated with complying with this special provision will not be paid for separately but will be considered to have been included in other pay items in the contract.

Eastern Massasauga Rattlesnake (*Sistrurus catenatus*)

Protected as federally threatened



Photos courtesy of the Michigan Department of Natural Resources and Michigan State University

This species is suspected to occur at or near the work site. Please have staff read the following information.

What Does an Eastern Massasauga Rattlesnake Look Like?

The eastern massasauga rattlesnake is a thick-bodied and short venomous snake. Adults typically measure 18 to 30 inches long. This species is gray to grayish-brown with dark blotches bordered by white down the middle of its back. The head is thick and triangular and has an obvious neck. Like many venomous snakes, the massasauga has vertical slitted pupils like a cat and heat sensing pits below the eyes. A rattle is present on the tail that "buzzes" as a warning signal, although they may strike without rattling. This is the only rattlesnake in Michigan.

Where Does It Live?

These snakes prefer wet areas, such as marshes, wet prairies, wet woods, and along rivers and lakes. They also use adjacent upland during parts of the year, especially in the summer. They hibernate during the winter in crayfish burrows, under logs and tree roots, and in small mammal burrows.

What Should You Do If You See a Massasauga Rattlesnake?

Massasaugas are shy and try to avoid confrontation but that does not mean they won't bite to protect themselves. Never try to handle, chase, provoke, or threaten a snake. When in potential snake habitat, wear thick boots that cover your ankles, long pants, and do not reach into thickets or under logs. If you hear the buzzing of a rattle stay calm and back away from the sound slowly. The snake will leave if you give it space.

If an eastern massasauga rattlesnake is found at a Michigan Department of Transportation (MDOT) project, the construction engineer should be contacted immediately. The construction engineer should then contact the MDOT ecologist at 517-335-2633.

How is the Massasauga Protected Under the Law?

The eastern massasauga rattlesnake is protected under federal law by the Endangered Species Act. This status prohibits harming or harassing the species along with policies to protect the species habitat.

For More Information:

60-Second Snakes: The Eastern Massasauga Rattlesnake
www.youtube.com/watch?v=-PFnXe_e02w

Photos

http://animaldiversity.org/site/accounts/pictures/Sistrurus_catenatus.html

General Information

<http://mnfi.anr.msu.edu/emr>

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
UTILIZING DISADVANTAGED BUSINESS ENTERPRISE TRUCKING VENDORS

CSD:LFS

1 of 1

APPR:JJG:MRB:11-18-21
FHWA:APPR:11-18-21

After the fifth paragraph of subsection 108.01, Subcontracting of Contract Work, of the Standard Specifications for Construction add the following:

The Contractor must provide a subcontract to the Engineer for each DBE trucking company on the project. The subcontract must be provided in advance of the work or no later than 15 calendar days of the DBE trucking company commencing work on the project.

The use of DBE trucking vendors does not apply to the limitation of subcontracting.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
PROMPT PAYMENT

CFS:JGG

1 of 4

APPR:LFS:DBP:03-27-20
FHWA:APPR:03-30-20

Add the following subsection to section 109, of the Standard Specifications for Construction:

109.08 Prompt Payment.

A. Definitions.

Lower-tier subcontract. An agreement between a subcontractor of any tier and any individual or legal entity to perform a part of the subcontract work.

Lower-tier subcontractor. The individual or legal entity that performs part of the subcontract work through a lower-tier subcontract with a subcontractor.

Supplier. The individual or legal entity that agrees to provide materials or services to the prime Contractor, a subcontractor, or a lower-tier subcontractor for the performance of their contract work.

Sworn Statement. A written verification under oath reflecting all persons or entities, which have furnished labor, equipment, services or materials to a subcontractor or lower-tier subcontractor for performance of work on the project. The written verification includes union fringe benefit funds, original contract amount, current amount due, amounts paid to date and balance to finish the work for each person or entity.

Waiver of Lien. A written release and waiver of any claim or right to payment for payments actually received for labor, equipment, services or materials furnished for performance of work on the project.

The sworn statement and waiver of lien documents are used by the prime Contractor and its subcontractors for verifying payments made to lower-tier subcontractors/suppliers and are not to be submitted to the Engineer unless requested as an aid in determining an alleged prompt payment violation. These documents can be found at the following website.

<https://mdotjboss.state.mi.us/webforms/WebFormsHome.htm>

B. Progress Payments. For the first payment, or for a one time payment, the prime Contractor agrees to pay each subcontractor for the work associated with their subcontract no later than 10 calendar days from the date the prime Contractor receives payment from the Department.

For the second and subsequent payments, the prime Contractor agrees to pay each

subcontractor for the work associated with their subcontract no later than 10 calendar days from the date the prime Contractor receives payment from the Department.

The Contractor is required to provide payment information for previous payments made to all first tier subcontractors and all DBE companies (sub-subcontractors, suppliers, truckers, etc.) at any tier before the Engineer will release the third and subsequent estimates. For all subsequent progress pay estimates if 1) the Engineer payment does not include any first tier subcontractors or any DBE company payments at any tier, and 2) the previously submitted payment reporting information remains unchanged, then payment reporting in the system is not required. Reporting is required when the prime Contractor makes payments to any first tier subcontractors and any DBE companies at any tier. The payment information is provided through submittal of the information via the 2124A reporting system (MERS). System information can be found at the following web link.

<https://milogin.michigan.gov/eai/login/authenticate?URL=/>

The prime Contractor must bring any concerns about the satisfactory completion of subcontractor or lower-tier subcontractor work items, to the Engineer's attention as soon as the concern is discovered. If the work meets the requirements of satisfactory completion and the prime Contractor has been paid for that work, the Engineer must determine whether:

1. The prime Contractor has demonstrated a valid reason for withholding payment from the subcontractor or supplier, or
2. The subcontractor has demonstrated a valid reason for withholding payment from the lower-tier subcontractor or supplier.

If the Engineer determines the reason for withholding payment is valid, the Engineer will process a negative estimate to withdraw the amount involved in the complaint. If payment has not been made for the work related to the complaint, the Engineer will not include those items of work on an estimate until the issue has been resolved.

The prime Contractor remains responsible to make prompt payments on this project to their subcontractors and suppliers except as noted in subsection 109.08.D of this special provision, even if the prime Contractor is in violation of other contractual obligations and the Department is withholding payment from the prime Contractor for those violations.

The prime Contractor must include language in all subcontracts that the Department prohibits prime Contractors from holding retainage from subcontractors. All provisions of this prompt payment subsection apply to all subcontracts, lower-tier subcontracts, and supplier agreements and must be included in each subcontract for the contract, including all lower-tier subcontracts and agreements.

This prompt payment provision is a requirement of 49 CFR 26.29 and does not confer third-party beneficiary rights or other direct rights to a subcontractor against the Department. This provision applies to both DBE and non-DBE subcontractors/suppliers at all tiers.

C. Satisfactory Completion. Progress and partial payments for contract work are issued based on the satisfactory completion of work. Satisfactory completion, for purposes of this prompt payment provision, is defined as:

1. Upon preliminary review, the Engineer finds the work completed in accordance with the contract, plans, and specifications; and,
2. Required documentation, including material certifications, payrolls, submission of 2124A, etc., has been received and reviewed and found to be acceptable by the Engineer; and,
3. Required subcontractor sworn statements and waivers of lien have been provided to the prime Contractor. The prime Contractor must provide notice to the Engineer if sworn statements and waivers of lien have not been received for completed work.

The Engineer will determine if the work meets the standards of satisfactory completion.

D. Less than full payment release. The Engineer may give written approval to:

1. Delay or postpone payment from the time frames specified herein,
2. Process partial payment from the prime Contractor to a subcontractor or supplier,
3. Process partial payment from a subcontractor to a lower-tier subcontractor or supplier.

The unpaid portion will be held by the Department.

The parties may initiate whatever dispute resolution procedure is specified in their agreement or is available under Michigan law. If dispute resolution or litigation is selected, the actions by both parties must proceed in a timely manner. The result of the dispute resolution proceeding or litigation must be provided to the Engineer promptly upon the conclusion of the proceeding. The Engineer will release the disputed payment being held by the Department in accordance with the outcome of the proceedings.

E. Non-Payment Claims. The prime Contractor, subcontractor, lower-tier subcontractor or supplier must notify the alleged offending party in writing of any prompt payment violations within 30 calendar days of the date the payment was to be received. Copies of the notifications must be provided to the Engineer and the prime Contractor (only if the prime Contractor is not the offending party).

The alleged offending party must respond in writing to the claimant within 10 calendar days of receipt of the notification of failure to meet prompt payment provisions. Provide copies of the response to the Engineer, the prime Contractor (only if the prime Contractor is not the offending party), and the Engineer of Construction Field Services. The prime Contractor, subcontractor, or supplier must also provide the required sworn statements and waivers of lien from the affected subcontractor or supplier to the Engineer within 10 days of receipt of the notification. The Department will consider the failure of the alleged offending party to respond to the notification from the claimant as an admission of the prompt pay violation which may result in sanctions.

The Engineer will review the written notice and response and will verify in writing if there is a valid prompt pay violation.

Independent of all procedures and requirements in this special provision the non-payment claimant has the additional option of submitting a lien claim to the MDOT Contract Services Division. MDOT will notify the project surety of the non-payment issue. It is the responsibility

of the surety to ensure that all legitimately due payments are made. The submission of a lien claim will not nullify or affect any other requirements, obligations or procedures in this special provision.

F. **Remedies.** When the Engineer verifies a prompt payment violation, the prime Contractor within 5 days must propose one or a combination of any of the following actions items for review and approval by the Engineer:

1. Issue payment to the subcontractor.
2. Issue payments to a subcontractor in the form of joint checks to the subcontractor and the subcontractor's lower-tier subcontractors and/or suppliers.
3. Issue payment directly to the subcontractor's lower-tier subcontractors or suppliers.
4. Request a negative estimate to withdraw the amount confirmed in the prompt payment violation.

If the prime Contractor fails to submit a timely remedy request or obtain an approved course of action within the 5 day time period, the Engineer will direct a course of action or issue a negative estimate to withdraw the amount confirmed in the prompt payment violation.

If the prime Contractor fails to fulfill the approved or directed course of action the Engineer will impose sanctions until such time as the approved or directed course of action is completed.

Any payments to a subcontractor's lower-tier subcontractor or supplier will be issued in the amounts reflected upon the subcontractor's sworn statements or in amounts independently verified by the Engineer as being due the subcontractor's lower-tier subcontractors and suppliers for work completed. Payments to a lower-tier subcontractor or supplier will be considered payment to the subcontractor directly so that payment for the same work cannot be claimed.

Any other use of joint checks must follow current Department procedures.

G. **Sanctions.** Failure to comply with any of the prompt payment requirements by the prime Contractor, subcontractor, lower-tier subcontractor, or supplier may result in sanctions against the offending party. These sanctions may include, but are not limited to: withholding of estimates on projects where prompt payment violations are confirmed; reduction or removal of prequalification; and/or suspension of bidding privileges.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
**NON-COMPLIANCE WITH SOIL EROSION AND SEDIMENTATION CONTROL
REQUIREMENTS**

COS:DMG

1 of 2

APPR:TWK:HLZ:02-26-20
FHWA:APPR:03-02-20

a. Description. This special provision establishes negative adjustments related to the failure to properly install and maintain soil erosion and sedimentation control (SESC) measures and the conditions under which these adjustments will be determined and applied. Nothing in this special provision modifies section 107 of the Standard Specifications for Construction.

Delays to the project as a result of the Contractor conducting corrective actions for SESC measures do not constitute a valid reason for an extension of time.

Ensure deficiencies with SESC measures are corrected in the time frame stated herein. For those deficiencies not corrected within the stated time frame, the Engineer will make a negative adjustment to the contract as stated herein.

b. Materials. None specified.

c. Construction. Install all temporary erosion control measures identified on the plans and as directed by the Engineer for an impacted area of the project prior to the start of any earth disturbance including, but not limited to, clearing, grading and excavation in that area. The Engineer will inspect these measures every 7 days and within 24 hours after a precipitation event that results in a discharge from the site. Deficiencies will be documented on the National Pollutant Discharge Elimination System and SESC Inspection Report (MDOT Form 1126).

If at any time during the project, including the time during the seasonal suspension, the Engineer documents deficient SESC measures, the Engineer will provide written notification with instructions for corrective action to the Contractor. The time frame for completion of these corrective actions will be specified in the notification and will be discussed with the Contractor as necessary.

Deficiencies are defined as one or more of the following:

1. Failure to install or construct SESC measures shown on the plans or as directed by the Engineer;
2. Failure to maintain the measures;
3. Failure to conduct earth change activities in a manner consistent with all applicable environmental permit requirements;
4. Failure to comply with the area limitations or the time limitations stated in subsections 208.03.A and 208.03.B, respectively, of the Standard Specifications for Construction.

SESC deficiencies are either emergency or non-emergency and the time frame for corrective action is determined accordingly. Sediment leaving the right-of-way or entering a drainage structure, waters of the state, or loss of support of the roadbed impacting public safety constitutes an emergency and corrective actions must be completed within 24 hours of notification, including weekends or holidays regardless of whether the Contractor is working or not. Non-emergency deficiencies must be corrected within 5 calendar days of notification.

For those emergency corrective actions not completed within 24 hours of notification, the Contractor will be assessed \$100.00 per hour for every hour the deficiency remains uncorrected after the initial 24 hours of notification. For those non-emergency corrective actions not completed within 5 calendar days, the Contractor will be assessed \$500.00 per day for every day, or part thereof, the deficiency remains uncorrected after the initial 5 days of notification.

If it is not practicable to complete the non-emergency corrective actions within 5 calendar days, the Contractor must document the reasons and propose a corrective action plan to the Engineer within 5 days of notification. The corrective action plan must contain the Contractor's course of action and a time frame for completion. If the reasons and the corrective action plan are acceptable to the Engineer, the Contractor will be allowed to proceed with the plan as proposed without incurring a negative adjustment. If the approved corrective action plan is not completed as proposed, the Contractor will be assessed \$1000.00 per calendar day for every day, or part thereof, the deficiency remains uncorrected after the time frame is exceeded in the approved corrective action plan.

Correct, in the timeframe stated herein, all other emergency or non-emergency SESC deficiencies documented anywhere else on the project during completion of the approved corrective action plan.

d. Measurement and Payment. The Engineer will make the necessary monetary adjustment to the contract amount based on the length of time the Contractor allows the deficiencies to remain uncorrected after the time allowance stated herein and as described to cover any costs incurred by the Department as a result of SESC violations.

All costs associated with corrective actions required due to the Contractor's failure to properly install or maintain SESC measures on this project will be borne by the Contractor.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SAMPLING ASPHALT BINDER ON LOCAL AGENCY PROJECTS

CFS:TRC

1 of 1

APPR:JWB:KPK:02-19-20
FHWA:APPR:02-19-20

a. Description. This work consists of the Contractor taking samples of the asphalt binder and delivering the samples to the Engineer prior to incorporation into the hot mix asphalt mixture.

b. Materials. For informational purposes, original samples of asphalt binder will be taken by the Contractor and delivered to the Engineer prior to incorporation into the mixture. The frequency of sampling will be determined by the Engineer.

The Contractor must certify in writing that the materials used in the HMA mixture are from the same source as the materials used in developing the HMA mixture design and the bond coat is from an approved supplier as stated in the *Material Quality Assurance Procedures Manual*.

c. Construction. None specified.

d. Measurement and Payment. The cost of obtaining and delivering the samples to the Engineer will be included in the hot mix asphalt (HMA) pay items in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
RECYCLED HOT MIX ASPHALT MIXTURE ON LOCAL AGENCY PROJECTS

CFS:KPK

1 of 2

APPR:JWB:CJB:02-26-20
FHWA:APPR:03-02-20

Add the following subsection to subsection 501.02.A.2 of the Standard Specifications for Construction.

- c. **Reclaimed Asphalt Pavement (RAP) and Binder Grade Selection.** The method for determining the binder grade in HMA mixtures incorporating RAP is divided into three categories designated Tier 1, Tier 2 and Tier 3. Each tier has a range of percentages that represent the contribution of the RAP binder toward the total binder, by weight. The tiers identified below apply to HMA mixtures with the following exception: Superpave mixture types EML, EML High Stress, EMH, EMH High Stress, and EH, EH High Stress used as leveling or top course must be limited to a maximum of 27 percent RAP binder by weight of the total binder in the mixture.

Recycled materials may be used as a substitute for a portion of the new materials required to produce HMA mixtures in accordance with contract.

- **Tier 1 (0% to 17% RAP binder by weight of the total binder in the mixture).** No binder grade adjustment is made to compensate for the stiffness of the asphalt binder in RAP.
- **Tier 2 (18% to 27% RAP binder by weight of the total binder in the mixture).** For all mixtures no binder grade change will occur in Tier 2 for all shoulder and temporary road mixtures.

Ensure the required asphalt binder grade is at least one grade lower for the low temperature than the design binder grade required for the specified project mixture type. Lowering the high temperature of the binder one grade is optional. For example, if the design binder grade for the mixture type is PG 58-22, the required grade for the binder in the HMA mixture containing RAP would be a PG 52-28 or a PG 58-28.

For Marshall Mixes, no binder grade change will be required when Average Daily Traffic (ADT) is above 7000 or Commercial Average Daily Traffic (CADT) is above 700. No binder grade change will occur for EL mixtures used as leveling or top course.

The asphalt binder grade can also be selected using a blending chart for high and low temperatures. Supply the blending chart and the RAP test data used in determining the binder selection according to *AASHTO M323*.

- **Tier 3 ($\geq 28\%$ RAP binder by weight of the total binder in the mixture).** The binder grade for the asphalt binder is selected using a blending chart for high and low temperatures per *AASHTO M323*. Supply the blending chart and the RAP test data

used in determining the binder selection.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
ACCEPTANCE OF HOT MIX ASPHALT MIXTURE ON LOCAL AGENCY PROJECTS

CFS:KPK

1 of 7

APPR:CJB:JWB:02-26-20
FHWA:APPR:03-13-20

a. Description. This special provision provides sampling and testing requirements for local agency projects using the roller method and the nuclear density gauge testing. Provide the hot mix asphalt (HMA) mixture in accordance with the requirements of the standard specifications, except where modified herein.

b. Materials. Provide aggregates, mineral filler (if required), and asphalt binder to produce a mixture proportioned within the master gradation limits shown in the contract, and meeting the uniformity tolerance limits in Table 1.

Table 1: Uniformity Tolerance Limits for HMA Mixtures

Parameter		Top and Leveling Course		Base Course		
Number	Description	Range 1 (a)	Range 2	Range 1 (a)	Range 2	
1	% Binder Content	-0.30 to +0.40	±0.50	-0.30 to +0.40	±0.50	
2	% Passing	# 8 and Larger Sieves	±5.0	±8.0	±7.0	±9.0
		# 30 Sieve	±4.0	±6.0	±6.0	±9.0
		# 200 Sieve	±1.0	±2.0	±2.0	±3.0
3	Crushed Particle Content (b)	Below 10%	Below 15%	Below 10%	Below 15%	
a. This range allows for normal mixture and testing variations. The mixture must be proportioned to test as closely as possible to the Job-Mix-Formula (JMF).						
b. Deviation from JMF.						

Parameter number 2 as shown in Table 1 is aggregate gradation. Each sieve will be evaluated on one of the three gradation tolerance categories. If more than one sieve is exceeding Range 1 or Range 2 tolerances, only the one with the largest exceedance will be counted as the gradation parameter.

The master gradation should be maintained throughout production; however, price adjustments will be based on Table 1. Aggregates which are to be used in plant-mixed HMA mixtures must not contain topsoil, clay, or loam.

c. Construction. Submit a Mix Design and a JMF to the Engineer. Do not begin production and placement of the HMA until receipt of the Engineer's approval of the JMF. Maintain the binder content, aggregate gradation, and the crushed particle content of the HMA mixture within the Range 1 uniformity tolerance limits in Table 1. For mixtures meeting the definition of top or leveling course, field regress air void content to 3.5 percent with liquid asphalt cement unless specified otherwise on HMA application estimate. For mixtures meeting the definition of base course, field regress air void content to 3.0 percent with liquid asphalt cement unless specified

otherwise on HMA application estimate.

Ensure all persons performing Quality Control (QC) and Quality Assurance (QA) HMA field sampling are "Local Agency HMA Sampling Qualified" samplers. At the pre-production or preconstruction meeting, the Engineer will determine the method of sampling to be used. Ensure all sampling is done in accordance with *MTM 313 (Sampling HMA Paving Mixtures)* or *MTM 324 (Sampling HMA Paving Mixtures Behind the Paver)*. Samples are to be taken from separate hauling loads.

For production/mainline type paving, obtain a minimum of two samples, each being 20,000 grams, each day of production, for each mix type. The Engineer will sample and maintain possession of the sample. Sampling from the paver hopper is prohibited. Each sample will be divided into two 10,000 gram parts with one part being for initial testing and the other part being held for possible dispute resolution testing. Obtain a minimum of three samples for each mix type regardless of the number of days of production.

Obtain samples that are representative of the day's paving. Sample collection is to be spaced throughout the planned tonnage. One sample will be obtained in the first half of the tonnage and the second sample will be obtained in the second half of the tonnage. If planned paving is reduced or suspended, when paving resumes, the remaining sampling must be representative of the original intended sampling timing.

Ensure all persons performing testing are Bit Level One certified or Bit QA/QC Technician certified.

Ensure daily test samples are obtained, except, if the first test results show that the HMA mixture is in specification, the Engineer has the option of not testing additional samples from that day.

At the pre-production or preconstruction meeting, the Engineer and Contractor will collectively determine the test method for measuring asphalt content (AC) using *MTM 319 (Determination of Asphalt Content from Asphalt Paving Mixtures by the Ignition Method)* or *MTM 325 (Quantitative Extraction of Bitumen from HMA Paving Mixtures)*. Back calculation will not be allowed for determining asphalt content.

Ensure all labs performing local agency acceptance testing are qualified labs per the *HMA Production Manual and the Michigan Quality Assurance Procedures Manual*, and participate in the MDOT round robin process, or they must be *AASHTO Materials Reference Laboratory (AMRL)* accredited for *AASHTO T30* or *T27*, and *AASHTO T164* or *T308*. Ensure on non-National Highway System (NHS) routes, Contractor labs are made available, and may be used, but they must be qualified labs as previously stated. Contractor labs may not be used on NHS routes. Material acceptance testing will be completed by the Engineer within 14 calendar days, except holidays and Sundays, for projects with less than 5,000 tons (plan quantity) of HMA and within 7 calendar days, except holidays and Sundays, for projects with 5,000 tons (plan quantity) or more of HMA, after the Engineer has obtained the samples. QA test results will be provided to the Contractor after the Engineer receives the QC test results. Failure on the part of the Engineer or the laboratory to provide QA test results within the specified time frame does not relieve the Contractor of their responsibility to provide an asphalt mix within specifications.

The correlation procedure for ignition oven will be established as follows. Asphalt binder content based on ignition method from *MTM 319*. Gradation (*ASTM D5444*) and Crushed particle content (*MTM 117*) based on aggregate from *MTM 319*. The incineration temperature will be established

at the pre-production meeting. The Contractor will provide a laboratory mixture sample to the acceptance laboratory to establish the correction factor for each mix. Ensure this sample is provided to the Engineer a minimum of 14 calendar days prior to production.

For production/mainline type paving, the mixture may be accepted by visual inspection up to a quantity of 500 tons per mixture type, per project (not per day). For non-production type paving defined as driveways, approaches, and patching, visual inspection may be allowed regardless of the tonnage.

The mixture will be considered out-of-specification, as determined by the acceptance tests, if for any one mixture, two consecutive tests per parameter, (for Parameter 2, two consecutive aggregate gradations on one sieve) are outside Range 1 or Range 2 tolerance limits. If a parameter is outside of Range 1 tolerance limits and the second consecutive test shows that the parameter is outside of Range 2, then it will be considered to be a Range 1 out-of-specification. Consecutive refers to the production order and not necessarily the testing order. Out-of-specification mixtures are subject to a price adjustment per the Measurement and Payment section of this special provision.

Contractor operations will be suspended when the mixture is determined to be out-of-specification, but contract time will continue to run. The Engineer may issue a Notice of Non-Compliance with Contract Requirements (Form 1165), if the Contractor has not suspended operations and taken corrective action. Submit a revised JMF or proposed alterations to the plant and/or materials to achieve the JMF to the Engineer. Effects on the Aggregate Wear Index (AWI) and mix design properties will be taken into consideration. Production and placement cannot resume until receipt of the Engineer's approval to proceed.

Pavement in-place density will be measured using one of two approved methods. The method used for measuring in-place density will be agreed upon at a pre-production or preconstruction meeting.

Pavement in-place density tests will be completed by the Engineer during paving operations and prior to traffic staging changes. Pavement in-place density acceptance testing will be completed by the Engineer prior to paving of subsequent lifts and being open to traffic.

Option 1 - Direct Density Method

Use of a nuclear density gauge requires measuring the pavement density using the Gmm from the JMF for the density control target. The required in-place density of the HMA mixture must be 92.0 to 98.0 percent of the density control target. Nuclear density testing and frequency will be in accordance with the *MDOT Density Testing and Inspection Manual*.

Option 2 - Roller Method

The Engineer may use the Roller Method with a nuclear or non-nuclear density gauge to document achieving optimal density as discussed below.

Use of the density gauge requires establishing a rolling pattern that will achieve the required in-place density. The Engineer will measure pavement density with a density gauge using the Gmm from the JMF for the density control target.

Use of the Roller Method requires developing and establishing density frequency curves, and

meeting the requirements of Table 2. A density frequency curve is defined as the measurement and documentation of each pass of the finished roller until the in-place density results indicate a decrease in value. The previous recording will be deemed the optimal density. The Contractor is responsible for establishing and documenting an initial or QC rolling pattern that achieves the optimal in-place density. When the density frequency curve is used, the Engineer will run and document the density frequency curve for each half day of production to determine the number of passes to achieve the maximum density. Table 5, located at the end of this special provision, can be used as an aid in developing the density frequency curve. The Engineer will perform density tests using an approved nuclear or non-nuclear gauge per the manufacturer's recommended procedures.

Table 2: Minimum Number of Rollers Recommended Based on Placement Rate

Average Laydown Rate, Square Yards per Hour	Number of Rollers Required (a)	
	Compaction	Finish
Less than 600	1	1 (b)
601 - 1200	1	1
1201 - 2400	2	1
2401 - 3600	3	1
3601 and More	4	1

a. Number of rollers may increase based on density frequency curve.
b. The compaction roller may be used as the finish roller also.

After placement, roll the HMA mixture as soon after placement as the roller is able to bear without undue displacement or cracking. Start rolling longitudinally at the sides of the lanes and proceed toward the center of the pavement, overlapping on successive trips by at least half the width of the drum. Ensure each required roller is 8 tons minimum in weight unless otherwise approved by the Engineer.

Ensure the initial breakdown roller is capable of vibratory compaction and is a maximum of 500 feet behind the paving operations. The maximum allowable speed of each roller is 3 miles per hour (mph) or 4.5 feet per second. Ensure all compaction rollers complete a minimum of two complete rolling cycles prior to the mat temperature cooling to 180 degrees Fahrenheit (F). Continue finish rolling until all roller marks are eliminated and no further compaction is possible. The Engineer will verify and document that the roller pattern has been adhered to. The Engineer can stop production when the roller pattern is not adhered to.

d. Measurement and Payment. The completed work, as described, will be measured and paid for using applicable pay items as described in subsection 501.04 of the Standard Specifications for Construction, or the contract, except as modified below.

Base Price. Price established by the Department to be used in calculating incentives and adjustments to pay items and shown in the contract.

If acceptance tests, as described in section c. of this special provision, show that a Table 1 mixture parameter exceeds the Range 1, but not the Range 2, tolerance limits, that mixture parameter will be subject to a 10 percent penalty. The 10 percent penalty will be assessed based on the acceptance tests only unless the Contractor requests that the 10,000 gram sample part retained for possible dispute resolution testing be tested. The Contractor has 4 calendar days from receipt

of the acceptance test results to notify the Engineer, in writing, that dispute resolution testing is requested. The Contractor's QC test results for the corresponding QA test results must result in an overall payment greater than QA test results otherwise the QA tests will not be allowed to be disputed. The Engineer has 4 calendar days to send the dispute resolution sample to the lab once dispute resolution testing is requested. The dispute resolution sample will be sent to an independent lab selected by the Local Agency, and the resultant dispute test results will be used to determine the penalty per parameter, if any. Ensure the independent lab is a MDOT QA/QC qualified lab or an AMRL HMA qualified lab. The independent lab must not have conflicts of interest with the Contractor or Local Agency. If the dispute testing results show that the mixture parameter is out-of-specification, the Contractor will pay for the cost of the dispute resolution testing and the contract base price for the material will be adjusted, based on all test result parameters from the dispute tests, as shown in Table 3 and Table 4. If the dispute test results do not confirm the mixture parameter is out-of-specification, then the Local Agency will pay for the cost of the dispute resolution testing and no price adjustment is required.

If acceptance tests, as described in section c. of this special provision, show that a Table 1 mixture parameter exceeds the Range 2 tolerance limits, the 10,000 gram sample part retained for possible dispute resolution testing will be sent, within 4 calendar days, to the MDOT Central Laboratory for further testing. The MDOT Central Laboratory's test results will be used to determine the penalty per mixture parameter, if any. If the MDOT Central Laboratory's results do not confirm the mixture parameter is out-of-specification, then no price adjustment is required. If the MDOT Central Laboratory's results show that the mixture is out-of-specification and the Engineer approves leaving the out-of-specification mixture in place, the contract base price for the material will be adjusted, based on all parameters, as shown in Table 3 and Table 4.

In the case that the Contractor disputes the results of the test of the second sample obtained for a particular day of production, the test turn-around time frames given would apply to the second test and there would be no time frame on the first test.

The laboratory (MDOT Central Laboratory or independent lab) will complete all Dispute Resolution testing and return test results to the Engineer, who will provide them to the Contractor, within 13 calendar days upon receiving the Dispute Resolution samples.

In all cases, when penalties are assessed, the penalty applies to each parameter, up to two parameters, that is out of specification.

Table 3: Penalty Per Parameter

Mixture Parameter out-of-Specification per Acceptance Tests	Mixture Parameter out-of-Specification per Dispute Resolution Test Lab	Price Adjustment per Parameter
No	N/A	None
Yes	No	None
	Yes	Outside Range 1 but not Range 2: decrease by 10% Outside Range 2: decrease by 25%

The quantity of material receiving a price adjustment is defined as the material produced from the time the first out-of-specification sample was taken until the time the sample leading to the first in-specification test was taken.

Each parameter of Table 1 is evaluated with the total price adjustment applied to the contract base price based on a sum of the two parameter penalties resulting in the highest total price adjustment as per Table 4. For example, if three parameters are out-of-specification, with two parameters outside Range 1 of Table 1 tolerance limits, but within Range 2 of Table 1 limits and one parameter outside of Range 2 of Table 1 tolerance limits and the Engineer approves leaving the mixture in place, the total price adjustment for that quantity of material is 35 percent.

Table 4: Calculating Total Price Adjustment

Cost Adjustment as a Sum of the Two Highest Parameter Penalties		
Number of Parameters Out-of-Specification	Range(s) Outside of Tolerance Limits of Table 1 per Parameter	Total Price Adjustment
One	Range 1	10%
	Range 2	25%
Two	Range 1 and Range 1	20%
	Range 1 and Range 2	35%
	Range 2 and Range 2	50%
Three	Range 1, Range 1 and Range 1	20%
	Range 1, Range 1 and Range 2	35%
	Range 1, Range 2 and Range 2	50%
	Range 2, Range 2 and Range 2	50%

Table 5: Density Frequency Curve Development

Tested by: _____ Date/Time: _____

Route/Location:		Air Temp:
Control Section/Job Number:		Weather:
Mix Type:	Tonnage:	Gauge:
Producer:	Depth:	Gmm:

Roller #1 Type:

Pass No.	Density	Temperature	Comments
1			
2			
3			
4			
5			
6			
7			
8			
Optimum			

Roller #2 Type:

Pass No.	Density	Temperature	Comments
1			
2			
3			
4			
5			
6			
7			
8			
Optimum			

Roller #3 Type:

Pass No.	Density	Temperature	Comments
1			
2			
3			
4			
5			
6			
7			
8			
Optimum			

Summary: _____

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
**CONCRETE CURB, AND GUTTER, WITH ___ FIBER REINFORCED POLYMER,
DETAIL ___**

STR:MJC

1 of 4

APPR:JAB:JFS:02-19-21

FHWA:APPR:03-05-21

a. Description. This work consists of constructing concrete curb, gutter, and dividers, using glass fiber reinforced polymer (GFRP), or basalt fiber reinforced polymer (BFRP) reinforcement in accordance with section 802 of the Standard Specifications for Construction, and as modified on the plans and this special provision. At the Contractors option the number 3 size GFRP or BFRP may be substituted for longitudinal epoxy coated number 4 conventional steel reinforcement shown on Standard Plans R-27 Series, R-30 Series, R-31 Series, and R-33 Series. Do not use GRFP or BFRP for lane ties, or any other transverse reinforcement.

b. Materials. Provide materials in accordance with subsection 802.02 of the Standard Specifications for Construction except as modified by this special provision. Furnish GFRP or BFRP reinforcement that meet the following material specifications and requirements. Provide GFRP or BFRP reinforcement in accordance with the details shown on the plans. Do not mix reinforcement types.

1. **Fibers.** Use fibers in the form of unidirectional rovings of given size and weight with fiber sizing and coupling agents that are compatible with the resin system used to impregnate them. The GFRP reinforcement must contain 70 percent, minimum, by weight of glass fiber in accordance with *ASTM D7957/D7957M, Standard Specification for Solid Round Glass Fiber Reinforced Polymer Bars for Concrete Reinforcement*. The BFRP reinforcement must contain 70 percent, minimum, by weight of basalt fiber in accordance with *ASTM D258, Standard Test Method for Ignition Loss of Cured Reinforced Resins*.

2. **Resin Matrix.** Use commercial grades of epoxy, polyurethanes, or vinyl ester resins. Thermo-set resin systems or their blending are permitted. Ensure the base polymer in the resin system does not contain any polyester. Blending of vinyl ester and epoxy resins is permitted. Ensure the glass transition temperature (T_g) of the resin is not less than 212 degrees Fahrenheit in accordance with the Differential Scanning Calorimetry (DSC) method described in *ASTM E1356, Standard Test Method for Assignment of the Glass Transition Temperatures by Differential Scanning Calorimetry*.

3. **Fillers.** Inorganic fillers and secondary fibers may be used, but their quantity must not exceed 20 percent by weight of the base polymer resin specified. Commercial grade additives and process aids such as release agents, low profile shrink additives, initiators, promoters, hardeners, catalysts, pigments, fire-retardants, and ultraviolet inhibitors are permitted and depend on the process method. If used, limit shrink additives to less than 20 percent by weight of the polymer resin.

4. **Mechanical Properties.** Furnish GFRP or BFRP bars with the following minimum requirements:

A. Tensile Strength. The minimum tensile strength of #3 GFRP or BFRP reinforcement is 140 kips per square inch (ksi). Test in accordance with *ASTM D7205/D7205M, Standard Test Method for Tensile Properties of Fiber Reinforced Polymer Matrix Composite Bars*.

B. Tensile Modulus. Ensure the nominal tensile modulus of elasticity averages 6,000 (ksi) in accordance with *ASTM D7205/D7205M*.

C. Transverse Shear. Ensure the minimum transverse shear strength is not less than 20 ksi, as tested in accordance with *ASTM D7617/D7617M, Standard Test Method for Transverse Shear Strength of Fiber-Reinforced Polymer Matrix Composite Bars*.

D. Moisture Absorption. Test moisture absorption in accordance with *ASTM D570, Standard test Method for Water Absorption of Plastic*. The maximum value of this test must follow ACI recommendations and be less than 1.0 percent.

E. Bond Strength. The bond strength for all bars must follow ACI recommendations of *ACI 440.6-08*, 1.4 ksi. The manufacturer must report the test method used for testing bond strength. Follow *ACI 440.3R test method B3* or a method approved by the Engineer.

F. Ultimate Tensile Strain. Ensure the ultimate tensile strain is at least 1.1 percent.

G. Provide GFRP as manufactured by:

(1) Neuvokas Corp., *GatorBar*, 3206 Number 6 Road, PO Box 220, Ahmeek, MI 49901, Ph. (906) 934-2661.

(2) Owens Corning Infrastructure Solutions, LLC, *PinkBar*, 123 S 9th street, Seward, NE, 68434. Ph. (402) 202-5379.

(3) Approved equal.

H. Provide BFRP as manufactured by:

(1) Neuvokas Corp., *GatorBar*, 3206 Number 6 Road, PO Box 220, Ahmeek, MI 49901, Ph. (906) 934-2661.

(2) Raw Energy Materials Corp., 1190 South Dixie Hwy Southeast, Pompano Beach, FL 33060, Ph: 954-803-9206, Alt: 954-270-9000.

(3) Approved equal.

c. Acceptance. Provide the Engineer a General Certification from the GFRP or BFRP reinforcement manufacturer stating the materials furnished meet the specifications as described herein.

The Department will sample three 4 foot in length quality assurance samples for informational purposes, of GFRP or BFRP bar at the beginning of each project.

d. Construction. Construct the concrete curb and gutter in accordance with the standard

specifications, except as modified by the details on the plans and this special provision. Ensure GFRP or BFRP reinforcement bars are uniform in diameter/size and free of defects. Defects include exposed fibers, cracks, kinks, and surface pitting. Slight discoloration is not cause for rejection.

1. Field Fabrication. Provide GFRP or BFRP reinforcement in accordance with the details shown on the plans. Field fabrication, except for tying and cutting, and gradual bending in accordance with manufacturer’s recommendations, of GFRP or BFRP reinforcement is prohibited. The minimum bending radius for GFRP or BFRP reinforcement is two feet and must utilize the necessary tying and stabilization methods to ensure the GFRP or BFRP remains in the proper position before and during concrete placement. Field cut GFRP or BFRP reinforcement using high speed grinding cutter, fine blade saw, diamond blade, or masonry blade. Ensure all surface damage due to cutting is repaired or replaced as directed by the Engineer, at no additional expense to the contract.

2. Handling. Ensure GFRP bars are handled and transported as to not damage or fracture the bars. Cracked or damaged GFRP bars are not to be used. BFRP bars can be handled similar to their steel counterparts. Minor scratches and chipping that do not impact performance may be permitted with approval of the Engineer.

3. Storage of GFRP or BFRP Reinforcement. Store reinforcement above the surface of the ground on platforms, skids, pallets, or other supports. Cover the GFRP or BFRP bars with a tarp or other protective cover if it is anticipated that the GFRP or BFRP bars will be stored outdoors for more than 2 months. Protective cover must eliminate exposure to ultraviolet (UV) light.

4. Placing and Fastening. Place all reinforcement within the tolerances recommended in the CRSI "Manual of Standard Practice" unless otherwise specified in the contract. Secure reinforcement firmly with mechanical fasteners during the placing and setting of the concrete. Suspend concrete placement and take corrective action if it is observed that the GFRP or BFRP reinforcement is not adequately supported or tied to resist settlement, floating upward, or movement in any direction during concrete placement.

5. Ties and Supports. Ensure all accessories for use with the GFRP or BFRP bars such as tie wires, bar chairs, supports or clips are either plastic coated steel or plastic. Place all reinforcement in locations as shown on the plans and securely hold in position while placing and consolidating concrete. Fasten bars together with ties at all intersections.

6. Lap Splices. Lap splices are the only approved method to tie bars together to make a continuous bar. Mechanical splices are prohibited. Ensure lap length and spacing is as specified in the contract. Provide the same cover clearances for splices that is shown or specified for the reinforcement.

e. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

Pay Item	Pay Unit
Curb and Gutter, Conc, with GFRP Reinf, Det ____	Foot
Valley Gutter, Conc, with GFRP Reinf	Foot
Curb and Gutter, Bridge Approach, with GFRP Reinf, Det ____	Foot

Curb and Gutter, Conc, with BFRP Reinf, Det __Foot
 Valley Gutter, Conc, with BFRP Reinf.....Foot
 Curb and Gutter, Bridge Approach, with BFRP Reinf, Det __Foot

Curb and Gutter, Conc, with GFRP Reinf, Det __; Valley Gutter, Conc, with GFRP Reinf; Curb and Gutter, Bridge Approach, with GFRP Reinf, Det __; Curb and Gutter, Conc, with BFRP Reinf, Det __; Valley Gutter, Conc, with BFRP Reinf; and Curb and Gutter, Bridge Approach, with BFRP Reinf, Det __ include the provision of documentation certifications and submittal of informational samples.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
BACKFILL FOR CONCRETE CURB, GUTTER, AND DIVIDERS

CFS:JJG

1 of 1

APPR:DMG:DBP:02-16-23
FHWA:APPR:02-21-23

Delete subsection 802.04.H, on page 8-7 of the Standard Specifications for Construction, in its entirety and replace with the following:

- H. **Backfill.** Unless the contract includes separate pay items for backfill, the unit price for other items of work will include the cost of backfill.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
GROUND MOUNTED SIGN SUPPORTS, REMOVE

DES:DBP

1 of 1

APPR:AJU:MWB:06-28-22
FHWA:APPR:06-28-22

a. Description. This work consists of removing each ground mounted sign support including but not limited to steel posts, wood posts and breakaway sign supports per section 810.03 Standard Specifications for Construction. Complete this work in accordance with this special provision, the plans, sections 810 and 919 of the Standard Specifications for Construction, and as directed by the Engineer.

b. Materials. None specified.

c. Construction. Once the existing sign has been removed and addressed per the contract remove the ground mounted sign support.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Ground Mtd Sign Support, Rem.....	Each

Ground Mtd Sign Support, Rem includes the cost of removing each support as shown on the plans or as directed by the Engineer.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
PAVEMENT MARKING EQUIPMENT

PMK:MKB

1 of 2

APPR:MWB:DBP:06-07-23
FHWA:APPR:06-20-23

Delete subsection 811.03.A on page 623 of the Standard Specifications for Construction in its entirety and replace it with the following:

- A. **Equipment.** Provide self-propelled equipment certified by the Department in accordance with MDOT's *Equipment Certification Guidelines – Pavement Markings* for longitudinal striping on roadways. Certification is effective for 2 years. The Engineer may approve other equipment for special markings, parking lots, or areas inaccessible to self-propelled pavement marking equipment.

Apply longitudinal lines using certified self-propelled pavement marking equipment equipped with at least two binder tanks (plus a third catalyst tank for plural component materials) each having a capacity of at least 100 gallons and, if a double drop of two different optics is required, at least two optics tanks that may be utilized at the same time and have enough capacity to match the operating duration of 100 gallon binder tanks. Operate marking equipment at no greater than the certified speed. The Engineer will assume that a striper operating above the certified working speed has operated at that speed for the entire day.

The Department may inspect the equipment at any time.

Use equipment capable of uniformly applying material to the required length and width.

Combination lines (double solid, solid and broken, double broken) must be placed in a single pass utilizing a multi-gun system. If the project calls for 4-inch width centerlines, provide equipment for placing centerlines equipped to apply three 4-inch-minimum-width lines on a two-lane road in one pass. If applying multiple centerlines, use three spray guns positioned 6 inches on center. If the project calls for 6-inch width centerlines, provide equipment for placing centerlines equipped to apply two 6-inch-minimum-width lines on a two-lane road in one pass. If applying multiple centerlines, use two spray guns positioned 10 inches on center. For two-lane freeways, apply the lane line from the left lane. For freeways with at least three lanes, apply the right lane line with the right edgeline when the right lane line and edgeline are the same material.

Use an easily adjusted, dashing mechanism to retrace existing lane or centerline markings.

Use a self-propelled pavement marker equipped to mark pavement in either direction on a roadway. Provide equipment setup to apply markings off both sides of the truck simultaneously when not striping in a recess. The driver's side carriage must be equipped with a dedicated white gun along with the yellow guns. The truck must also be

equipped with blowers in front of the gun carriages with the air supply produced by a minimum 185 cfm compressor. If striping contraflow to traffic, a lane closure must be utilized. Use a continuous skip cycle. Do not zero or return the cycle control unit to the beginning or start of a new cycle.

Provide a distance meter to measure the length of each line.

The Engineer may check the calibration of metering devices at any time. If the Engineer determines that the equipment is unsatisfactory, use other methods approved by the Engineer.

Use equipment for placing hot-applied thermoplastic and sprayable thermoplastic material that can maintain the temperature recommended by the material manufacturer.

Allow time for the Engineer to inspect traffic control devices as shown in MDOT's *Pavement Marking Convoy Typical*s or the project plans prior to marking applications and make any corrections as directed by the Engineer before continuing. If applying markings on a roadway closed to traffic, the traffic control devices specified in MDOT's *Pavement Marking Convoy Typical*s are not required, unless otherwise directed by the Engineer.

The equipment must have the following minimum safety equipment: a backup camera; strobes on the front, rear and midpoint of the truck bed; flood lights for night work; and flashers on the gun carriages.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
MOBILE ATTENUATOR

COS:CRB

1 of 4

APPR:CT:LLR:08-04-22
FHWA:APPR:08-15-22

a. Description. This special provision sets the guidelines for when mobile attenuators are to be used to protect workers or work equipment from vehicular traffic. Throughout this special provision, mobile attenuators refer to truck mounted attenuators (TMA) and trailer mounted attenuators.

Use mobile attenuators in projects to protect personnel or equipment when one or more of the following conditions are met.

- The vehicle is designated as a protective vehicle (shadow vehicle or barrier vehicle) as part of the Maintaining Traffic Typicals, maintenance of traffic plans, or other contract documents.
- Aerial work is being performed on scaffolding, lifts, hoists, bucket trucks, etc., where workers using this equipment are in an occupied lane or shoulder and not protected by temporary barrier. Mobile attenuators are not intended to be used for the removal, installation, or maintenance of traffic signals.
- Mobile/short duration operations such as pavement marking convoys, grinding in rumble strips, permanent sign installations, temporary ground mounted sign installations, sign installations located in areas where a work-vehicle cannot pull entirely outside of the edge line, luminescent installations, etc. Mobile attenuators are not intended to be used for the removal or installation of special markings.

Do not mount mobile attenuators on the vehicle or equipment used by personnel to complete aerial work. Do not use mobile attenuators as a temporary/permanent barrier ending except during replacement of damaged temporary/permanent barrier endings. In the event that a mobile attenuator is used as a temporary safety measure for a damaged temporary/permanent barrier ending, the maximum length of time that it can be used for this purpose is 48 hours or as approved by the Engineer.

1. Stationary and Mobile Operation. This work consists of furnishing a vehicle with a gross vehicle weight meeting manufacturer's specifications, or meeting the minimum weight requirements shown in Tables 1 and 2, whichever is greater. Furnish, install, and operate a mobile attenuator in accordance with the manufacturer's recommendations, the contract, and/or as directed by the Engineer. Locate the attenuator placement as detailed in the applicable Maintaining Traffic Typical, maintenance of traffic plans or elsewhere in the contract.

Securely attach material loaded onto the vehicle to obtain the required gross weight, for transport or during work operations to the vehicle. Hazardous materials will not be allowed

on this vehicle. Materials that will be off loaded and incorporated into the construction activities will not be considered part of the vehicle gross weight.

b. Materials and Design. Use mobile attenuators that meet or exceed the requirements of *NCHRP 350 Test Level 2 (TL-2)* or *Test Level 3 (TL-3)*, or *MASH TL-2* or *TL-3*, as described below for work zone traffic control devices.

1. Utilize a mobile attenuator rated for *NCHRP 350, TL-2* or *MASH, TL-2* on non-freeway roadways with a normal posted speed of 40 mph or less. TL-2 mobile attenuators are prohibited for use on all freeways, regardless of the posted speed limit, and non-freeway roadways and work zones with posted speed limits of 45 mph or greater.

2. Utilize a mobile attenuator rated for *NCHRP 350, TL-3* or *MASH, TL-3* on all freeways, regardless of the posted speed limit, and non-freeway roadways and work zones with posted speed limits of 45 mph or greater. TL-3 mobile attenuators may be used on all roadways and work zones regardless of the posted speed limit.

Furnish the Engineer a copy of the FHWA letter of eligibility for federal aid stating the mobile attenuator meets the appropriate *NCHRP 350* or *MASH* test level specified in the above stated criteria. In addition, furnish a letter to the Engineer stating the mobile attenuator system has been installed and maintained in accordance with the manufacturer's specifications.

The face of the mobile attenuator, visible to approaching traffic must have reflectorized alternating yellow and black stripes, sloping downwards in both directions from the center of the attenuator.

c. Operating Details and Utilization. Operate the mobile attenuator per manufacturer's recommendations, the contract, and/or as directed by the Engineer. This includes, but is not limited to, the following:

- Unless otherwise specified by the mobile attenuator manufacturer, ensure the height from the bottom of the mobile attenuator to the roadway surface is 12 inches (± 2.5 inches). When specified otherwise by the manufacturer, furnish documentation to the Engineer indicating the manufacturer's bottom height recommendations and tolerances.
- Ensure the mobile attenuator is parallel (level) with the roadway surface.
- Furnish a shoulder harness and headrest for the mobile attenuator vehicle's operator.

For stationary operations, when operating the vehicle with the attenuator installed, ensure the vehicle is in second gear if it has a standard transmission (park if an automatic transmission), with the parking brakes set and steering wheels turned away from the work area and traffic, if possible.

Place the mobile attenuator in accordance with the manufacturer's recommended roll-ahead distance, or the minimum roll-ahead distance shown in Tables 1 and 2, whichever is greater.

If the mobile attenuator is involved in a crash, provide pictures of the crash scene and the damage of the mobile attenuator to the Engineer within 7 days of the incident.

d. Measurement and Payment. Mobile attenuators will be furnished and operated at no cost to the Department for all contract items associated with pavement marking operations.

The cost for the equipment, mobilization, and labor to furnish and operate this equipment will be included in other contract pay items. The Department will pay for repair or replacement of a mobile attenuator called for as part of the pavement marking operations if damaged by something other than the Contractor’s own equipment, during contract operations as described below. Measurement and payment for the use of mobile attenuators on all other contract items will be as described below.

Pay Item	Pay Unit
Mobile Attenuator	Each

The Department will pay for the maximum number of mobile attenuators deployed per the Maintaining Traffic Typical, maintenance of traffic plans or elsewhere in the contract and in use at any one time during the life of the project or as approved by the Engineer. If the Contractor uses alternative construction operations or methods that require additional mobile attenuators that exceed the amount specified in the contract, the additional mobile attenuators must be provided at the Contractor’s expense.

The Department will pay for repair or replacement of a mobile attenuator called for as part of the contract if damaged by something other than the Contractor’s own equipment, during contract operations by contract modification with the name of the extra pay item to be defined as Mobile Attenuator, Repair or Mobile Attenuator, Replace if the following criteria are met:

1. The damaged or destroyed attenuator must meet all of the manufacturing and operating criteria of this special provision.
2. The Contractor must have attenuators repaired or replaced in accordance with the Manufacturer/Supplier recommendations to ensure that the units are in good working order. Documentation of repair is to be furnished to the Engineer via signed certification from the Contractor stating that the repairs have been done in accordance with the Manufacturer’s recommendations prior to implementing the mobile attenuators for use.
3. Furnish a crash report from the enforcement agency involved in the crash investigation.
4. Furnish pictures of the crash scene and damages to the mobile attenuator.
5. Ensure the attenuator repair or replacement is for the actual unit as required by this special provision. The cost to perform the repairs or replace the attenuator including installation will be paid for by the Contractor. Furnish to the Engineer a detailed invoice from the Supplier showing material costs for replacement or repair for payment. The Department will not pay for repair or replacement cost beyond the Suppliers’ invoice cost for a new attenuator.
6. The Department will not pay for any costs that are required to replace or repair the attenuator vehicle and any other items which were used to operate the attenuator.
7. Attenuators that have been repaired or replaced as part of the contract are not eligible for additional payment using the Mobile Attenuator pay item once the attenuator is placed back into service.

Table 1. Guidelines For Roll-Ahead Distance For Mobile Attenuator Vehicles Test Level 2

Weight of Mobile Attenuator Vehicle (b)	Posted Speed (mph) (Posted Speed Prior to Work Zone)	Roll Ahead Distance (a), (c) (Distance from front of Mobile Attenuator Vehicle to Work Area)
5.5 Tons (Stationary Operation)	40 or Less	25 feet
a. Roll ahead distances are calculated using a 4,410 pound impact vehicle weight. b. Minimum vehicle weight specified. Use manufacturer's recommended mobile attenuator vehicle weight when the manufacturer's recommendation exceeds the minimum weight specified in this table. c. Minimum roll-ahead distance specified. Use manufacturer's recommended roll-ahead distance when the manufacturer's recommendation exceeds the minimum roll-ahead distance specified in this table.		

Table 2. Guidelines For Roll-Ahead Distance For Mobile Attenuator Vehicles Test Level 3

Weight of Mobile Attenuator Vehicle (b)	Posted Speed (mph) (Posted Speed Prior to Work Zone)	Roll-Ahead Distance (a), (c) (Distance from front of Mobile Attenuator Vehicle to Work Area)
5 Tons (Mobile Operation)	60-70	175 feet
	50-55	150 feet
	45	100 feet
12 Tons (Stationary Operation)	60-70	50 feet
	50-55	25 feet
	45	25 feet
a. Roll ahead distances are calculated using a 10,000 pound impact vehicle weight. b. Minimum vehicle weight specified. Use manufacturer's recommended mobile attenuator vehicle weight when the manufacturer's recommendation exceeds the minimum weight specified in this table. c. Minimum roll-ahead distance specified. Use manufacturer's recommended roll-ahead distance when the manufacturer's recommendation exceeds the minimum roll-ahead distance specified in this table.		

MICHIGAN
DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION
FOR
EXCAVATED TOPSOIL OR SALVAGED TOPSOIL

RSD:NJM

1 of 1

APPR:NMA:DMG:02-16-23
FHWA:APPR:02-21-23

Delete subsection 816.03.A.3, on page 8-145 of the Standard Specifications for Construction, in its entirety and replace with the following:

- 3. Excavated Topsoil or Salvaged Topsoil.** Excavate topsoil intended for salvaging in accordance with subsection 205.03.A.1. The Engineer will direct stockpiling excavated or salvaged topsoil within the right-of-way. Salvaged topsoil must be weed-free prior to establishing new growth. Salvaged topsoil that is made unsuitable for use from excavation, maintenance, or other Contractor operations will be rejected by the Engineer.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
INDUSTRIAL BY-PRODUCTS AND BENEFICIAL RE-USE

HYD:HLZ

1 of 1

APPR:JJG:JFS:04-02-20
FHWA:APPR:04-03-20

a. Description. For this project, regardless of the application, the use of industrial by-products covered in 2014 PA 178 is prohibited unless the use and application of a particular material is covered elsewhere in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
PORTLAND CEMENT (TYPE IL)

CFS:JFS

1 of 2

APPR:TES:TEB:12-14-21
FHWA:APPR:12-16-21

a. Description. The Contractor may substitute Type IL Portland cement in lieu of Type I Portland cement for concrete mixtures and other applications where Type I Portland cement is specified, provided documentation showing specification compliance is provided as described herein.

The Contractor must provide the Engineer a minimum of 14 calendar days prior notification of their intent to substitute Type IL Portland cement in lieu of Type I Portland cement for the project.

b. Materials. Furnish Type IL Portland cement in accordance with section 901 of the Standard Specifications for Construction meeting the chemical and physical requirements specified in *ASTM C595/C595M, Standard Specifications for Blended Hydraulic Cements*. Ensure the Type IL Portland cement proposed for substitution is from the same Approved Manufacturer as the Type I Portland cement in the approved JMF.

c. Construction. At least 7 days prior to concrete production, the concrete producer must provide test data (specified below) generated from a four cubic yard (minimum) trial batch of concrete using Type IL Portland cement for the Engineer's review and approval. The trial batch must represent a current approved JMF for either a standard MDOT Grade 3500, Grade 3500HP, Grade 4500, or Grade 4500HP concrete mixture produced using Type I Portland cement, as described in section 1004 of the Standard Specifications for Construction. Ensure the materials and mixture proportions for the Type IL JMF are the same as those documented in the above mentioned JMF using Type I Portland cement. Minor adjustments to chemical admixture dosages are permitted in efforts to achieve the specified fresh concrete properties. Trial batch compliance for applications other than Portland cement concrete mixtures will be in accordance with the contract.

1. Fresh Concrete Properties.
 - A. Concrete temperature,
 - B. Air content of fresh concrete, and
 - C. Slump.
2. Hardened Concrete Properties.
 - A. 7-day compressive strength.

The Engineer will review the trial batch test data to determine if the fresh and hardened concrete properties of the Type IL JMF meet specification requirements for the respective MDOT Grade of

concrete represented by the trial batch. If the Engineer determines that the trial batch test data are in conformance with specification requirements, then the Type IL Portland cement will be permitted to be substituted in lieu of the Type I Portland cement for all approved concrete mixtures generated at the concrete production facility for the project. If the Engineer determines that the trial batch test data do not meet specification requirements for the respective MDOT Grade of concrete, the Contractor will not be permitted to substitute Type IL Portland cement in lieu of Type I Portland cement. Mix design and JMF documentation for concrete mixtures using Type IL Portland cement will then be required in accordance with subsection 1003.03.C of the Standard Specifications for Construction or the contract, where applicable.

Once Type IL Portland cement is approved for use on the project, reinstatement of Type I Portland cement into the JMF is not permitted. Substitution of other material types or sources, including admixtures, as documented in the initial Type I JMF is not permitted.

The Engineer will complete field sampling and testing for all production lots containing Type I Portland cement JMF prior to respective Type IL Portland cement substitution. Do not include concrete mixtures containing Type I and Type IL Portland cement types in the same production lot.

d. Acceptance. The Contractor may substitute Type IL Portland cement in lieu of Type I Portland cement for the project with no additional laboratory trial batch requirements, as described in subsection 1003.03.C.2.a of the Standard Specifications for Construction, provided the Engineer has reviewed the concrete producer's test data generated from a four cubic yard (minimum) trial batch of concrete, described above, and has determined that the fresh and hardened concrete properties of the Type IL JMF meet specification requirements for the respective MDOT Grade of concrete represented by the trial batch.

e. Measurement and Payment. The work included in this special provision will not be paid for separately and is included in other pay items in the contract.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
AGGREGATE, 46G

CFS:JJG

1 of 1

APPR:SAG:DMG:02-15-22
FHWA:APPR:02-16-22

Delete the last row of Table 902-2 in subsection 902 of the Standard Specifications for Construction in its entirety and replace with the following:

Open-graded aggregates	46G	80	45	—	—	—
---------------------------	-----	----	----	---	---	---

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
MICRONIZED COPPER WATER BASED WOOD PRESERVATIVE SYSTEMS

STR:SCK

1 of 1

APPR:HLZ:POJ:04-13-20
FHWA:APPR:04-13-20

a. Description. Micronized copper water based wood preservative systems are an alternate to the preservative systems identified in section 912 of the Standard Specifications for Construction, except on wood posts used for signing. Micronized copper water based wood preservative systems are proprietary systems used to treat timber and lumber for resistance to insect attack, decay, and rot. Proprietary micronized copper based wood preservative systems are evaluated by the *International Code Council Evaluation Service, Inc (ICC-ES)*. This special provision covers the requirements for micronized copper azole (MCA) and micronized copper quaternary (MCQ).

b. Materials. *ICC-ES* requirements and specified commercial standards are incorporated herein by reference. Treated wood product reports issued by the *ICC-ES* as Evaluation Service Reports (ESRs) must be current as posted on the *ICC-ES* website <https://icc-es.org/> and in compliance with AC326. The preservative(s) must not contain arsenic. The treated wood product's report must allow for the wood species and end use that is required by the project specifications. The Contractor must provide test data certification for each lot, that the treated timber and lumber meets the retention requirements of the appropriate *AWPA* Use Category.

Condition and treat timber and lumber for above ground use to the minimum preservative retention corresponding to *AWPA* Use Category 4A (UC4A). Condition and treat timber and lumber for ground contact to the minimum preservative retention corresponding to *AWPA* Use Category 4B (UC4B).

Condition and treat all round posts, except northern white cedar, to the minimum preservative retention corresponding to *AWPA* Use Category 4B (UC4B).

Incorporation of timber and lumber treated to the preservative retention in *AWPA* Use Category 3B (UC3B) or less is not permitted. Timber and lumber placed in violation of this special provision is cause for removal and replacement at the contractor's expense. No pay adjustments will be allowed for incorporation of timber and lumber treated to UC3B preservative retention. Removal is required.

c. Construction. Use stainless steel fasteners or hot dipped galvanized fasteners in accordance with *ASTM A653/A653M*, batch or post-dipped process, with a minimum coating thickness of 1.85 oz of Zinc per square foot of surface area (G185). Do not mix fastener types. Do not use aluminum fasteners. Aluminum must not be in direct contact with treated wood. Non metallic spacers are to be used where contact with aluminum could occur.

d. Measurement and Payment. Payment is included in other items of work.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
WET REFLECTIVE PAVEMENT MARKINGS

PMK:MKB

1 of 1

APPR:MWB:DBP:06-07-23

FHWA:APPR:06-20-23

Delete subsection 920.02.C on page 9-170 of the Standard Specifications for Construction in its entirety and replace it with the following:

- C. **General Requirements for Wet Reflective Optics.** Select wet reflective optics from the Qualified Products List or a Department-approved alternative that meets or exceeds the retroreflectivity requirements specified in Table 920-3.

Prior to application, submit certification from the wet reflective optics manufacturer that when applied according to the manufacturer's application recommendations, the wet reflective optics meet the requirements in Table 920-3.

**Table 920-3:
General Wet Reflective Optic Requirements: Average Initial
Retroreflectivity at 30-meter Geometry in mcd/lux/m²**

Test Method	Color	
	White	Yellow
Dry (<i>ASTM E1710</i>) for cold plastic, polyurea, waterborne, regular dry, and sprayable thermoplastic	700	500
Dry (<i>ASTM E1710</i>) for all other materials	550	350
Wet Recovery for all materials (<i>ASTM E2177</i>)	250	200
Wet Continuous for all materials (<i>ASTM E2832</i>)	100	75

Initial retroreflectivity is defined as readings taken no earlier than 7 days and no later than 30 days after material placement.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
TEMPORARY PAVEMENT MARKING, TYPE R TAPE REVISION

COS:CRB

1 of 1

APPR:LLR:MKB:04-18-22
FHWA:APPR:05-05-22

Delete subsection 922.06.A.1 of the Standard Specifications for Construction, in its entirety and replace with the following:

1. **Pavement Marking, Wet Reflective, Type R.** Provide wet reflective Type R temporary pavement marking as preformed tape. Apply and remove preformed tape in accordance with the manufacturer's instructions. The tape must remain flexible and conform to the texture of the pavement surface during use. Select one of the following materials:
 - a. 3M™ Stamark™ Wet Reflective Removable Tape Series IR710 White manufactured by 3M Traffic Safety & Security Division, 3M Center, 225-4N-14 St. Paul, MN, 55144, (800)-553-1380.
 - b. 3M™ Stamark™ Wet Reflective Removable Tape Series IR711 Yellow manufactured by 3M Traffic Safety & Security Division, 3M Center, 225-4N-14 St. Paul, MN, 55144, (800)-553-1380.
 - c. Deltaline Temporary Wet Reflective/TWR-HP white manufactured by Brite-line LLC 10660 East 51st Ave. Denver, CO 80239, phone 303-375-1293.
 - d. Deltaline Temporary Wet Reflective/TWR-HP yellow manufactured by Brite-line LLC 10660 East 51st Ave. Denver, CO 80239, phone 303-375-1293.

Local Agencies may use a material listed above or select wet reflective Type R markings from the Qualified Products List (922.06A).

MICHIGAN
DEPARTMENT OF TRANSPORTATION

NOTICE TO BIDDERS
FOR
MULTIPLE DAVIS-BACON WAGE DECISIONS

CSD:LFS

1 of 1

APPR:CT:03-24-22

This proposal may contain multiple Davis-Bacon Wage Decisions. In order to clarify the work covered by each decision, the following explanations are offered:

General Decision MIxxxx0001 covers all airport construction, bridge construction, highway construction, and sewer and water main work that are incidental to highway projects. The construction type indicated on this decision is "HIGHWAY (HIGHWAY, AIRPORT & BRIDGE xxxxx and SEWER/INCID. TO HWY.)". This wage decision is the most commonly used wage decision in MDOT's federally funded projects.

In accordance with the U.S. Department of Labor's (DOL) all agency memorandums No. 130, No 131 and No. 236, multiple wage decisions will be included in those projects in which a second category of work is substantial in relation to project cost – more than approximately 20 percent or \$2,500,000. Sewer and water main work is considered to fall under the heavy construction work classification by the DOL, therefore when that work type is more than 20 percent of the engineer's estimate or \$2,500,000, the wage decision with the construction type "HEAVY CONSTRUCTION PROJECTS" will also be included in the proposal and is to be used for the sewer and watermain work in the proposal. All other work performed on the project will be covered by the "HIGHWAY (HIGHWAY, AIRPORT & BRIDGE xxxxx and SEWER/INCID. TO HWY.)" wage decision.

Also, when the landscape work is more than 20 percent of the project cost or \$2,500,000, the "HEAVY CONSTRUCTION PROJECTS" wage decision will be included in the proposal to cover all landscape work. All other work performed on the project will be covered by the "HIGHWAY (HIGHWAY, AIRPORT & BRIDGE xxxxx and SEWER/INCID. TO HWY.)" wage decision. If the project is a total landscape project, only the "HEAVY CONSTRUCTION PROJECTS" wage decision will be in the proposal.

Rest area building projects will include the construction type "BUILDING" wage decision when the building portion of the work is more than 20 percent of the project cost or \$2,500,000. The other work performed on the project will be covered by the "HIGHWAY (HIGHWAY, AIRPORT & BRIDGE xxxxx and SEWER/INCID. TO HWY.)" wage decision and/or the "HEAVY CONSTRUCTION PROJECTS" wage decision (landscape and/or sewer and water main work) if either or both are greater than 20 percent or \$2,500,000.

Although there is only one wage decision for "HIGHWAY (HIGHWAY, AIRPORT & BRIDGE xxxxx and SEWER/INCID. TO HWY.)", work (MIxxxx0001), the "HEAVY CONSTRUCTION PROJECTS" and "BUILDING" wage decisions vary from county to county.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

NOTICE TO BIDDERS
FOR
BID RIGGING

CSD:LS

1 of 1

APPR:MAS:02-09-21

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially, and caller anonymity will be respected.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

NOTICE TO BIDDERS
FOR
FRAUD AND ABUSE HOTLINE

CSD:LS

1 of 1

APPR:MAS:02-09-21

The Michigan Department of Transportation (MDOT) has established a Fraud and Abuse Hotline for employees, contractors, consultants, and others to report suspected fraud or abuse, such as: prevailing wage non-compliance, theft, kickbacks, wrongful claims, contract fraud, use of materials that do not comply with specifications, unapproved substitution of materials, commodities, or test samples, or failure to follow contract procedures.

Anyone with knowledge of any activity involving the potential for fraud or abuse is requested to call the Hotline at (toll free) **1-866-460-6368** or **517-241-2256**.

MICHIGAN
DEPARTMENT OF TRANSPORTATION

NOTICE TO BIDDERS
FOR
USE OF CRUSHED CONCRETE FOR DENSE- AND OPEN-GRADED AGGREGATES

ENV:CP

1 of 1

APPR:MAS:09-09-21

Pursuant to section 902 of the 2020 Standard Specifications for Construction, the use of crushed concrete for dense-graded aggregate, open-graded aggregate is prohibited within 100 feet of a waterbody (stream, river, county drain, wetland, lake, etc.).

Waterbodies are located at the following stations:

STA 1209+71 (Averill Drain)

MIDLAND COUNTY ROAD COMMISSION

NOTICE TO BIDDERS
FOR
UTILITY COORDINATION

MCRC:ROWE

1 of 2

AUGUST 2023

The contractor shall cooperate and coordinate construction activities with the owners of utilities as stated in subsection 104.08 of the Standard Specifications for Construction. In addition, for the protection of underground utilities, the contractor shall follow the requirements in subsection 107.12 of the Standard Specifications for Construction. Contractor delay claims, resulting from a utility, will be determined based upon subsection 108.09 of the Standard Specifications for Construction.

AT&T

Michael Baiz
502 Beach Street
Flint, MI 48502
810-938-3143
mb1269@att.com

Charter Communications

Mark Kelly
1480 South Valley Center Drive
Bay City, MI 48706
989-233-9404
mark.kelly@charter.com

Consumers Energy (Electric)

Virgie Downs
2400 Weiss St
Saginaw, MI 48602
989-791-5938
virgie.downs@cmsenergy.com

TDS Telecom

Bill Bouman
104 N. Cedar Street
Sanford, MI 48657
989-687-0120
william.bouman@tdstelecom.com

Consumers Energy (Gas Distribution)

Evan Huizenga
2400 Weiss St
Saginaw, MI 48602
810-847-8227 (W)
evan.huizenga@cmsenergy.com

City of Midland Engineering Department

Matt Lemon
333 W. Ellsworth St
Midland, MI 48640
989-837-3348
mlemon@midland-mi.org

City of Midland Water Distribution

Tom Hoblet
333 W. Ellsworth St
Midland, MI 48640
989-837-3341
thoblet@midland-mi.org

Water District #1 of Midland County

Nathan French
246 E. Price Road
Midland, MI 48642
989-687-2709
[N. French@wd1midcounty.com](mailto:N.French@wd1midcounty.com)

Midland County Drain Commissioner

Joseph Sova

220 W. Ellsworth St

Midland, MI 48640

989-832-6770

drain@co.midland.mi.us

For the protection of underground utilities, and in conformance with Public Act 174 of 2013, the Contractor shall contact MISS DIG System, Inc. by phone at 811 or 800-482-7171 or via the web at either elocate.missdig.org for single address or rte.missdig.org, a minimum of 3 business days prior to excavating, excluding weekends and holidays. Members will thus be routinely notified. This does not relieve the Contractor of the responsibility of notifying utility owners who may not be part of the "Miss Dig" alert system.

The owners of existing service facilities that are within grading or structure limits will move them to locations designated by the Engineer or will remove them entirely from the roadway right-of-way.

Owners of utilities will not be required to move additional poles or structures in order to facilitate construction operations, unless it is determined by the Engineer that such poles or structures constitute a hazard to the public or are extremely dangerous to the Contractor's operations.

The existing utilities shown on the plans represent the best information available as obtained from survey and existing records. This information does not relieve the Contractor of the responsibility of protecting all existing utilities, in case utilities have been constructed or removed since the survey date or if utilities are encountered in different locations.

MICHIGAN
DEPARTMENT OF TRANSPORTATION
SUPPLEMENTAL SPECIFICATION
FOR
ERRATA TO THE 2020 STANDARD SPECIFICATIONS

1 of 10

06-30-23

Page	Subsection	Errata
1-06	101.02	Delete the second abbreviation of the list on this page reading: “IES Illuminating Engineering Society
1-06	101.02	Add the abbreviation to the list on this page reading: “IESNA Illuminating Engineering Society of North America
1-83	108.05.A.2	In the first paragraph of this subsection change the language “MDOT Form 1130” to read “MDOT Form 1130A”.
1-88	108.08.D	Move the last paragraph of this subsection to the left one indent to align with the first paragraph of the subsection and not with the subsection 108.08.D.3.
2-29	205.03.P.1	Delete the first sentence of this subsection and replace with the following: “Do not dispose of material, temporarily or permanently, beyond the normal plan fill slope across wetlands or floodplains.”
2-30	205.03.P.2	Delete the first sentence of this subsection and replace with the following: “Do not dispose of material, temporarily or permanently, in wetlands or floodplains.”
2-30	205.03.P.3	Delete the second paragraph of this subsection and replace with the following: “Contact the appropriate regulatory agencies to determine whether an area is a regulated wetland or floodplain before disposing of surplus or unsuitable material in areas outside the right-of-way and not shown on the plans as disposal sites.”
2-30	205.03.P.3	Delete the first sentence of the third paragraph of this subsection and replace with the following: “Immediately move to an upland site any surplus or unsuitable material that was disposed of in portions of wetlands or floodplains not shown on the plans as disposal sites, at no additional cost to the Department.”
2-30	205.03.P.4	Delete the first sentence of this subsection and replace with the following:

“The Department will notify the applicable regulatory agencies if the Department becomes aware that the Contractor disposed of surplus or unsuitable material in portions of a wetland or floodplain not shown on the plans.”

- 3-31 308.04.D Change the subsection title from “D. **General.**” to read “A. **General.**”
- 4-7 401.03.E Delete the third sentence of the second paragraph of this subsection and replace with the following:
“Use precast or cast-in-place footings for precast end sections as required.”
- 4-8 401.03.E Delete the first sentence of this subsection and replace with the following:
“When discharging stormwater directly to waters of the state, permanently label all end sections or other piped points of stormwater entry with “MDOT” or the local agency’s name in a conspicuous location that will remain visible after construction.
- 4-11 401.04 Change the eighth pay item from the bottom of the list on this page to read as follows:
Culv End Sect __ inch, Grate.....Each
- 4-12 401.04.C.4 Change this subsection to read:
“The Engineer will measure Culv End Sect __ inch, Grate by each as shown on the plans for the size of grate required.”
- 4-21 402.03 Add a new subsection to the end of subsection 402.03 on this page reading as follows:
“K. **Outfall Labeling.** Label all stormwater outfalls directly discharging to waters of the state in accordance with subsection 401.03.E.
- 4-39 406.02 Change the third line in the list of materials to read:
Coarse Aggregate 6A, 6AA, 17A.....902
- 4-41 406.03.A.3 Delete the third paragraph of this subsection and replace with the following:
“Design joints between adjacent box culvert sections in accordance with Section 9 of ASTM C1577 and to accommodate the joint sealing material in accordance with section 914 as applicable.”
- 4-50 406.03.G.3 Change the first sentence of the first paragraph to read:
“Unless otherwise shown on the plans, construct culvert bedding for box culverts by placing a 9-inch-thick layer of 46G aggregate, covered with a 3-inch-thick layer of 34G, 34R aggregate, or approved equal.”
- 4-51 406.03.G.3 Add the following sentence to the end of the second paragraph of this subsection:

“The cold applied joint sealer must completely cover the external rubber gasket with the placement limits matching the width of the geotextile blanket.”

- 4-52 406.04.B In the second paragraph of this subsection delete the first sentence and replace with the following:
“The Department will pay separately for cast-in-place concrete, other than for culvert segments, headwalls, wingwalls, aprons, and curtain walls.”
- 5-26 502.02 Delete the first sentence of the subsection and the listed materials in this subsection.
- 5-26 502.02.A Add the following to the end of the first sentence in this subsection:
“(914.04A)”
- 5-26 502.02.B Add the following to the end of the first sentence in this subsection:
“(502.02B)”
- 5-35 503.04 Change the first paragraph to read:
“The unit price for **Paver-Placed Surface Seal**, of the type required, includes the cost of preparing the surface, and placing a membrane and paver placed surface seal course for full-width coverage, except that the Department will pay separately for removing pavement markings in accordance with subsection 812.04”
- 5-46 504.04.A Change the first paragraph to read:
“A. **General**. The unit prices for **Micro-Surface**, regardless of the type required, include cleaning existing pavement, applying a bond coat, stationing, corrective action, and traffic control to complete corrective action.”
- 6-20 602.04 Delete the fifteenth pay item of the list on this page reading:
“Shoulder, Reinf Conc..... Square Yard
- 6-20 602.04 Change the sixteenth thru the eighteenth pay items on this page to read as follows:
Shld, Nonreinf Conc..... Square Yard
Shld, Nonreinf Conc, High Performance Square Yard
Shld, Freeway..... Square Yard
- 6-21 602.04.B.1 Delete this subsection and replace with the following:
“**Shld, Nonreinf Conc**; and **Shld, Nonreinf Conc, High Performance**. The Engineer will measure, and the Department will pay for, **Shld, Nonreinf Conc**; and **Shld, Nonreinf Conc, High Performance** by area, based on plan quantities in accordance with subsection 109.01.”
- 6-21 602.04.B.2 Delete this subsection and replace with the following:
“**Shld, Freeway**. The Engineer will measure, and the Department will pay for, **Shld, Freeway** based on plan quantities in accordance

with subsection 109.01. If the Contractor uses concrete for the shoulder, the unit price for **Shld, Freeway** includes the cost of the transverse joints in the shoulder and the external longitudinal pavement joints.”

6-23	602.04.F	Add the following sentence to the end of the first paragraph of this subsection: Temporary concrete pavement, pavement within 4 feet of an obstruction, pavement areas less than 300 square yards, or pavement less than 3 feet wide will not be cored.
6-23	602.04.F	Delete the following language from this subsection on this page: “The Engineer will not core the following: 1. Temporary concrete pavement; 2. Pavement within 4 feet of an obstruction; 3. Pavement areas less than 300 square yards; or 4. Pavement less than 3 feet wide.”
6-24	602.04	Rename the following subsections as follows: “1. Initial Core.
6-24	602.04	2. Additional Cores.
6-24	602.04	3. Price Adjustment for Thickness.
6-25	602.04	4. Price Adjustments for Steel Locations within the Pavement.
6-26	602.04	5. Remove and Replace.”
7-107	709.04	Change the Pay Unit on the second pay item from the top of the list on this page to read as follows: Thousand Board Foot
8-12	804.03.B.2	Change the first sentence in this subsection to read: “Cast in place light standard and sign support foundations using fixed forms in accordance with the <i>MDOT Standard Plan R-50 series.</i> ”
8-27		Change the last pay item at the bottom of this page to read as follows: Guardrail Anch, Bridge, Det __, Curved.....Each
8-44	810.03.J.9	Add a period to the end of the third sentence in this subsection.
8-53	810.03.V	Add a period to the end of the second sentence of the first paragraph of this subsection.
8-53	810.04	Change the fourth pay item from the top of the list on this page to read as follows: Post, Steel, __ pound.....Foot

- 8-53 810.04 Change the last four pay items at the bottom of this page to read as follows:
Fdn, Truss Sign Structure Type __, __ inch dia, Cased.....Foot
Fdn, Truss Sign Structure Type __, __ inch dia, UncasedFoot
Fdn, Cantilever Sign Structure Type __, __ inch dia, CasedFoot
Fdn, Cantilever Sign Structure Type __, __ inch dia, Uncased.Foot
- 8-55 810.04.B.1 Delete the second paragraph of this subsection and replace with the following:
“The unit prices for **Fdn, Truss Sign Structure Type __, __ inch dia, Cased** and **Fdn, Cantilever Sign Structure Type __, __ inch dia, Cased** include the cost of concrete, slurry, steel reinforcement, permanent casings, anchor bolts, excavation, and disposal of excavated material.”
- 8-55 810.04.B.2 Delete this subsection and replace with the following:
“**Foundation, Truss Sign Structure, Uncased and Foundation, Cantilever Sign Structure, Uncased.** The unit prices for **Fdn, Truss Sign Structure Type __, __ inch dia, Uncased** and **Fdn, Cantilever Sign Structure Type __, __ inch dia, Uncased** include the cost of concrete, slurry, steel reinforcement, temporary casings, anchor bolts, excavation, and disposal of excavated material.”
- 8-57 810.04.I Delete the first paragraph of this subsection and replace with the following:
“The unit price for **Sign, Rem** of the type required includes the cost of removing signs from supports and stacking by shape and size.”
- 8-57 810.04.I Delete the second paragraph of this subsection and replace with the following:
“The unit prices for **Ground Mtd Sign Supports, Rem; Cantilever, Rem** and **Truss, Rem** include the cost of removing ground mounted sign supports, cantilever or truss supports.”
- 8-57 810.04.L Change this subsection to read:
“The unit price for Sign, Erect, Salv of the type required includes erecting the salvaged sign on a new sign support or existing sign support, as shown on the plans, and attaching devices, and hardware, including brackets.”
- 8-58 810.04.N Delete this subsection in its entirety.
- 8-110 812.04 Change the fifth and sixth pay item from the top of the list on this page to read as follows:
Sign, Type B, Temp, Prismatic, Spec, Furn Square Foot
Sign, Type B, Temp, Prismatic, Spec, Oper Square Foot
- 8-141 815.04.C.1.b Delete this subsection in its entirety.
- 8-141 815.04.C.1.c Rename and change this subsection as follows:

“b. Removal and disposal of unacceptable plants including the root ball.

8-141	815.04.C.1.d	Delete this subsection in its entirety.
8-142	815.04.C.2.d	Change this subsection to read: "During the first watering of the second growing season, remove and dispose of the guying material, identification tags, and inspection tags."
8-144	816.03.A	Change the third sentence in this subsection to read: "Use topsoil from within the project limits; or from off-site sources meeting the requirements in subsection 917.06."
8-167	818.04	Add the pay item to the bottom of the list on this page as follows: Power Company (Estimated Cost to Contractor)..... Dollar
8-170	818.04.G	Delete this subsection in its entirety.
8-170	818.04	Rename the following subsections as follows: "G. Handholes (Hh).
8-171	818.04	H. Service Disconnect.
8-171	818.04	I. Metered Service.
8-171	818.04	J. Unmetered Service.
8-172	818.04	K. Wood Pole.
8-172	818.04	L. Concrete Pole, Fit Up.
8-172	818.04	M. Steel Pole, Fit Up.
8-172	818.04	N. Bracket Arm. "
8-171	818.04.J	Delete the second paragraph of this subsection and replace with the following: "The pay item, Power Company (Estimated Cost to Contractor) , establishes a budgeted amount in the contract to cover the cost of reimbursing the Contractor for payments made to the power company for providing electrical power at the locations shown on the plans. The Department will estimate the reimbursement costs to the Contractor and establish a budgeted amount as shown on the plans. The Department will pay the Contractor for power company invoices paid, as submitted to the Engineer."
8-176	819.03.B.5.b	In the second paragraph of this subsection delete the first sentence and replace with the following: "Tighten bolts connecting the pole to the frangible base to a snug tight condition in accordance with subsection 707.03.E.6.c."
8-185	820.01.B	Add a period to the end of the first sentence of this subsection.
8-187	820.02	Change the first line in the list of materials on this page to read: Conduit Material.....918

8-196	820.03.O	In the fourth paragraph of this subsection delete the last sentence and replace with the following: "Use smooth wall, Schedule 80, rigid PVC conduit, or coilable, Schedule 80 PE conduit in accordance with section 818."
8-199	820.04	Add the pay item to the list on this page: TS, (number) Way (type) Mtd (LED) Optic
8-200	820.04	Change the second pay item from the top of the list on this page to read as follows: TS Head, TempEach
8-200	820.04	Change the eleventh pay item from the top of the list on this page to read as follows: TS, Lens, Pedestrian Sym (LED)Each
8-200	820.04	Delete the following pay items from the list: Strain Pole, Steel, 6 bolt, __ foot.....Each Mast Arm Pole, Cat.....Each Mast Arm, __Foot, Cat.....Each
8-200	820.04	Change the eleventh pay item from the bottom of the list on this page to read as follows: Mast Arm, Rem.....Each
8-201	820.04	Delete the following pay item from the list: Power Co. (Est Cost to Contractor)..... Dollar
8-202	820.04	Add the following pay item to the list: Bracket, Truss, Salv.....Each
8-204	820.04.C	Delete the last paragraph of this subsection in its entirety.
8-204	820.04.D	Delete the first paragraph of this subsection in its entirety.
9-9	902.03.C.1.b	Delete the first sentence in this subsection and replace with the following: "The physical requirements for the coarse aggregate are as specified in Table 902-2 and as follows:"
9-16	Table 902-2	Delete the superscript footnote in the first through fourth rows under the header row that reads "(m)" in the column Loss, % max, LA Abrasion (MTM 102).
9-16	Table 902-2	Add the superscript footnote in the header row that reads "(m)" in the column Loss, % max, LA Abrasion (MTM 102).
9-15	Table 902-2	Delete the footnote (d) in one location in the table.
9-17	Table 902-2	Delete the footnote (d) in one location in the table.

tests referenced in AASHTO's LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals."

- | | | |
|----------|----------------|--|
| 9-170 | 920.02.C | Change the reference to Table 920-2 to read Table 920-3 in two locations. |
| 9-222 | 922.10.A.3 | Delete this subsection and replace with the following:
"Conform to the wind load requirements specified by AASHTO's LRFD Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals with all equipment mounted without the need for additional ballast;" |
| 10-23 | 1003.03.B | Delete the last sentence of this subsection and replace with the following:
"Aggregate sampling for concrete will be performed by an MCAT-certified Aggregate Technician Level II." |
| 10-43 | Table 1006-02 | Replace Table 1006-02 with the Table 1006-02 below. |
| 1A - 20A | Pay Item Index | Replace the Pay Item Index in its entirety. |

**Table 1006-2:
Overlay Mixtures**

Mixture Type	Aggregate	Slump (inch)	Air Content	Admixture Required	Mixture Proportions lb/yd ³ , dry weight					
					Cement ^(a)	Dry Densified Silica Fume ^(b)	Net Mix Water	Fine Agg	Coarse Agg	Latex Admixture
SFMC	2NS and 26A ^(c)	4–6	6.5 ±1.5%	(d),(e),(f)	618	40	273 ^(g)	1273	1601	—
LMC	2NS and 26A ^(c)	(h)	4.5 ±1.5%	—	658	—	(h)	1490 ^{(i),(j)}	1300 ^{(i),(j)}	206

(a) Use only Type I Portland cement.

(b) For SFMC mixtures, the Contractor may use a blended silica fume Portland cement. However, if the silica fume content of the blended material is greater than 8% of the total cementitious material, submit to the Engineer modified mix proportions with Type I Portland cement added to the blended material to achieve the equivalent individual cementitious material mixture proportions.

(c) Provide coarse aggregate, 95% minimum crushed materials in accordance with Michigan Test Method (MTM) 117, with an absorption no greater than 2.5%, in accordance with ASTM C127.

(d) Water-reducing high-range admixture or water-reducing high-range and retarding admixture.

(e) Virgin polypropylene collated fibers at 2 lb/yd³.

(f) Air-entraining admixture.

(g) Provide a net water to cementitious material ratio of 0.41 (cementitious material includes cement and silica fume).

(h) Add water in addition to water in the latex admixture to control slump to within 3 to 5 inches. Measure slump from 4 to 5 minutes after discharge from the mixer. During the waiting period, deposit concrete on the deck and do not disturb. If placing mixtures on sections within superelevated curves, the Contractor may need to use the lower allowable range of the slump requirement, as determined by the Engineer. Do not exceed water-cement ratio, by weight, of 0.30 including water contained in the latex emulsion.

(i) Aggregate proportions are approximate; due to gradation changes, the Contractor may increase proportions by no greater than 5% by weight of total aggregate if reducing coarse aggregate by an equivalent volume.


(j) Aggregate weights specified in the table are based on a dry bulk specific gravity of 2.65 for gravel and stone. Adjust the weights if the specific gravity of the materials used varies by more than 0.02 from the specified values.

MIDLAND COUNTY ROAD COMMISSION
 IN CO-OPERATION WITH
 MICHIGAN DEPARTMENT OF TRANSPORTATION
 AND
 FEDERAL HIGHWAY ADMINISTRATION
 PLANS OF PROPOSED
SAGINAW ROAD RESURFACING
 CONTROL SECTION: 56000 JOB NO: 214571

TRAFFIC DATA	SAGINAW ROAD	
YEAR	2024	2044
A.D.T.	8,102	10,912
D.H.V.	N.A.	N.A.
COMM. %	3.1%	3.1%

P.O.B. TO P.O.E.
 DESIGN SPEED 55 MPH

POSTED SPEED..... 55 MPH



INDEX OF PLANS

COVER SHEET	1
LOG OF PROJECT	2-7
TYPICAL CROSS SECTIONS	8-13
DETAILS	14-24
PAVEMENT MARKINGS	25-27
CRITICAL STATIONING	28-31

POINT OF BEGINNING
 STA 1203+18

POINT OF ENDING
 STA 1390+73



COUNTY KEY

THE IMPROVEMENTS COVERED BY THESE PLANS SHALL BE DONE IN ACCORDANCE WITH THE MICHIGAN DEPARTMENT OF TRANSPORTATION 2020 STANDARD SPECIFICATIONS FOR CONSTRUCTION AND THE 2017 EDITION OF THE MDOT LOCAL AGENCY PROGRAMS GUIDELINES FOR GEOMETRICS SECTION D PREVENTATIVE MAINTENANCE (PM).

THE PLACEMENT OF PAVEMENT MARKINGS AND SIGNS SHALL BE DONE IN ACCORDANCE WITH THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 2011 EDITION.

CONTRACT FOR: 3.60 MILES OF HMA MILLING AND RESURFACING, PAVEMENT MARKINGS, MISCELLANEOUS INTERSECTION IMPROVEMENTS, AND MAINTENANCE OF TRAFFIC.



**ROWE PROFESSIONAL
 SERVICES COMPANY**

127 S. Main Street
 Mt. Pleasant, MI 48858

O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com

**LOG OF PROJECT
SAGINAW ROAD RESURFACING
CONTROL SECTION: 56000
JOB NUMBER: 214571
Page 2 of 31**

LOCATION

Saginaw Road from Pinesboro Drive to the Midland City Limits within Homer and Lincoln Townships, Midland County.

The length of project is 3.60 miles long.

STA 1203+18 (P.O.B.) is the pavement joint located approximately 134 feet west of the intersection of Saginaw Road and Pinesboro Drive.

STA 1390+73 (P.O.E) is the pavement joint located at the Midland City Limits approximately 1,300 feet west of the intersection of Saginaw Road and Dublin Avenue.

DESCRIPTION OF WORK

Perform the proposed work in accordance with the standard specifications and the details, specifications, and special provisions contained within the proposal.

Throughout the project limits, perform the following work as directed by the Engineer:

Stark Road Right Turn Lane Taper Reconstruction

Remove HMA, excavate the existing aggregate base and place Approach, CI I, Modified within the right turn lane taper to northbound Stark Road to prepare for paving in accordance with the details in the proposal.

Construct curb and gutter and concrete spillways in accordance with the details in the proposal.

Wackerly Road Approach Realignment

Remove HMA and curb and gutter, excavate the existing aggregate base and place Approach, CI I, Modified within the East Wackerly Road intersection to prepare for paving in accordance with the details in the proposal.

Construct curb and gutter in accordance with the details in the proposal.

HMA Cold Milling and HMA Resurfacing

Cold mill the existing Saginaw Road mainline lanes as shown on the typicals and the paved side street approaches to an estimated depth of 1.5 inches. Cold mill side street approaches to the location shown on the plans, or to the limits as directed by the Engineer. **All milled surfaces must be paved within 48 hours of the milling operation. Resurface all milled areas prior to the end of day Friday unless Saturday work is approved by the Engineer.**

Surface the milled mainline lanes and milled side street approaches with HMA Bond Coat, at a rate of 0.05 to 0.15 gallons per syd and HMA at a rate of 165 lbs per syd, as detailed on the typical cross sections. Surface the reconstructed the right turn lane taper to northbound Stark Road with a leveling course at a rate of 275 lbs per syd and a top course at a rate of 165 lbs per syd, as detailed in the proposal. Place hand patching along the proposed curb at East Wackerly Road to match the pavement depth remaining after the cold milling operation and surface the intersection at a rate of 165 lbs per syd, as detailed in the proposal.

Placing HMA Approach - Surface side street approaches to the dimensions as shown on the detail sheets in the proposal. The payment for HMA Approach includes all HMA side street approaches to the spring point, or to the limits as directed by the Engineer.

Hand Patching - Fill joints, cracks, holes, and depressions in the existing surface. Place hand patching at variable rates. Use hand patching to provide temporary tapered ramps to approaches, or to taper the surface to meet utility and drainage structures, or any similar use as directed by the Engineer.

Aggregate Shoulders

Place Shld, CI II, Modified in accordance with the typical cross sections following HMA paving. Place and compact aggregate shoulder flush with HMA edge.

Center Line Corrugations

Place sinusoidal centerline corrugations in accordance with standard plan R-112-Series, with the corrugation profile as shown in the special provision for sinusoidal corrugations.

Center line corrugations to extend from STA 1203+18 (P.O.B.) to STA 1281+59, STA 1319+97 to STA 1339+06, and STA 1347+27 to STA 1389+23.

Pavement Markings

Inventory all existing pavement markings from STA 1203+18 (P.O.B.) to STA 1281+59 and STA 1319+97 to STA 1390+73 (P.O.E.) and provide a copy to the Engineer one (1) week prior to commencing any construction operations.

Do not commence any cold milling operations prior to the approval of the said inventory by the Engineer. The cost associated with the inventory is included in the pay item "Witness, Log, \$1,250.00".

Place proposed two-way left-turn lane pavement markings from STA 1281+59 to STA 1319+97 as detailed in the proposal and in accordance with the standard plans.

Apply permanent pavement markings after all paving has been completed.

Maintenance of Traffic

Maintain traffic in accordance with the Special Provision for Maintaining Traffic.

ITEMS OF WORK

The following items of work apply to Saginaw Road resurfacing as detailed in this Proposal and as directed by the Engineer.

Pay Item Description	Quantity	Units
Mobilization, Max \$104,200	1	LSUM
Curb and Gutter, Rem	108	Ft
Embankment, CIP	36	Cyd
Excavation, Earth	260	Cyd
Erosion Control, Silt Fence	500	Ft

Pay Item Description	Quantity	Units
Subbase, CIP	28	Cyd
Approach, CI I, Modified	166	Ton
Shld, CI II, Modified	810	Ton
Dr Structure Cover, Adj, Case 1	1	Ea
Cold Milling HMA Surface	90370	Syd
HMA Surface, Rem	678	Syd
Hand Patching	100	Ton
HMA Approach	522	Ton
HMA, 5EML	7817	Ton
Curb and Gutter, Conc, Det B2	192	Ft
Shld Gutter, Conc, Det 2	1	Ea
Shld Gutter, Conc, Det 3	1	Ea
Spillway, Conc	9	Ft
Post, Mailbox	1	Ea
Post, Steel, 3 pound	45	Ft
Sign, Type III, Erect, Salv	4	Ea
Reflective Panel for Permanent Sign Support, 6 Foot	2	Ea
Sign, Type III, Rem, Salv	4	Ea
Ground Mtd Sign Support, Rem	2	Ea
Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	45	Ft
Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	4	Ea
Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	3	Ea
Pavt Mrkg, Waterborne, 4 inch, White	37578	Ft
Pavt Mrkg, Waterborne, 4 inch, Yellow	20545	Ft
Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	37578	Ft
Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	20545	Ft
Witness, Log, \$1,250.00	1250	Dlr
Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8	Ea
Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8	Ea
Channelizing Device, 42 inch, Fluorescent, Furn	250	Ea
Channelizing Device, 42 inch, Fluorescent, Oper	250	Ea
Lighted Arrow, Type C, Furn	2	Ea
Lighted Arrow, Type C, Oper	2	Ea
Minor Traf Devices	1	LSUM
Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	33	Ft
Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	2827	Ft
Sign Cover	5	Ea
Sign, Type B, Temp, Prismatic, Furn	804	Sft
Sign, Type B, Temp, Prismatic, Oper	804	Sft

Pay Item Description	Quantity	Units
Sign, Type B, Temp, Prismatic, Spec, Furn	10	Sft
Sign, Type B, Temp, Prismatic, Spec, Oper	10	Sft
Traf Regulator Control	1	LSUM
Riprap, Plain	11	Syd
Slope Restoration, Non-Freeway, Type B	180	Syd
Monument Box	1	Ea
Monument Box Adj	1	Ea
Sinusoidal Corrugations, Milled, HMA Centerline	13403	Ft
Gate Box, Adj, Case 1	1	Ea

GENERAL NOTES

1. Mill to edge of mainline roadway at driveways. All costs are included in the pay items Cold Milling HMA Surface and HMA, 5EML. See detail on sheet 23.
2. Pave gravel driveways 1 foot wider than the edge of roadway during mainline paving. All costs included in the pay item HMA, 5EML. See detail on sheet 23.
3. Construct butt joints at paving limits as shown on sheet 24 or as directed by the Engineer.
4. Earthwork quantities are estimated without survey information. These quantities are for bidding purposes only and will be adjusted by the Engineer based upon actual field measurements.
5. Appropriate soil erosion and sedimentation control measures shall be in place prior to earth disturbing activities. Place turf establishment items as soon as possible on potential erodible slopes as directed by the Engineer.
6. A miscellaneous quantity of silt fence has been included to be placed at locations as directed by the engineer.
7. Use aggregate 21AA for aggregate bases unless otherwise specified.
8. Broom off the gravel from existing intersections that are to be paved prior to placing the bond coat. This work is included in the pay item HMA Approach.
9. Preserve all corners within the project limits, whether shown or not. Adjust monument boxes as required. A miscellaneous quantity of Monument Box has been included to be placed at locations as directed by the Engineer.
10. Contact MISS DIG System, Inc. for the protection of underground utilities and in conformance with MCL 460.721 et seq, by phone at 811 or 800-482-7171 or via the web at either elocate.missdig.org for single address or rte.missdig.org, a minimum of 3 working days prior to excavating, excluding weekends and holidays.
11. Notify the Engineer 24 hours in advance of the establishment of lane closures.

12. The Engineer will be responsible for notifying emergency services, transit agencies, law enforcement and schools prior to any lane closures.

<u>Response Agency</u>	<u>Telephone Number</u>
Midland County Road Commission	989-687-9060
Midland County Central Dispatch	989-839-6464
Midland County Sheriff	989-839-4600
Homer Township Fire Department	989-832-8034
Lincoln Township Fire Department	989-687-7333
Midland Public Schools	989-923-5001
Meridian Public Schools	989-687-3200

13. Proposed callouts in log:


<u>Topo Callout</u>	<u>Description</u>
ADJ	Adjust Structure
R&R	Remove and Replace
SALV	Salvage

NOTES APPLYING TO STANDARD PLANS

Where the following items are called for on plans, they are to be constructed according to the standard plan given below opposite each item unless otherwise indicated.

Title	Plan No.
ROAD	
MONUMENT BOXES	R-11-E
CONCRETE CURB AND CONCRETE CURB & GUTTER	R-30-G
CONCRETE SHOULDER GUTTER AND SPILLWAY	R-35-E
SOIL EROSION & SEDIMENTATION CONTROL MEASURES	R-96-E
SEEDING AND TREE PLANTING	R-100-I *
SUPERELEVATION AND PAVEMENT CROWNS	R-107-H
SHOULDER AND CENTER LINE CORRUGATIONS	R-112-J *
PAVEMENT MARKINGS	
PAVEMENT ARROW & MESSAGE DETAILS	PAVE-900-G
TEMPORARY LONGITUDINAL LINE TYPES & PLACEMENT	PAVE-904-B *
LONGITUDINAL LINE TYPES & PLACEMENT	PAVE-905-E
PAVEMENT MARKINGS FOR NON-SIGNALIZED INTERSECTIONS	PAVE-930-D
LEFT TURN LANE MARKINGS	PAVE-935-E
RIGHT TURN LANE AND ISLAND PAVEMENT MARKINGS	PAVE-940-D
INTERSECTION, STOP BAR, & CROSSWALK MARKINGS	PAVE-945-D
SIGNING	
STANDARD SIGN INSTALLATIONS	SIGN-100-G
ROADSIDE SIGN LOCATIONS & SUPPORT SPACING	SIGN-120-E
PLACEMENT OF D3-1 SIGNS ABOVE R1-1	SIGN-140-A
SIGN SUPPORT SELECTION CHARTS	SIGN-150-D
STEEL POSTS	SIGN-200-E

* Denotes Special Detail included in the Proposal



EXISTING & PROPOSED CROSS SECTION

STA 1203+18 (P.O.B.) TO STA 1226+35
 STA 1242+56 TO STA 1281+59
 STA 1319+97 TO STA 1341+06
 STA 1350+48 TO STA 1389+23

PROFILE MILL 1.5" DEPTH AT EDGE OF TRAVELED WAY AND HOLD +2% TO THE CROWN POINT. MATCH MILL DEPTH AT THE CROWN AND MILL OPPOSING BOUND -2%. MATCH MILL DEPTH AT EDGE OF TRAVELED WAY AND MILL SHOULDERS AT -4%.

TRANSITION NOTE

TRANSITION BETWEEN 1.5" MILL DEPTH AT EDGE OF TRAVELED WAY AND 1.5" MILL DEPTH AT CROWN POINT OVER 100 FEET.

EXISTING & PROPOSED APPROACH TAPERS

SEE DETAIL SHEETS

IDENT NO.	ITEM	RATE	PERFORMANCE GRADE	REMARKS
5EML	HMA, 5EML	165 #/SYD MIN	64-28	AWI=260 TOP COURSE
HP	Hand Patching	VARIES	64-28	5EML FOR PAVEMENT REPAIRS. MATCH DEPTH OF MILLED HMA AT WACKERLY RD
HA-T	HMA Approach	VARIES	64-28	SIDE STREET APPROACHES MATCH MAINLINE APPLICATION RATE (HMA, 5EML)
HA-L	HMA Approach	VARIES	64-28	HMA 4EML AT 275 #/SYD MAX AT STARK RD RIGHT TURN LANE_RECONSTRUCT
	HMA BOND COAT	0.05 to 0.15 GAL/SYD		FOR INFORMATION ONLY


NOTE: FOR SHOULDERS ONLY THE MIX DESIGN AND/OR JMF TARGET VALUE FOR AIR VOIDS ARE TO BE ADJUSTED TO 2.5 PERCENT.



127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 TYPICAL CROSS SECTION

PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 8



TRANSITION NOTE

TRANSITION BETWEEN 1.5" MILL DEPTH AT EDGE OF TRAVELED WAY AND 1.5" UNIFORM MILL DEPTH OVER 100 FEET.

MILL TO A UNIFORM DEPTH OF 1.5". PAID FOR AS Cold Milling HMA Surface

EXISTING & PROPOSED SUPERELEVATED SECTION

STA 1226+35 TO STA 1242+56


Shld, Cl II, Modified PLACED AT AN AVERAGE THICKNESS OF 3" (TYP)



127 S. Main Street
Mt. Pleasant, MI 48858
O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
TYPICAL CROSS SECTION

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 9




TRANSITION NOTE
 TRANSITION BETWEEN 1.5" MILL DEPTH AT EDGE OF TRAVELED WAY AND 1.5" MILL DEPTH AT CROWN POINT OVER 100 FEET.

PROFILE MILL 1.5" DEPTH AT CROWN POINT AND HOLD -2% TO THE EDGE OF THE TRAVELED WAY. MATCH MILL DEPTH AT THE CROWN AND MILL OPPOSING BOUND -2%. MATCH MILL DEPTH AT EDGE OF TRAVELED WAY AND MILL SHOULDERS AT -4%.


EXISTING & PROPOSED CROSS SECTION

STA 1281+59 TO STA 1319+97



EX CURB AND GUTTER

STA 1287+12 TO STA 1289+14
 STA 1308+33 TO STA 1308+81



EXISTING & PROPOSED APPROACH TAPERS

SEE DETAIL SHEETS



127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 TYPICAL CROSS SECTION

PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 10

EXISTING 150' ROW

CONSTRUCTION CONTROL LINE

LIMITS OF Cold Milling HMA Surface AND HMA Overlay (VARIES 40' - 56')



EXISTING & PROPOSED CROSS SECTION

STA 1341+06 TO STA 1343+58

PROFILE MILL 1.5" DEPTH AT EDGE OF TRAVELED WAY AND HOLD +2% TO THE CROWN POINT. MATCH MILL DEPTH AT THE CROWN AND MILL OPPOSING BOUND -2%. MATCH MILL DEPTH AT EDGE OF TRAVELED WAY AND MILL SHOULDERS AT -4%.

Shld, Cl II, Modified PLACED AT AN AVERAGE THICKNESS OF 3"

TRANSITION NOTE

- A** VARIES FROM 9' AT STA 1341+06 TO 14' AT STA 1343+58
- B** VARIES FROM 0' AT STA 1339+06 TO 12' AT STA 1343+58



127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
TYPICAL CROSS SECTION

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 11

EXISTING 150' ROW

CONSTRUCTION CONTROL LINE

LIMITS OF Cold Milling HMA Surface AND HMA Overlay (VARIES 40'-56')




EXISTING & PROPOSED CROSS SECTION

STA 1343+58 TO STA 1350+48

Shld, Cl II, Modified
PLACED AT AN AVERAGE
THICKNESS OF 3"


PROFILE MILL 1.5" DEPTH AT
EDGE OF TRAVELED WAY AND
HOLD +2% TO THE CROWN
POINT. MATCH MILL DEPTH
AT THE CROWN AND MILL
OPPOSING BOUND -2%.
MATCH MILL DEPTH AT EDGE
OF TRAVELED WAY AND MILL
SHOULDERS AT -4%.

EX CURB & GUTTER
TO BE REMOVED. SEE
DETAIL ON SHEET 22



CURBED RIGHT TURN LANE RECONSTRUCT

SEE SHEET 22 FOR DETAIL



TRANSITION NOTE

- C** VARIES FROM 14' AT STA 1343+58 TO 13' AT STA 1345+73
13' FROM STA 1345+73 TO STA 1348+23
VARIES FROM 13' AT STA 1348+23 TO 9' AT STA 1350+48
- D** 12' FROM STA 1343+58 TO STA 1348+23
VARIES FROM 12' AT STA 1348+23 TO 0' AT STA 1350+48

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 TYPICAL CROSS SECTION




127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 12

EXISTING 150' ROW

CONSTRUCTION CONTROL LINE

LIMITS OF Cold Milling HMA Surface AND HMA OVERLAY (VARIES 40'-54')



PROFILE MILL 1.5" DEPTH AT EDGE OF TRAVELED WAY AND HOLD +2% TO THE CROWN POINT. MATCH MILL DEPTH AT THE CROWN AND MILL OPPOSING BOUND -2%. MATCH MILL DEPTH AT EDGE OF TRAVELED WAY AND MILL SHOULDERS AT -4%.

EXISTING & PROPOSED CROSS SECTION

STA 1389+23 TO STA 1390+73 (P.O.E.)

Shld, CI II, Modified
PLACED AT AN AVERAGE
THICKNESS OF 3" (TYP)

TRANSITION NOTE

- E** VARIES FROM 9' AT STA 1389+23 TO 5' AT STA 1390+73 (P.O.E.)
- F** VARIES FROM 11' AT STA 1389+23 TO 19' AT STA 1390+73 (P.O.E.)
- G** VARIES FROM 0' AT STA 1389+23 TO 5' AT STA 1390+73 (P.O.E.)




127 S. Main Street
Mt. Pleasant, MI 48858


O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
TYPICAL CROSS SECTION

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 13



**LIMITS OF PAVING
AT N PINESBORO DRIVE**



**LIMITS OF PAVING
AT N 5 MILE ROAD**



MAINLINE
PAVING



HMA
APPROACH



**ROWE PROFESSIONAL
SERVICES COMPANY**


127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 14

SAGINAW ROAD



**LIMITS OF PAVING
AT N BURRELL STREET**



**LIMITS OF PAVING
AT N GREEN MEADOW STREET**




ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858


O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 15



**LIMITS OF PAVING
AT N DIANA DRIVE**



 MAINLINE PAVING

 HMA APPROACH

**LIMITS OF PAVING
AT E SANFORD ROAD AND FARMER ROAD**




ROWE PROFESSIONAL SERVICES COMPANY


127 S. Main Street
Mt. Pleasant, MI 48858
O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS
SHEET NO:	16

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET



**LIMITS OF PAVING
AT N KETCHUM ROAD**



 MAINLINE PAVING

 HMA APPROACH

**LIMITS OF PAVING
AT DALLAS ROAD**




 **ROWE PROFESSIONAL SERVICES COMPANY**

127 S. Main Street
Mt. Pleasant, MI 48858


O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET


PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 17



**LIMITS OF PAVING
AT FRANCIS STREET**



**LIMITS OF PAVING
AT E WACKERLY ROAD**

-  MAINLINE PAVING
-  HMA APPROACH




ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858


O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 18



**LIMITS OF PAVING
AT N HOPE ROAD**



**LIMITS OF PAVING
AT E PIONEER TRAIL**



MAINLINE
PAVING



HMA
APPROACH

SEE COLD MILLING BUTT JOINT
DETAIL ON SHEET 24



**ROWE PROFESSIONAL
SERVICES COMPANY**

127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 19

SEE COLD MILLING BUTT JOINT
DETAIL ON SHEET 24

N OLD OAK
TRAIL

EX CONC PAVT
TO REMAIN

EX CURB & GUTTER
TO REMAIN (TYP)

SAGINAW ROAD

SEE COLD MILLING BUTT JOINT
DETAIL ON SHEET 24 (TYP)

**LIMITS OF PAVING
AT N OLD OAK TRAIL**

TITTABAWASSEE
RIVER ROAD

EX CURB & GUTTER
TO REMAIN (TYP)

SAGINAW ROAD

**LIMITS OF PAVING
AT TITTABAWASSEE
RIVER ROAD**

 MAINLINE
PAVING

 HMA
APPROACH



**ROWE PROFESSIONAL
SERVICES COMPANY**


127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 20


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
DETAIL SHEET

HMA REMOVAL NOTE:
 REMOVE A MINIMUM OF 2' OF
 HMA IN FRONT OF THE PROPOSED
 CURB AND GUTTER OR AS
 DIRECTED BY THE ENGINEER.



**E WACKERLY ROAD
 REMOVALS**

 HMA SURFACE REMOVE



**E WACKERLY ROAD
 PROPOSED**

SEE SHEET 24 FOR REMOVAL AND
 PROPOSED CROSS SECTIONS




ROWE PROFESSIONAL SERVICES COMPANY
 127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com




PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 DETAIL SHEET


PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 21

CAUTION
HAZARDOUS
FLAMMABLE MATERIAL
UNDERGROUND



SAGINAW ROAD REHABILITATION DETAIL

-  MAINLINE PAVING
-  HMA APPROACH
-  HMA APPROACH (RECONSTRUCT)



PROPOSED PAVEMENT MARKINGS AT N STARK ROAD




ROWE PROFESSIONAL SERVICES COMPANY


127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 DETAIL SHEET


PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 22




**TYPICAL MAINLINE
PAVING AT HMA AND
CONC DRIVEWAYS**



**TYPICAL MAINLINE
PAVING AT GRAVEL AND
FIELD DRIVEWAYS**



UNCURBED INTERSECTION DETAIL



CURBED INTERSECTION DETAIL





ROWE PROFESSIONAL SERVICES COMPANY
 127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 DETAIL SHEET

PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 23

HMA REMOVAL NOTE:
 REMOVE A MINIMUM OF 2' OF
 HMA IN FRONT OF THE PROPOSED
 CURB AND GUTTER OR AS
 DIRECTED BY THE ENGINEER.



E WACKERLY ROAD
PARTIAL SECTIONS



COLD MILLING NOTES

1. BUTT JOINTS TO BE MILLED AT 1.5" UNIFORM DEPTH
2. APPLIES TO INTERSECTIONS AND MAINLINE P.O.B. AND P.O.E.

BUTT JOINT DETAIL



ROWE PROFESSIONAL SERVICES COMPANY
 127 S. Main Street
 Mt. Pleasant, MI 48858
 O: (989) 772-2138
 F: (989) 773-7757
 www.rowepsc.com



PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
 SAGINAW ROAD RESURFACING
 DETAIL SHEET

PLAN NO. 21M0087
 DATE: AUGUST 2023
 PROJECT MGR: MJS
 REVIEWER: TCL
 SCALE: NTS SHEET NO: 24

MATCH LINE STA 1288+00 - SEE LOWER RIGHT

MATCH LINE STA 1294+50 - SEE SHEET 26

N OLD OAK TRAIL



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858



O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
PAVEMENT MARKING SHEET

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 25

MATCH LINE STA 1301+50 - SEE LOWER RIGHT

MATCH LINE STA 1308+00 - SEE SHEET 27



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
PAVEMENT MARKING SHEET

PLAN NO.	21M0087
DATE:	AUGUST 2023
PROJECT MGR:	MJS
REVIEWER:	TCL
SCALE:	NTS SHEET NO: 26

MATCH LINE STA 1314+00 - SEE LOWER RIGHT

TITTABAWASSEE RIVER ROAD

1313+00

Pavt Mrkg, Waterborne, 4 inch, Yellow (555 FT) SOLID AND SKIP LINES

1312+00

Pavt Mrkg, Waterborne, 4 inch, White (343 FT) (TYP)

Pavt Mrkg, Waterborne, 4 inch, White (405 FT) (TYP)

1311+00

1310+00

E WACKERLY ROAD

SAGINAW ROAD

NOTE: SEE SHEET 21 FOR E WACKERLY ROAD DETAIL

1309+00

Pavt Mrkg, Ovlv Cold Plastic, Lt Turn Arrow Sym

Pavt Mrkg, Waterborne, 4 inch, Yellow (145 FT) SOLID AND SKIP LINES

Pavt Mrkg, Waterborne, 4 inch, White (125 FT)

1308+00

MATCH LINE STA 1308+00 - SEE SHEET 26

PROP PAVEMENT MARKINGS TO MATCH EXISTING LAYOUT AS LOGGED

1320+00

+97

1319+00

Pavt Mrkg, Waterborne, 4 inch, Yellow (1165 FT) DOUBLE SOLID LINES

1318+00

Pavt Mrkg, Waterborne, 4 inch, White (553 FT)

1317+00

+94

Pavt Mrkg, Waterborne, 4 inch, Yellow (625 FT) SOLID AND SKIP LINES

1316+00

1315+00

Pavt Mrkg, Waterborne, 4 inch, White (591 FT)

TITTABAWASSEE RIVER ROAD

1314+00

MATCH LINE STA 1314+00 - SEE UPPER LEFT



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street Mt. Pleasant, MI 48858



O: (989) 772-2138 F: (989) 773-7757 www.rowepsco.com

PREPARED FOR: MIDLAND COUNTY ROAD COMMISSION SAGINAW ROAD RESURFACING PAVEMENT MARKING SHEET

PLAN NO. 21M0087 DATE: AUGUST 2023 PROJECT MGR: MJS REVIEWER: TCL SCALE: NTS SHEET NO: 27

MATCH LINE STA 1227+00 - SEE LOWER RIGHT

MATCH LINE STA 1249+00 - SEE SHEET 29



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858
O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
CRITICAL STATIONING

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 28

MATCH LINE STA 1274+00 - SEE LOWER RIGHT

STA 1273+84 - GRAVEL DRIVE

STA 1271+26 - HMA DRIVE

1270+00

STA 1269+98 - HYDRANT

STA 1268+65 - MAILBOX
STA 1268+48 - GRAVEL DRIVE

STA 1267+92 - 24" CULVERT

STA 1267+92 - 24" CULVERT

CONSTRUCTION CONTROL LINE

STA 1265+72 - MAILBOX
STA 1265+20 - HMA DRIVE

1265+00

STA 1264+20 - SIGN

SAGINAW ROAD

STA 1262+05 - GRAVEL DRIVE

STA 1261+70 - MAILBOX (2)

1260+00

STA 1259+98 - GRAVEL DRIVE
STA 1259+07 - HMA DRIVE

STA 1258+72 - MAILBOX
STA 1257+92 - 18" CULVERT

STA 1257+92 - 18" CULVERT
STA 1257+77 - SIGN

STA 1257+77 - SIGN

STA 1257+77 C/L
E PIONEER TRL

STA 1256+75 - SIGN
STA 1256+64 - HYDRANT
STA 1256+43 - SIGN

STA 1257+50 - MAILBOX

STA 1255+50 - HMA DRIVE

1255+00

STA 1254+58 - HMA DRIVE
STA 1254+38 - MAILBOX (2)

STA 1253+85 - HMA DRIVE
STA 1253+31 - HMA DRIVE

STA 1252+48 - GRAVEL DRIVE
STA 1252+43 - GRAVEL DRIVE
STA 1252+01 - MAILBOX (2)

STA 1250+80 - HMA DRIVE

STA 1250+00 C/L
N HOPE RD

1250+00

STA 1249+60 - SIGN

STA 1251+83 - SIGN
STA 1251+58 - AVERILL ROLLWAY TRAILHEAD

STA 1249+43 - SIGN

STA 1249+20 C/L
E WACKERLY RD

MATCH LINE STA 1249+00 - SEE SHEET 28



MATCH LINE STA 1298+00 - SEE SHEET 30

STA 1297+23 - MAILBOX

STA 1296+45 - HMA DRIVE

STA 1295+74 - HYDRANT

1295+00

CONSTRUCTION CONTROL LINE

STA 1291+33 - GRAVEL DRIVE

1290+00

STA 1289+98 - HYDRANT

STA 1288+52 - MAILBOX
STA 1288+33 - GRAVEL DRIVE

STA 1287+58 - END C&G

STA 1286+06 C/L
N OLD OAK TRL

STA 1286+06 - MANHOLE
STA 1285+52 - BEGIN C&G

1285+00

STA 1284+33 - HMA DRIVE
STA 1284+07 - MAILBOX

STA 1283+28 - HYDRANT

STA 1281+59 - BEGIN CENTER LEFT TURN LANE
STA 1281+58 - HMA DRIVE

STA 1280+77 - 30" CULVERT
STA 1280+50 - FIELD DRIVE

1280+00

STA 1280+77 - 30" CULVERT

STA 1277+95 - MAILBOX
STA 1277+48 - HMA DRIVE

STA 1276+32 - FIELD DRIVE
STA 1276+17 - 18" CULVERT

1275+00

STA 1276+17 - 18" CULVERT

STA 1274+79 - MAILBOX (3)
STA 1274+60 - GRAVEL DRIVE

MATCH LINE STA 1274+00 - SEE UPPER LEFT



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
CRITICAL STATIONING

170

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 29

MATCH LINE STA 1323+00 - SEE LOWER RIGHT

MATCH LINE STA 1347+00 - SEE SHEET 31

STA 1322+77 - HMA DRIVE

STA 1346+35- BEGIN RIGHT TURN TAPER

STA 1319+97 - END CENTER LEFT TURN LANE
STA 1319+70 - MAILBOX
STA 1319+43 - GRAVEL DRIVE

STA 1345+93 - HMA DRIVE
STA 1345+46 - SIGN SALV
STA 1345+19 - 24" CULVERT
STA 1344+90 - HMA DRIVE

1320+00

STA 1316+53 - SIGN

STA 1343+08 C/L
N STARK RD

STA 1343+64 - 24" CULVERT

1315+00

STA 1314+97 - HMA DRIVE

STA 1342+96 - MANHOLE ADJ

1340+00

STA 1340+96 - MAILBOX
STA 1340+74 - HMA DRIVE

STA 1339+06 - SIGN

STA 1313+08 - HMA DRIVE

CONSTRUCTION CONTROL LINE

STA 1339+06 - BEGIN CENTER LEFT TURN LANE
STA 1339+06 - MAILBOX
STA 1338+66 - HMA DRIVE

1335+00

STA 1311+53 C/L
TITABAWASSEE RIVER RD
STA 1311+28 - SIGN

STA 1312+33 - SIGN
STA 1311+93 C/L
TITABAWASSEE RIVER RD

CONSTRUCTION CONTROL LINE

STA 1337+30- MAILBOX
STA 1337+07 - GRAVEL DRIVE

1330+00

STA 1307+56 C/L
W WACKERLY RD

STA 1307+28 - SIGN SALV

STA 1335+13 - MAILBOX
STA 1334+87 - GRAVEL DRIVE

SAGINAW ROAD

STA 1333+53 - HYDRANT
STA 1333+30 - HMA DRIVE

1305+00

STA 1306+75 - GAS LINE MARKER
STA 1306+34 - HMA APPROACH

STA 1305+88 - MAILBOX
STA 1305+08 - SIGN

STA 1331+39 - MAILBOX
STA 1331+12 - HMA DRIVE

1300+00

STA 1302+50 - SIGN

STA 1326+92 - SIGN
STA 1326+11 - GRAVEL DRIVE
STA 1325+90 - MAILBOX

1325+00

STA 1301+56 - GRAVEL DRIVE
STA 1301+37 - MAILBOX

STA 1300+77 - GRAVEL DRIVE

STA 1324+33 - GRAVEL DRIVE
STA 1324+11 - MAILBOX

STA 1299+81 - HMA DRIVE

STA 1323+05 - MAILBOX

MATCH LINE STA 1323+00 - SEE UPPER LEFT

MATCH LINE STA 1298+00 - SEE SHEET 29



ROWE PROFESSIONAL SERVICES COMPANY

127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com

PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
CRITICAL STATIONING

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 30

MATCH LINE STA 1371+00 - SEE LOWER RIGHT

STA 1370+12 - FIELD DRIVE

1370+00

STA 1366+46 - SIGN

1365+00

CONSTRUCTION CONTROL LINE

1360+00

SAGINAW ROAD

STA 1357+32 - GRAVEL DRIVE
STA 1356+95 - MAILBOX

1355+00

STA 1354+68 - GRAVEL DRIVE
STA 1354+53 - MAILBOX

STA 1353+83 - FIELD DRIVE
STA 1353+09 - GRAVEL DRIVE
STA 1352+77 - MAILBOX

STA 1350+53 - HMA DRIVE

1350+00

STA 1348+60 - END RIGHT TURN TAPER

STA 1347+80 - MAILBOX
STA 1347+51 - HMA DRIVE
STA 1347+27 - END CENTER LEFT TURN LANE

1347+00

MATCH LINE STA 1347+00 - SEE SHEET 30



1394+86

P.O.E. STA 1390+73

1390+00

STA 1389+23 - BEGIN CENTER LEFT TURN LANE

STA 1387+23 - SIGN

CONSTRUCTION CONTROL LINE

1385+00

STA 1386+07 - MAILBOX
STA 1385+90 - GRAVEL DRIVE
STA 1385+43 - HYDRANT

STA 1385+67 - SIGN

STA 1384+20 - MAILBOX
STA 1384+01 - CONC DRIVE

SAGINAW ROAD

STA 1383+48 - MAILBOX
STA 1383+22 - HMA DRIVE

1380+00

STA 1381+37 - MAILBOX
STA 1380+99 - HMA DRIVE

STA 1377+12 - SIGN
STA 1377+04 - MAILBOX
STA 1376+65 - HMA DRIVE
STA 1376+31 - FIELD DRIVE

1375+00

STA 1375+47 - MAILBOX
STA 1375+13 - GRAVEL DRIVE

STA 1373+99 - FIELD DRIVE
STA 1373+75 - HYDRANT
STA 1373+25 - MAILBOX

STA 1372+88 - HMA DRIVE

STA 1371+66 - SIGN
STA 1371+42 - DUCK HUNTERS MEMORIAL

MATCH LINE STA 1371+00 - SEE UPPER LEFT




127 S. Main Street
Mt. Pleasant, MI 48858

O: (989) 772-2138
F: (989) 773-7757
www.rowepsc.com


PREPARED FOR:
MIDLAND COUNTY ROAD COMMISSION
SAGINAW ROAD RESURFACING
CRITICAL STATIONING

PLAN NO. 21M0087
DATE: AUGUST 2023
PROJECT MGR: MJS
REVIEWER: TCL
SCALE: NTS SHEET NO: 31




MULCH BLANKET ON GUARDRAIL FILL SLOPE

DETAIL A




TYPICAL SLOPE AND DITCH PROTECTION




MULCH BLANKET SPILLWAY DITCH


* NOTE:

MULCH BLANKET SHALL BE USED ON BOTH SIDES OF NORMAL SECTIONS, HIGH SIDES OF ALL SUPERELEVATED SECTIONS, AND LOW SIDES OF PAVEMENTS HAVING A SUPERELEVATION OF 5% OR LESS. HIGH VELOCITY MULCH BLANKET SHALL BE USED ON THE LOW SIDE OF PAVEMENTS HAVING A RATE OF SUPERELEVATION GREATER THAN 5%.

 PREPARED BY DESIGN DIVISION DRAWN BY: <u>B.L.T.</u> CHECKED BY: <u>W.K.P.</u>	DEPARTMENT DIRECTOR Paul C. Ajegba APPROVED BY: _____ DIRECTOR, BUREAU OF FIELD SERVICES	MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR SEEDING AND TREE PLANTING	
	APPROVED BY: _____ DIRECTOR, BUREAU OF DEVELOPMENT 173	F.H.W.A. APPROVAL	8-3-2021 PLAN DATE




BRACING - VERTICAL STAKES



BRACING DETAIL


BRACE DECIDUOUS TREES 2" TO 4" IN CALIPER OR 8' OR MORE IN HEIGHT WITH TWO STAKES.

BRACE DECIDUOUS TREES LESS THAN 2" IN CALIPER OR 8' IN HEIGHT WITH ONE STAKE ON THE WESTERLY SIDE OF THE PLANT.




TRIPOD GUYING DETAIL

GUY EVERGREENS OVER 4" IN CALIPER OR 6' IN HEIGHT WITH THE TRIPOD METHOD AND UNDER 6' IN HEIGHT WITH TWO STAKES.



GUYING - TRIPOD METHOD




SLOPE PLANTING

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR


**SEEDING
AND TREE PLANTING**

	8-3-2021 PLAN DATE	R-100-I	SHEET 2 OF 4
174	F.H.W.A. APPROVAL		



RAISED SHRUB BED DETAIL

SHRUB BED EDGING DETAIL



SHRUB BED DETAIL

FIRST AND SECOND WATERING AND CULTIVATION SHALL INCLUDE SHRUB BEDS.

CUT 6" X 12" (MIN.) EDGING AROUND THE PERIMETER OF ALL SHRUB BEDS SHOWN ON THE PLANS. SPRAY A NON-PERSISTANT GLYPHOSATE HERBICIDE TO ENTIRE SHRUB BEDS PRIOR TO PLANTING AND BARK PLACEMENT.

SHRUB BEDS ARE TO BE PAID FOR BY THE PAY ITEM 'SITE PREPARATION'.

ALL PLANTS SHALL BE SET PLUMB AND HAVE THE BEST SIDE OF PLANT FACING THE MAIN VIEWING DIRECTION.

PLANTING NOTES:

ALL EXCAVATED MATERIAL SHALL BE REMOVED FROM THE SITE - IMMEDIATELY.

LOOSEN SUBSOIL TO A DEPTH OF 4". LOOSEN EARTH ON SIDES OF PLANT POCKET TO BREAK ANY GLAZING CAUSED BY DIGGING.

FILL PREPARED SOIL TO 1/2 THE DEPTH OF THE ROOT BALL, PACK FIRMLY, AND PUDDLE WITH WATER.


BACKFILL WITH PREPARED SOIL WHICH, AFTER COMPACTION, IS FLUSH WITH SURROUNDING GROUND LEVEL.

COVER ENTIRE PLANT POCKET AREA WITH 4" MULCH. PRUNE AND BRACE AND GUY.

WHEN PLANTS ARE FURNISHED IN CONTAINERS, CONTAINERS SHALL BE COMPLETELY REMOVED AT THE TIME OF PLANTING.

TREE HEIGHTS ARE SHOWN BEFORE PRUNING. TREE PLANTING DEPTHS ARE SHOWN AFTER SETTLING.

TREES AND SHRUBS SHALL NOT BE PLANTED WITHIN 50' AND 30' RESPECTIVELY OF THE NEAREST EDGE OF METAL - EXCEPT WHERE INACCESSIBLE TO VEHICLES.




MULTIPLE STEM TREES


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

**SEEDING
AND TREE PLANTING**

F.H.W.A. APPROVAL	8-3-2021 PLAN DATE	R-100-I	SHEET 3 OF 4
-------------------	-----------------------	---------	-----------------



MEDIAN PLANTING
NOT TO SCALE



BARE ROOT PLANTS

PLANTING BARE ROOT PLANT MATERIAL

REFER TO THE "SPECIAL PROVISIONS FOR BARE ROOT PLANTING" FOR SHIPPING, STORAGE AND HANDLING REQUIREMENTS.

MAINTAIN ROOT MOISTURE BY KEEPING ROOTS IMMersed IN WATER PRIOR TO PLANTING.


ROOT PRUNE AS NECESSARY TO REMOVE ALL DAMAGED OR BROKEN ROOTS, AND AS REQUIRED BY THE DISTRICT FORESTER OR RESOURCE SPECIALIST.

DIG PLANTING HOLES AT LEAST 12" WIDE AND 12" DEEP TO ACCOMMODATE ROOT MASS.

SET PLANTS PLUMB WITH THE ROOTS SPREAD PUT IN A NATURAL POSITION AT A DEPTH EQUAL TO THE DEPTH AT THE NURSERY.

HOLD PLANT FIRMLY AND PUDDLE (NOT TAMP) THE BACKFILL AROUND THE ROOTS WITH WATER. SUFFICIENT WATER SHALL BE USED TO ENSURE SATURATION OF THE BACKFILL, BUT CARE SHOULD BE TAKEN NOT TO OVERWATER, CAUSING A FLOATING SOIL MASS THAT PREVENTS COMPACTION AND MAY RESULT IN AIR POCKETS ADJACENT TO THE ROOTS. BACKFILL SHOULD BE FLUSH WITH THE GROUND AFTER COMPACTION.

COVER ENTIRE PLANT POCKET AREA WITH 4" MULCH AS SHOWN.



PERENNIAL PLANTS

FIRST AND SECOND WATERING AND CULTIVATION SHALL INCLUDE PERENNIAL BEDS.

PERENNIALS ARE TO BE FULLY DEVELOPED TWO YEAR #2 CONTAINER PLANTS.

ENTIRE PERENNIAL BED SHALL BE EXCAVATED DOWN 12" AND REPLACED WITH 12" OF PREPARED SOIL.

PERENNIAL BEDS ARE TO BE PAID FOR BY THE PAY ITEM 'SITE PREPARATION'.

SEEDING NOTES:

THIS STANDARD ILLUSTRATES THE TYPICAL USE OF SEEDING WITH MULCH, AS THESE ITEMS RELATE TO ROADWAY CONSTRUCTION. THE ACTUAL DESIGN AND MATERIALS USED TO CONSTRUCT THE COMPLETE SECTION, WHICH INCLUDES SEEDING WITH MULCHING, WILL BE ACCORDING TO THE PLANS AND CURRENT SPECIFICATIONS.

ITEMS CALLED FOR ON THIS STANDARD MAY ALSO BE USED DURING CONSTRUCTION AS AN EROSION CONTROL MEASURE. SEE STANDARD PLAN R-96-SERIES.

ALL DITCHES SHOULD HAVE HIGH VELOCITY MULCH BLANKET FOR EROSION CONTROL.

THE FIRST 8' BEHIND THE CURB OR SHOULDER IN URBAN MEDIAN AREAS WILL BE SEEDED, FERTILIZED, AND MULCHED WITH MULCH BLANKET. THE REMAINING AREAS WILL BE SEEDED, FERTILIZED, AND MULCHED WITH MULCH BLANKET OR STANDARD MULCH ANCHORED IN PLACE WITH A MULCH ADHESIVE OR WITH A MULCH NET.


ALL AREAS WHERE MULCH BLANKET IS CALLED FOR SHALL BE SEEDED, FERTILIZED, AND TOPSOILED AS SPECIFIED ON PLANS. NO MULCH OR ANCHORING MULCH IS REQUIRED WHERE MULCH BLANKET IS INSTALLED.

BACKSLOPE RESTORATION TREATMENT SHALL BE THE SAME AS THE FRONT SLOPE.


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

**SEEDING
AND TREE PLANTING**


F.H.W.A. APPROVAL	8-3-2021 PLAN DATE	R-100-I	SHEET 4 OF 4
-------------------	-----------------------	---------	-----------------




HMA SHOULDER PLAN
ADJACENT TO 12' LANE



HMA SHOULDER PLAN
ADJACENT TO 14' LANE




CONCRETE SHOULDER PLAN
ADJACENT TO 12' LANE




CONCRETE SHOULDER PLAN
ADJACENT TO 14' LANE

* THE DISTANCE FROM THE CORRUGATION TO THE TRANSVERSE JOINT SHALL BE AT LEAST 6" BUT LESS THAN 12".

* THE DISTANCE FROM THE CORRUGATION TO THE TRANSVERSE JOINT SHALL BE AT LEAST 6" BUT LESS THAN 12".



SECTION A - A



SECTION B - B

FREEWAY SHOULDER CORRUGATIONS
(FOR FREEWAY SHOULDERS PAVED 4 FEET OR GREATER)



PREPARED BY
DESIGN DIVISION

DRAWN BY: B.L.T.

CHECKED BY: W.K.P.

DEPARTMENT DIRECTOR
Paul C. Ajegba

APPROVED BY: _____
DIRECTOR, BUREAU OF FIELD SERVICES

APPROVED BY: _____
DIRECTOR, BUREAU OF DEVELOPMENT 177

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR


**SHOULDER AND CENTER LINE
CORRUGATIONS**

F.H.W.A. APPROVAL

9-7-2022
PLAN DATE

R-112-J

SHEET
1 OF 10



SHOULDER CORRUGATIONS AT BRIDGES
 FREEWAY SHOULDER CORRUGATIONS
 (FOR FREEWAY SHOULDERS PAVED 4 FEET OR GREATER)


MICHIGAN DEPARTMENT OF TRANSPORTATION
 BUREAU OF DEVELOPMENT STANDARD PLAN FOR
**SHOULDER AND CENTER LINE
 CORRUGATIONS**

F.H.W.A. APPROVAL	9-7-2022 PLAN DATE	R-112-J	SHEET 2 OF 10
-------------------	-----------------------	---------	------------------


* LATERAL DEVIATION SHALL NOT EXCEED 1" IN 100'.

NOTE:

ON CONCRETE PAVEMENTS, THE DISTANCE FROM A SHOULDER CORRUGATION TO A TRANSVERSE JOINT SHALL BE AT LEAST 6" BUT LESS THAN 12".





TYPICAL NON-FREEWAY SHOULDER CORRUGATION INSTALLATION



LOCATION	DEPTH AT EDGE	
	MILS	INCHES *
a	62.5	1/16
b	156	5/32
c	281	9/32
d	438	7/16
e	500	1/2

* +1/8"

PROFILE VIEW




SECTION E-E
CONCRETE & HMA SHOULDER

SINUSOIDAL CORRUGATIONS

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

SHOULDER AND CENTER LINE CORRUGATIONS




SHOULDER CORRUGATIONS ON TWO-WAY ROADWAYS

NON-FREEWAY SHOULDER CORRUGATIONS


(FOR NON-FREEWAY SHOULDERS PAVED 6 FEET OR GREATER)

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR		
SHOULDER AND CENTER LINE CORRUGATIONS		
	9-7-2022 PLAN DATE	R-112-J
F.H.W.A. APPROVAL		SHEET 4 OF 10




NOTE:

SHOULDER CORRUGATIONS MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVES, WHEN DIRECTED BY THE ENGINEER.



SHOULDER CORRUGATIONS AT INTERSECTIONS




SHOULDER CORRUGATIONS AT BRIDGES


**NON-FREEWAY SHOULDER CORRUGATIONS
(FOR NON-FREEWAY SHOULDERS PAVED 6 FEET OR GREATER)**

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

**SHOULDER AND CENTER LINE
CORRUGATIONS**




SHOULDER CORRUGATIONS AT INTERSECTIONS



SHOULDER CORRUGATIONS AT RAILROADS

NON-FREEWAY SHOULDER CORRUGATIONS
 (FOR NON-FREEWAY SHOULDERS PAVED 6 FEET OR GREATER)

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR		
SHOULDER AND CENTER LINE CORRUGATIONS		
	9-7-2022 PLAN DATE	R-112-J
182	F.H.W.A. APPROVAL	SHEET 6 OF 10



TYPICAL NON-FREEWAY CENTER LINE CORRUGATION INSTALLATION FOR CONCRETE PAVEMENT


* LATERAL DEVIATION SHALL NOT EXCEED 1" IN 100'.

NOTES:


ON CONCRETE PAVEMENTS, THE DISTANCE FROM A CENTER LINE CORRUGATION TO A TRANSVERSE JOINT SHALL BE AT LEAST 6" BUT LESS THAN 12".

ON CONCRETE PAVEMENTS, CORRUGATIONS MAY BE CONSTRUCTED IN TWO PASSES AND THEREFORE NOT BE SYMMETRICAL ACROSS THE CENTER LINE.


SEE NOTE




SECTION A-A



**SECTION B-B
SUPERELEVATED ROADWAY**




**SECTION B-B
CROWNED ROADWAY**




TYPICAL NON-FREEWAY CENTER LINE CORRUGATION INSTALLATION FOR HMA PAVEMENT


* LATERAL DEVIATION SHALL NOT EXCEED 1" IN 100'.



SECTION C-C



**SECTION D-D
SUPERELEVATED ROADWAY**




**SECTION D-D
CROWNED ROADWAY**


NON-FREEWAY CENTER LINE CORRUGATIONS

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

SHOULDER AND CENTER LINE CORRUGATIONS



CENTER LINE CORRUGATIONS ON TWO-WAY ROADWAYS




CENTER LINE CORRUGATIONS AT INTERSECTIONS

NON-FREEWAY CENTER LINE CORRUGATIONS

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR		
SHOULDER AND CENTER LINE CORRUGATIONS		
	9-7-2022 PLAN DATE	R-112-J
184	F.H.W.A. APPROVAL	SHEET 8 OF 10


TERMINATE CENTER LINE CORRUGATIONS
 3 TIMES WIDTH OF COMMERCIAL DRIVE
 OR AS DIRECTED BY THE ENGINEER
 SEE NOTES




RESIDENTIAL
 DRIVE

COMMERCIAL
 DRIVE

CENTER LINE CORRUGATIONS AT DRIVEWAYS



CENTER LINE CORRUGATIONS AT BRIDGES



CENTER LINE CORRUGATIONS AT RAILROADS

NON-FREEWAY CENTER LINE CORRUGATIONS

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR			
SHOULDER AND CENTER LINE CORRUGATIONS			
	9-7-2022 PLAN DATE	R-112-J	SHEET 9 OF 10
185	F.H.W.A. APPROVAL		

NOTES: (NON-FREEWAY)

SHOULDER CORRUGATION CROSS-SECTIONS AND LOCATIONS SHALL BE AS DETAILED ON THIS STANDARD. CORRUGATIONS ON NON-FREEWAYS SHALL BE IN CONCRETE AND HMA SHOULDERS PAVED AT LEAST 6'-0" WIDE WITH A POSTED SPEED OF 55 MPH. CORRUGATIONS CAN BE USED IN OTHER SITUATIONS WHERE THEY HAVE BEEN PREVIOUSLY APPROVED USING CURRENT GUIDELINES.

CORRUGATIONS SHALL NOT BE PLACED OVER A TRANSVERSE SHOULDER JOINT.

DO NOT MILL SHOULDER OR CENTER LINE CORRUGATIONS THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.

NOTES: (FREEWAY)

SHOULDER CORRUGATION CROSS-SECTIONS AND LOCATIONS SHALL BE AS DETAILED ON THIS STANDARD. CORRUGATIONS ON FREEWAYS SHALL BE IN CONCRETE AND HMA SHOULDERS PAVED 4'-0" OR WIDER OR WHERE THE SHOULDER LIES BETWEEN THE PAVEMENT AND VALLEY GUTTER OR CURB AND GUTTER. CORRUGATIONS WILL NOT BE USED IN FREEWAY EXIT/ENTRANCE RAMP SHOULDERS OR WHERE SHOULDERS ARE SEPARATED FROM THE PAVEMENT BY VALLEY GUTTER OR CURB AND GUTTER. EXCEPT FOR LOOP RAMP, CORRUGATIONS WILL BE USED ON FREEWAY TO FREEWAY RAMP.

CORRUGATIONS SHALL NOT BE PLACED OVER A TRANSVERSE SHOULDER JOINT.

CORRUGATION LOCATION IN THE AREA OF FREEWAY RAMP WILL BE AS FOLLOWS: THE TYPICAL OFFSET WILL BE INCREASED TO 24" AND BE LOCATED ON THE SHOULDER SIDE OF THE JOINT BEGINNING 300' IN ADVANCE OF THE EXIT RAMP TAPER. THIS OFFSET WILL CONTINUE UNTIL THE 2' POINT OF THE GORE. FOR EXIT/ENTRANCE RAMP AND LOOPS RAMP THE CORRUGATIONS WILL END ALONG THE RAMP AT THIS POINT AND SIMULTANEOUSLY RESUME ON THE MAINLINE SHOULDER AND GORE WITH THE NORMAL OFFSET. THE CONFIGURATION FOR ENTRANCE RAMP WILL BE IN THE REVERSE ORDER OF THE EXIT RAMP. FOR FREEWAY TO FREEWAY RAMP, IN ADDITION TO RESUMING THE MAINLINE SHOULDER CORRUGATION AT THIS POINT, RETURN TO THE NORMAL MAINLINE OFFSET ALONG THE LENGTH OF THE RAMP SHOULDER.

WITHIN AN URBAN FREEWAY AREA OR OTHER LIMITED FREEWAY AREA, SHOULDER CORRUGATIONS MAY BE OFFSET UP TO 12" FROM THE EDGE OF THE TRAVEL LANE, AS SHOWN IN THE PLANS, OR AS DIRECTED BY THE ENGINEER. IF NEEDED, THE CORRUGATION MAY BE LOCATED ON THE OPPOSITE SIDE OF THE JOINT FOR 14' LANES TO MAINTAIN THE MINIMUM OFFSET TO THE JOINT LINE.


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN FOR

SHOULDER AND CENTER LINE
CORRUGATIONS


	9-7-2022	R-112-J	SHEET 10 OF 10
F.H.W.A. APPROVAL	PLAN DATE		

TYPES OF TEMPORARY LONGITUDINAL LINES


BROKEN WHITE LANE LINE (1)




BROKEN WHITE LANE LINE (2)




SOLID WHITE LANE LINE OR LANE SHIFT




BROKEN YELLOW CENTERLINE (1)




BROKEN YELLOW CENTERLINE (2)




SOLID WHITE EDGE LINE



SOLID YELLOW EDGE LINE




SOLID WHITE GORE MARKING




LINE PATTERNS

TWO - LANE PASSING PROHIBITED (YELLOW)




DOUBLE SOLID YELLOW (OR WHITE)




Notes:

1. See project documents for correct broken line pattern.

 PREPARED BY TSMO DIVISION DRAWN BY: <u>MKB</u> CHECKED BY: <u>KMW</u>	DEPARTMENT DIRECTOR Paul C. Ajegba APPROVED BY: _____ (SPECIAL DETAIL) DIRECTOR, BUREAU OF FIELD SERVICES	MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF DEVELOPMENT STANDARD PLAN FOR TEMPORARY LONGITUDINAL LINE TYPES & PLACEMENT		
	APPROVED BY: _____ 187 (SPECIAL DETAIL) DIRECTOR, BUREAU OF DEVELOPMENT	(SPECIAL DETAIL) F.H.W.A. APPROVAL	(SPECIAL DETAIL) PLAN DATE	PAVE-904-B SHEET 1 OF 2

BASIC COLOR RULE: WHITE LINES SEPARATE FLOW OF TRAFFIC IN THE SAME DIRECTION, YELLOW LINES SEPARATE FLOW OF TRAFFIC IN THE OPPOSITE DIRECTION.



PLACEMENT OF LINES

Notes:

1. Temporary marking locations shall conform with section 812 of the Standard Specifications for Construction.
2. See PAVE-905 for locations of permanent pavement marking lines.
3. Remove pavement markings that conflict with proposed temporary traffic markings before making any changes in traffic pattern. Do not use paint or bituminous bond coat to cover existing and inappropriate pavement markings. Tape may only be used with approval of the Engineer.

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF DEVELOPMENT STANDARD PLAN

188

(SPECIAL DETAIL)
F.H.W.A. APPROVAL

(SPECIAL DETAIL)
PLAN DATE

PAVE-904-B

SHEET
2 OF 2

NOTICE TO BIDDERS - INQUIRY

All inquiries concerning the plans and proposal for this project are to be directed to:

Name

Title

MDOT-eProposal@Michigan.gov

E-mail Address

All inquiries must be made by E-mail through the electronic proposal system at [MILogin for Third Party](#)'s MDOT e-Proposal application.

Telephone inquiries will not be answered.

To be able to process and distribute an addendum, if required, all inquiries shall be made at least seven (7) calendar days before the letting.

Inquiries made after this date will be considered by MDOT, but will not require a response.

Inquiries made by MDOT's e-Proposal application must include the following information:

- Proposal Item Number
- Contract ID
- Name of Inquiring Person
- Company Name
- Phone and E-mail address
- Detailed question(s) with reference to proposal page and plan sheet number

Other employees of MDOT have been instructed to direct all inquiries to the person mentioned above.

07/2021

"General Decision Number: **MI20230001 08/25/2023**

Superseded General Decision Number: MI20220001

State: Michigan

Construction Types: Highway (Highway, Airport & Bridge xxxxx and Sewer/Incid. to Hwy.)

Counties: Michigan Statewide.

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an option is exercised) on or after January 30, 2022: 	. Executive Order 14026 generally applies to the contract. . The contractor must pay all covered workers at least \$16.20 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2023.
If the contract was awarded on or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022: 	. Executive Order 13658 generally applies to the contract. . The contractor must pay all covered workers at least \$12.15 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on that contract in 2023.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the

Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at <http://www.dol.gov/whd/govcontracts>.

Modification Number	Publication Date
0	01/06/2023
1	02/03/2023
2	02/17/2023
3	03/17/2023
4	05/12/2023
5	05/19/2023
6	05/26/2023
7	07/21/2023
8	08/25/2023

CARP0004-004 06/01/2019

REMAINDER OF STATE

	Rates	Fringes
CARPENTER (Piledriver).....	\$ 27.62	20.59

CARP0004-005 06/01/2018

LIVINGSTON (Townships of Brighton, Deerfield, Genoa, Hartland, Oceola & Tyrone), MACOMB, MONROE, OAKLAND, SANILAC, ST. CLAIR AND WAYNE COUNTIES

	Rates	Fringes
CARPENTER (Piledriver).....	\$ 30.50	27.28

ELEC0017-005 06/01/2022

STATEWIDE

	Rates	Fringes
Line Construction		
Groundman/Driver.....	\$ 29.57	7.20+32%
Journeyman Signal Tech, Communications Tech, Tower Tech & Fiber Optic Splicers.	\$ 43.90	7.20+32%

Journeyman Specialist.....	\$ 50.49	7.20+32%
Operator A.....	\$ 37.13	7.20+32%
Operator B.....	\$ 34.67	7.20+32%

Classifications

Journeyman Specialist: Refers to a crew of only one person working alone.

Operator A: Shall be proficient in operating all power equipment including: Backhoe, Excavator, Directional Bore and Boom/Digger truck.

Operator B: Shall be proficient in operating any 2 of the above mentioned pieces of equipment listed under Operator A.

 ENGI0324-003 06/01/2023

ALCONA, ALPENA, ARENAC, BAY, CHEBOYGAN, CLARE, CLINTON, CRAWFORD, GENESEE, GLADWIN, GRATIOT, HURON, INGHAM, IOSCO, ISABELLA, JACKSON, LAPEER, LENAWEE, LIVINGSTON, MACOMB, MIDLAND, MONROE, MONTMORENCY, OAKLAND, OGEMAW, OSCODA, OTSEGO, PRESQUE ISLE, ROSCOMMON, SAGINAW, ST. CLAIR, SANILAC, SHIAWASSEE, TUSCOLA, WASHTENAW AND WAYNE COUNTIES:

	Rates	Fringes
OPERATOR: Power Equipment (Steel Erection)		
GROUP 1.....	\$ 53.02	25.25
GROUP 2.....	\$ 54.02	25.25
GROUP 3.....	\$ 51.52	25.25
GROUP 4.....	\$ 52.52	25.25
GROUP 5.....	\$ 50.02	25.25
GROUP 6.....	\$ 51.02	25.25
GROUP 7.....	\$ 49.75	25.25
GROUP 8.....	\$ 50.75	25.25
GROUP 9.....	\$ 49.30	25.25
GROUP 10.....	\$ 50.30	25.25
GROUP 11.....	\$ 48.57	25.25
GROUP 12.....	\$ 49.57	25.25
GROUP 13.....	\$ 48.21	25.25
GROUP 14.....	\$ 49.21	25.25
GROUP 15.....	\$ 47.57	25.25
GROUP 16.....	\$ 44.37	25.25
GROUP 17.....	\$ 28.89	12.40
GROUP 18.....	\$ 33.38	25.25

FOOTNOTE:

Paid Holidays: New Year's Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day and Christmas Day.

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Engineer when operating combination of boom and jib 400' or longer

GROUP 2: Engineer when operating combination of boom and jib 400' or longer on a crane that requires an oiler

GROUP 3: Engineer when operating combination of boom and jib 300' or longer

GROUP 4: Engineer when operating combination of boom and jib 300' or longer on a crane that requires an oiler

GROUP 5: Engineer when operating combination of boom and jib 220' or longer

GROUP 6: Engineer when operating combination of boom and jib 220' or longer on a crane that requires an oiler

GROUP 7: Engineer when operating combination of boom and jib 140' or longer

GROUP 8: Engineer when operating combination of boom and jib 140' or longer on a crane that requires an oiler

GROUP 9: Tower crane & derrick operator (where operator's work station is 50 ft. or more above first sub-level)

GROUP 10: Tower crane & derrick operator (where operator's work station is 50 ft. or more above first sub-level) on a crane that requires an oiler

GROUP 11: Engineer when operating combination of boom and jib 120' or longer

GROUP 12: Engineer when operating combination of boom and jib 120' or longer on a crane that requires an oiler

GROUP 13: Crane operator; job mechanic and 3 drum hoist and excavator

GROUP 14: Crane operator on a crane that requires an oiler

GROUP 15: Hoisting operator; 2 drum hoist and rubber tired backhoe

GROUP 16: Forklift and 1 drum hoist

GROUP 17: Compressor or welder operator

GROUP 18: Oiler

ENGI0324-004 06/01/2023

AREA 1: ALLEGAN, BARRY, BERRIEN, BRANCH, CALHOUN, CASS, EATON, HILLSDALE, IONIA, KALAMAZOO, KENT, LAKE, MANISTEE, MASON, MECOSTA, MONTCALM, MUSKEGON, NEWAYGO, OCEANA, OSCEOLA, OTTAWA, ST. JOSEPH, VAN BUREN

AREA 2: ANTRIM, BENZIE, CHARLEVOIX, EMMET, GRAND TRAVERSE, KALKASKA, LEELANAU, MISSAUKEE AND WEXFORD COUNTIES:

	Rates	Fringes
OPERATOR: Power Equipment		
(Steel Erection)		
AREA 1		
GROUP 1.....	\$ 53.02	25.25
GROUP 2.....	\$ 49.75	25.25
GROUP 3.....	\$ 48.21	25.25
GROUP 4.....	\$ 44.37	25.25
GROUP 5.....	\$ 28.89	12.40
GROUP 6.....	\$ 33.38	25.25
AREA 2		
GROUP 1.....	\$ 53.02	25.25
GROUP 2.....	\$ 49.75	24.25
GROUP 3.....	\$ 48.21	25.25
GROUP 4.....	\$ 44.37	25.25
GROUP 5.....	\$ 28.89	12.40
GROUP 6.....	\$ 33.38	25.25

FOOTNOTES:

Crane operator with main boom and jib 300' or longer: \$1.50 additional to the group 1 rate. Crane operator with main boom and jib 400' or longer: \$3.00 additional to the group 1 rate.

PAID HOLIDAYS: New Year's Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day and Christmas Day.

POWER EQUIPMENT OPERATOR CLASSIFICATIONS:

GROUP 1: Crane Operator with main boom & jib 400', 300', or 220' or longer.

GROUP 2: Crane Operator with main boom & jib 140' or longer, Tower Crane; Gantry Crane; Whirley Derrick.

GROUP 3: Regular Equipment Operator, Crane, Dozer, Loader, Hoist, Straddle Wagon, Mechanic, Grader and Hydro Excavator.

GROUP 4: Air Tugger (single drum), Material Hoist Pump 6" or over, Elevators, Brokk Concrete Breaker.

GROUP 5: Air Compressor, Welder, Generators, Conveyors

GROUP 6: Oiler and fire tender

 ENGI0324-005 09/01/2022

AREA 1: GENESEE, LAPEER, LIVINGSTON, MACOMB, MONROE, OAKLAND, ST. CLAIR, WASHTENAW AND WAYNE COUNTIES

AREA 2: ALCONA, ALLEGAN, ALGER, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX, CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA, DICKINSON, EATON, EMMET, GLADWIN, GOGEBIC, GRAND TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA, IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT, KWEENAW, LAKE, LEELANAU, LENAWEE, LUCE, MACKINAC, MANISTEE, MARQUETTE, MASON, MECOSTA, MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MUSKEGON, NEWAYGO, OCEANA, OGEMAW, ONTONAGON, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SAGINAW, SANILAC, SCHOOLCRAFT, SHIAWASSEE, ST. JOSEPH, TUSCOLA, VAN BUREN AND WEXFORD COUNTIES

	Rates	Fringes
OPERATOR: Power Equipment (Underground construction (including sewer))		
AREA 1:		
GROUP 1.....	\$ 39.38	24.85
GROUP 2.....	\$ 34.65	24.85
GROUP 3.....	\$ 33.92	24.85
GROUP 4.....	\$ 33.35	24.85
GROUP 5.....	\$ 24.90	12.05

AREA 2:

GROUP 1.....	\$ 37.67	24.85
GROUP 2.....	\$ 32.78	24.85
GROUP 3.....	\$ 32.28	24.85
GROUP 4.....	\$ 32.00	24.85
GROUP 5.....	\$ 24.90	12.05

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Backfiller tamper; Backhoe; Batch plant operator (concrete); Clamshell; Concrete paver (2 drums or larger); Conveyor loader (Euclid type); Crane (crawler, truck type or pile driving); Dozer; Dragline; Elevating grader; Endloader; Gradall (and similar type machine); Grader; Mechanic; Power shovel; Roller (asphalt); Scraper (self-propelled or tractor drawn); Side boom tractor (type D-4 or equivalent and larger); Slip form paver; Slope paver; Trencher (over 8 ft. digging capacity); Well drilling rig; Concrete pump with boom operator; Hydro Excavator

GROUP 2: Boom truck (power swing type boom); Crusher; Hoist; Pump (1 or more - 6-in. discharge or larger - gas or diesel- powered or powered by generator of 300 amperes or more - inclusive of generator); Side boom tractor (smaller than type D-4 or equivalent); Tractor (pneu-tired, other than backhoe or front end loader); Trencher (8-ft. digging capacity and smaller); Vac Truck and End dump operator;

GROUP 3: Air compressors (600 cfm or larger); Air compressors (2 or more-less than 600 cfm); Boom truck (non-swinging, non- powered type boom); Concrete breaker (self-propelled or truck mounted - includes compressor); Concrete paver (1 drum-1/2 yd. or larger); Elevator (other than passenger); Maintenance person; Pump (2 or more-4-in. up to 6-in. discharge-gas or diesel powered - excluding submersible pumps); Pumpcrete machine (and similar equipment); Wagon drill (multiple); Welding machine or generator (2 or more-300 amp. or larger - gas or diesel powered)

GROUP 4: Boiler; Concrete saw (40 hp or over); Curing machine (self-propelled); Farm tractor (with attachment); Finishing machine (concrete); Hydraulic pipe pushing machine; Mulching equipment; Pumps (2 or more up to 4-in. discharge, if used 3 hours or more a day, gas or diesel powered - excluding submersible pumps); Roller (other than asphalt); Stump remover; Trencher (service); Vibrating compaction equipment, self-propelled (6 ft. wide or over); Sweeper

(Wayne type); Water wagon and Extend-a boom forklift

Group 5: Fire Person, Oiler

* ENGI0324-006 06/01/2023

GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW, WAYNE, ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX, CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA, DICKINSON, EATON, EMMET, GLADWIN, GOGEBIC, GRAND TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA, IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT, KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LIVINGSTON, LUCE, MACKINAC, MANISTEE, MARQUETTE, MASON, MECOSTA, MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MUSKEGON, NEWAYGO, OCEANA, OGEMAW, ONTONAGON, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SAGINAW, ST. CLARE, ST. JOSEPH, SANILAC, SCHOOLCRAFT, SHIAWASSEE, TUSCOLA, VAN BUREN AND WEXFORD COUNTIES

	Rates	Fringes
Power equipment operators: (AIRPORT, BRIDGE & HIGHWAY CONSTRUCTION)		
GROUP 1.....	\$ 40.46	25.25
GROUP 2.....	\$ 37.73	25.25
GROUP 3.....	\$ 33.17	25.55
GROUP 4.....	\$ 33.00	25.25

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Asphalt plant operator; Crane operator (does not include work on bridge construction projects when the crane operator is erecting structural components); Dragline operator; Shovel operator; Locomotive operator; Paver operator (5 bags or more); Elevating grader operator; Pile driving operator; Roller operator (asphalt); Blade grader operator; Trenching machine operator (ladder or wheel type); Auto-grader; Slip form paver; Self-propelled or tractor-drawn scraper; Conveyor loader operator (Euclid type); Endloader operator (1 yd. capacity and over); Bulldozer; Hoisting engineer; Tractor operator; Finishing machine operator (asphalt); Mechanic; Pump operator (6-in. discharge or over, gas, diesel powered or generator of 300 amp. or larger); Shouldering or gravel distributing machine operator (self-propelled); Backhoe (with over 3/8 yd. bucket); Side boom tractor (type D-4 or equivalent or

larger); Tube finisher (slip form paving); Gradall (and similar type machine); Asphalt paver (self-propelled); Asphalt planer (self-propelled); Batch plant (concrete-central mix); Slurry machine (asphalt); Concrete pump (3 in. and over); Roto-mill; Swinging boom truck (over 12 ton capacity); Hydro demolisher (water blaster); Farm-type tractor with attached pan; Vacuum truck operator; Batch Plant (concrete dry batch); Concrete Saw Operator (40h.p. or over); Tractor Operator (farm type); Finishing Machine Operator (concrete); Grader Operator (self-propelled fine grade or form (concrete)).

GROUP 2: Screening plant operator; Washing plant operator; Crusher operator; Backhoe (with 3/8 yd. bucket or less); Side boom tractor (smaller than D-4 type or equivalent); Sweeper (Wayne type and similar equipment); Greese Truck; Air Compressor Operator (600 cu.ft. per min or more); Air Compressor Operator (two or more, less than 600 cfm);

GROUP 3: Boiler fire tender; Tractor operator (farm type with attachment); Concrete Breaker; Wagon Drill Operator;

GROUP 4: Oiler; Fire tender; Trencher (service); Flexplane operator; Cleftplane operator; Boom or winch hoist truck operator; Endloader operator *under 1 yd. capacity); Roller Operator (other than asphalt); Curing equipment operator (self-propelled); Power bin operator; Plant drier (6 ft. wide or over); Guard post driver operator (power driven); All mulching equipment; Stump remover; Concrete pump (under 3-in.); Mesh installer (self-propelled); End dump; Skid Steer.

 ENGI0324-007 05/01/2023

ALGER, BARAGA, CHIPPEWA, DELTA, DICKINSON, GOGEBIC, HOUGHTON, IRON, KEWEENAW, LUCE, MACKINAC MARQUETTE, MENOMINEE, ONTONAGON AND SCHOOLCRAFT COUNTIES:

	Rates	Fringes
OPERATOR: Power Equipment (Steel Erection)		
Compressor, welder and forklift.....	\$ 38.50	25.00
Crane operator, main boom & jib 120' or longer.....	\$ 44.97	25.00
Crane operator, main boom & jib 140' or longer.....	\$ 44.17	24.60

Crane operator, main boom & jib 220' or longer.....	\$ 45.27	25.00
Mechanic with truck and tools.....	\$ 44.10	25.00
Oiler and fireman.....	\$ 39.96	25.00
Regular operator.....	\$ 42.32	25.00

 ENGI0324-008 10/01/2022

ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY,
 BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX,
 CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA,
 DICKINSON, EATON, EMMET, GENESEE, GLADWIN, GOGEBIC, GRAND
 TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA,
 IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT,
 KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LIVINGSTON, LUCE,
 MACKINAC, MACOMB, MANISTEE, MARQUETTE, MASON, MECOSTA,
 MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MONROE,
 MUSKEGON, NEWAYGO, OAKLAND, OCEANA, OGEMAW, ONTONAGON, OSCEOLA,
 OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SAGINAW, ST.
 CLARE, ST. JOSEPH, SANILAC, SCHOOLCRAFT, SHIAWASSEE, TUSCOLA,
 VAN BUREN, WASHTENAW, WAYNE AND WEXFORD COUNTIES

	Rates	Fringes
OPERATOR: Power Equipment (Sewer Relining)		
GROUP 1.....	\$ 35.37	14.77
GROUP 2.....	\$ 33.33	14.77

SEWER RELINING CLASSIFICATIONS

GROUP 1: Operation of audio-visual closed circuit TV system,
 including remote in-ground cutter and other equipment used
 in connection with the CCTV system

GROUP 2: Operation of hot water heaters and circulation
 systems, water jettors and vacuum and mechanical debris
 removal systems

 ENGI0325-012 05/01/2023

	Rates	Fringes
Power equipment operators - gas distribution and duct installation work:		
GROUP 1.....	\$ 36.18	25.25
GROUP 2.....	\$ 33.45	25.25

SCOPE OF WORK: The construction, installation, treating and reconditioning of pipelines transporting gas vapors within cities, towns, subdivisions, suburban areas, or within private property boundaries, up to and including private meter settings of private industrial, governmental or other premises, more commonly referred to as "distribution work," starting from the first metering station, connection, similar or related facility, of the main or cross country pipeline and including duct installation.

Group 1: Backhoe, crane, grader, mechanic, dozer (D-6 equivalent or larger), side boom (D-4 equivalent or larger), trencher(except service), endloader (2 yd. capacity or greater).

GROUP 2: Dozer (less than D-6 equivalent), endloader (under 2 yd. capacity), side boom (under D-4 capacity), backfiller, pumps (1 or 2 of 6-inch discharge or greater), boom truck (with powered boom), tractor (wheel type other than backhoe or front endloader). Tamper (self-propelled), boom truck (with non-powered boom), concrete saw (20 hp or larger), pumps (2 to 4 under 6-inch discharge), compressor (2 or more or when one is used continuously into the second day) and trencher(service). Oiler, hydraulic pipe pushing machine, grease person and hydrostatic testing operator.

 IRON0008-007 06/01/2022

ALGER, BARAGA, CHIPPEWA, DELTA, DICKINSON, GOGEBIC, HOUGHTON, IRON, KEWEENAW, LUCE, MACKINAC MARQUETTE, MENOMINEE, ONTONAGON AND SCHOOLCRAFT COUNTIES:

	Rates	Fringes
Ironworker - pre-engineered metal building erector.....	\$ 23.70	6.95
IRONWORKER		
General contracts		
\$10,000,000 or greater.....	\$ 38.14	28.70
General contracts less than \$10,000,000.....	\$ 38.14	28.70

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

 * IRON0025-002 06/01/2023

ALCONA, ALPENA, ARENAC, BAY, CHEBOYGAN, CLARE, CLINTON,
 CRAWFORD, GENESEE, GLADWIN, GRATIOT, HURON, INGHAM, IOSCO,
 ISABELLA, JACKSON, LAPEER, LIVINGSTON, MACOMB, MIDLAND,
 MONTMORENCY, OAKLAND, OGEMAW, OSCODA, OTSEGO, PRESQUE ISLE,
 ROSCOMMON, SAGINAW, SANILAC, SHIAWASSEE, ST. CLAIR, TUSCOLA,
 WASHTENAW AND WAYNE COUNTIES:

	Rates	Fringes
Ironworker - pre-engineered metal building erector		
ALLEGAN, ANTRIM, BARRY, BENZIE, BRANCH, CALHOUN, CHARLEVOIX, EATON, EMMET, GRAND TRAVERSE, HILLSDALE, IONIA, KALAMAZOO, KALKASKA, KENT, LAKE, LEELANAU, MANISTEE, MASON, MECOSTA, MISSAUKEE, MONTCALM, MUSKEGON, NEWAYGO, OCEANA, OSCEOLA, OTTAWA, ST. JOSEPH, VAN BUREN AND WEXFORD COUNTIES:..\$	24.59	25.43
Bay, Genesee, Lapeer, Livingston (east of Burkhardt Road), Macomb, Midland, Oakland, Saginaw, St. Clair, The University of Michigan, Washtenaw (east of U.S. 23) & Wayne...\$	25.81	26.43
IRONWORKER		
Ornamental and Structural...\$	34.50	38.44
Reinforcing.....\$	32.68	35.15

IRON0055-005 07/01/2022

LENAWEE AND MONROE COUNTIES:

	Rates	Fringes
IRONWORKER		
Pre-engineered metal buildings.....\$	23.59	19.35
All other work.....\$	33.00	27.20

IRON0292-003 06/01/2020

BERRIEN AND CASS COUNTIES:

	Rates	Fringes
IRONWORKER (Including pre-engineered metal building erector).....	\$ 31.75	22.84

LABO0005-006 10/01/2022

	Rates	Fringes
Laborers - hazardous waste abatement: (ALCONA, ALPENA, ANTRIM, BENZIE, CHARLEVOIX, CHEBOYGAN, CRAWFORD, EMMET, GRAND TRAVERSE, IOSCO, KALKASKA, LEELANAU, MISSAUKEE, MONTMORENCY, OSCODA, OTSEGO, PRESQUE ISLE AND WEXFORD COUNTIES - Zone 10)		
Levels A, B or C.....	\$ 17.45	12.75
class b.....	\$ 18.64	12.90
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 16.45	12.75
class a.....	\$ 17.64	12.90
Zone 10		
Laborers - hazardous waste abatement: (ALGER, BARAGA, CHIPPEWA, DELTA, DICKINSON, GOGEBIC, HOUGHTON, IRON, KEWEENAW, LUCE, MACKINAC, MARQUETTE, MENOMINEE, ONTONAGON AND SCHOOLCRAFT COUNTIES - Zone 11)		
Levels A, B or C.....	\$ 25.18	12.90
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 22.58	12.90
Laborers - hazardous waste abatement: (ALLEGAN, BARRY, BERRIEN, BRANCH, CALHOUN, CASS, IONIA COUNTY (except the city of Portland);		

KALAMAZOO, KENT, LAKE,
 MANISTEE, MASON, MECOSTA,
 MONTCALM, MUSKEGON, NEWAYGO,
 OCEANA, OSCEOLA, OTTAWA, ST.
 JOSEPH AND VAN BUREN COUNTIES
 - Zone 9)

Levels A, B or C.....	\$ 21.88	13.26
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 20.80	12.90

Laborers - hazardous waste
 abatement: (ARENAC, BAY,
 CLARE, GLADWIN, GRATIOT,
 HURON, ISABELLA, MIDLAND,
 OGEMAW, ROSCOMMON, SAGINAW
 AND TUSCOLA COUNTIES - Zone 8)

Levels A, B or C.....	\$ 23.74	12.95
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 20.80	12.90

Laborers - hazardous waste
 abatement: (CLINTON, EATON
 AND INGHAM COUNTIES; IONIA
 COUNTY (City of Portland);
 LIVINGSTON COUNTY (west of
 Oak Grove Rd., including the
 City of Howell) - Zone 6)

Levels A, B or C.....	\$ 26.33	12.95
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 24.64	12.90

Laborers - hazardous waste
 abatement: (GENESEE, LAPEER
 AND SHIAWASSEE COUNTIES -
 Zone 7)

Levels A, B or C.....	\$ 24.20	13.80
Work performed in conjunction with site preparation not requiring		

the use of personal protective equipment; Also, Level D.....\$ 23.20	13.80
Laborers - hazardous waste abatement: (HILLSDALE, JACKSON AND LENAWEЕ COUNTIES - Zone 4)	
Levels A, B or C.....\$ 27.13	14.95
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;	
Also, Level D.....\$ 24.17	12.90
Laborers - hazardous waste abatement: (LIVINGSTON COUNTY (east of Oak Grove Rd. and south of M-59, excluding the city of Howell); AND WASHTENAW COUNTY - Zone 3)	
Levels A, B or C.....\$ 29.93	14.20
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;	
Also, Level D.....\$ 28.93	14.20
Laborers - hazardous waste abatement: (MACOMB AND WAYNE COUNTIES - Zone 1)	
Levels A, B or C.....\$ 29.93	16.90
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;	
Also, Level D.....\$ 28.93	16.90
Laborers - hazardous waste abatement: (MONROE COUNTY - Zone 4)	
Levels A, B or C.....\$ 31.75	14.90
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;	
Also, Level D.....\$ 31.75	14.90
Laborers - hazardous waste	

abatement: (OAKLAND COUNTY
 and the Northeast portion of
 LIVINGSTON COUNTY bordered by
 Oak Grove Road on the West
 and M-59 on the South - Zone
 2)

Level A, B, C.....	\$ 29.93	16.90
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 28.93	16.90

Laborers - hazardous waste
 abatement: (SANILAC AND ST.
 CLAIR COUNTIES - Zone 5)

Levels A, B or C.....	\$ 26.21	16.62
Work performed in conjunction with site preparation not requiring the use of personal protective equipment;		
Also, Level D.....	\$ 24.75	16.35

 LABO0259-001 09/01/2022

AREA 1: MACOMB, OAKLAND AND WAYNE COUNTIES
 AREA 2: ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA,
 BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX,
 CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA,
 DICKINSON, EATON, EMMET, GENESEE, GLADWIN, GOGEBIC, GRAND
 TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA,
 IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT,
 KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LIVINGSTON, LUCE,
 MACKINAC, MANISTEE, MARQUETTE, MASON, MECOSTA, MENOMINEE,
 MIDLAND, MISSAUKEE, MONROE, MONTCALM, MONTMORENCY, MUSKEGON,
 NEWAYGO, OCEANA, OGEMAW, ONTONAGON, OSCEOLA, OSCODA, OTSEGO,
 OTTAWA, PRESQUE ISLE, ROSCOMMON, SAGINAW, ST. CLARE, ST.
 JOSEPH, SANILAC, SCHOOLCRAFT, SHIAWASSEE, TUSCOLA, VAN BUREN,
 WASHTENAW AND WEXFORD COUNTIES

	Rates	Fringes
Laborers - tunnel, shaft and caisson:		
AREA 1		
GROUP 1.....	\$ 23.62	16.95
GROUP 2.....	\$ 23.73	19.95
GROUP 3.....	\$ 23.79	16.95

GROUP 4.....	\$ 23.97	16.95
GROUP 5.....	\$ 24.22	16.95
GROUP 6.....	\$ 24.55	16.95
GROUP 7.....	\$ 17.83	16.95
AREA 2		
GROUP 1.....	\$ 25.15	12.95
GROUP 2.....	\$ 25.24	12.95
GROUP 3.....	\$ 25.34	12.95
GROUP 4.....	\$ 25.50	12.95
GROUP 5.....	\$ 25.76	12.95
GROUP 6.....	\$ 26.07	12.95
GROUP 7.....	\$ 18.34	12.95

SCOPE OF WORK: Tunnel, shaft and caisson work of every type and description and all operations incidental thereto, including, but not limited to, shafts and tunnels for sewers, water, subways, transportation, diversion, sewerage, caverns, shelters, aquifers, reservoirs, missile silos and steel sheeting for underground construction.

TUNNEL LABORER CLASSIFICATIONS

GROUP 1: Tunnel, shaft and caisson laborer, dump, shanty, hog house tender, testing (on gas) and watchman

GROUP 2: Manhole, headwall, catch basin builder, bricklayer tender, mortar machine and material mixer

GROUP 3: Air tool operator (jackhammer, bush hammer and grinder), first bottom, second bottom, cage tender, car pusher, carrier, concrete, concrete form, concrete repair, cement invert laborer, cement finisher, concrete shoveler, conveyor, floor, gasoline and electric tool operator, gunite, grout operator, welder, heading dinky person, inside lock tender, pea gravel operator, pump, outside lock tender, scaffold, top signal person, switch person, track, tugger, utility person, vibrator, winch operator, pipe jacking, wagon drill and air track operator and concrete saw operator (under 40 h.p.)

GROUP 4: Tunnel, shaft and caisson mucker, bracer, liner plate, long haul dinky driver and well point

GROUP 5: Tunnel, shaft and caisson miner, drill runner, key board operator, power knife operator, reinforced steel or mesh (e.g. wire mesh, steel mats, dowel bars, etc.)

GROUP 6: Dynamite and powder

GROUP 7: Restoration laborer, seeding, sodding, planting, cutting, mulching and top soil grading; and the restoration of property such as replacing mailboxes, wood chips, planter boxes, flagstones, etc.

 LABO0334-001 09/01/2022

	Rates	Fringes
Laborers - open cut:		
ZONE 1 - MACOMB, OAKLAND AND WAYNE COUNTIES:		
GROUP 1.....	\$ 23.47	16.72
GROUP 2.....	\$ 23.58	16.72
GROUP 3.....	\$ 23.63	16.72
GROUP 4.....	\$ 23.71	16.72
GROUP 5.....	\$ 24.17	16.72
GROUP 6.....	\$ 22.00	16.72
GROUP 7.....	\$ 17.84	16.72
ZONE 2 - LIVINGSTON COUNTY (east of M-151 (Oak Grove Rd.)); MONROE AND WASHTENAW COUNTIES:		
GROUP 1.....	\$ 25.20	16.72
GROUP 2.....	\$ 24.91	16.72
GROUP 3.....	\$ 25.03	16.72
GROUP 4.....	\$ 25.10	16.72
GROUP 5.....	\$ 25.25	16.72
GROUP 6.....	\$ 22.55	16.72
GROUP 7.....	\$ 22.11	16.72
ZONE 3 - CLINTON, EATON, GENESEE, HILLSDALE AND INGHAM COUNTIES; IONIA COUNTY (City of Portland); JACKSON, LAPEER AND LENAWEЕ COUNTIES; LIVINGSTON COUNTY (west of M-151 Oak Grove Rd.); SANILAC, ST. CLAIR AND SHIAWASSEE COUNTIES:		
GROUP 1.....	\$ 23.39	16.72
GROUP 2.....	\$ 23.13	16.72
GROUP 3.....	\$ 23.25	16.72
GROUP 4.....	\$ 23.30	16.72
GROUP 5.....	\$ 23.44	16.72
GROUP 6.....	\$ 20.74	16.72
GROUP 7.....	\$ 22.23	16.72

ZONE 4 - ALCONA, ALLEGAN,
ALPENA, ANTRIM, ARENAC,
BARRY, BAY, BENZIE,
BERRIEN, BRANCH,
CALHOUN, CASS, CHARLEVOIX,
CHEBOYGAN, CLARE,
CRAWFORD, EMMET,
GLADWIN, GRAND TRAVERSE,
GRATIOT AND HURON
COUNTIES; IONIA COUNTY
(EXCEPT THE CITY OF
PORTLAND); IOSCO,
ISABELLA, KALAMAZOO,
KALKASKA, KENT,
LAKE, LEELANAU, MANISTEE,
MASON, MECOSTA, MIDLAND,
MISSAUKEE, MONTCALM,
MONTMORENCY, MUSKEGON,
NEWAYGO, OCEANA, OGEMAW,
OSCEOLA, OSCODA, OTSEGO,
OTTAWA, PRESQUE ISLE,
ROSCOMMON, SAGINAW, ST.
JOSEPH, TUSCOLA, VAN BUREN
AND WEXFORD COUNTIES:

GROUP 1.....	\$ 22.42	16.72
GROUP 2.....	\$ 22.15	16.72
GROUP 3.....	\$ 22.26	16.72
GROUP 4.....	\$ 22.33	16.72
GROUP 5.....	\$ 22.45	16.72
GROUP 6.....	\$ 19.67	16.72
GROUP 7.....	\$ 22.30	16.72

ZONE 5 - ALGER, BARAGA,
CHIPPEWA, DELTA,
DICKINSON, GOGEBIC,
HOUGHTON, IRON,
KEWEENAW, LUCE, MACKINAC,
MARQUETTE, MENOMINEE,
ONTONAGON AND SCHOOLCRAFT
COUNTIES:

GROUP 1.....	\$ 22.24	16.72
GROUP 2.....	\$ 22.38	16.72
GROUP 3.....	\$ 22.51	16.72
GROUP 4.....	\$ 22.56	16.72
GROUP 5.....	\$ 22.64	16.72
GROUP 6.....	\$ 19.99	16.72
GROUP 7.....	\$ 22.45	16.72

SCOPE OF WORK:

Open cut construction work shall be construed to mean work which requires the excavation of earth including industrial, commercial and residential building site excavation and preparation, land balancing, demolition and removal of concrete and underground appurtenances, grading, paving, sewers, utilities and improvements; retention, oxidation, flocculation and irrigation facilities, and also including but not limited to underground piping, conduits, steel sheeting for underground construction, and all work incidental thereto, and general excavation. For all areas except the Upper Peninsula, open cut construction work shall also be construed to mean waterfront work, piers, docks, seawalls, breakwalls, marinas and all incidental work. Open cut construction work shall not include any structural modifications, alterations, additions and repairs to buildings, or highway work, including roads, streets, bridge construction and parking lots or steel erection work and excavation for the building itself and back filling inside of and within 5 ft. of the building and foundations, footings and piers for the building. Open cut construction work shall not include any work covered under Tunnel, Shaft and Caisson work.

OPEN CUT LABORER CLASSIFICATIONS

GROUP 1: Construction laborer

GROUP 2: Mortar and material mixer, concrete form person, signal person, well point person, manhole, headwall and catch basin builder, headwall, seawall, breakwall and dock builder

GROUP 3: Air, gasoline and electric tool operator, vibrator operator, driller, pump person, tar kettle operator, bracer, rodder, reinforced steel or mesh person (e.g., wire mesh, steel mats, dowel bars, etc.), welder, pipe jacking and boring person, wagon drill and air track operator and concrete saw operator (under 40 h.p.), windlass and tugger person and directional boring person

GROUP 4: Trench or excavating grade person

GROUP 5: Pipe layer (including crock, metal pipe, multi-plate or other conduits)

GROUP 6: Grouting man, audio-visual television operations and all other operations in connection with closed circuit

television inspection, pipe cleaning and pipe relining work and the installation and repair of water service pipe and appurtenances

GROUP 7: Restoration laborer, seeding, sodding, planting, cutting, mulching and top soil grading; and the restoration of property such as replacing mailboxes, wood chips, planter boxes, flagstones, etc.

LABO0465-001 06/01/2023

LABORER: Highway, Bridge and Airport Construction

AREA 1: GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE COUNTIES

AREA 2: ALLEGAN, BARRY, BAY, BERRIEN, BRANCH, CALHOUN, CASS, CLINTON, EATON, GRATIOT, HILLSDALE, HURON, INGHAM, JACKSON, KALAMAZOO, LAPEER, LENAWEE, LIVINGSTON, MIDLAND, MUSKEGON, SAGINAW, SANILAC, SHIAWASSEE, ST. CLAIR, ST. JOSEPH, TUSCOLA AND VAN BUREN COUNTIES

AREA 3: ALCONA, ALPENA, ANTRIM, ARENAC, BENZIE, CHARLEVOIX, CHEBOYGAN, CLARE, CRAWFORD, EMMET, GLADWIN, GRAND TRAVERSE, IONIA, IOSCO, ISABELLA, KALKASKA, KENT, LAKE, LEELANAU, MANISTEE, MASON, MECOSTA, MISSAUKEE, MONTCALM, MONTMORENCY, NEWAYGO, OCEANA, OGEMAW, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON AND WEXFORD COUNTIES

AREA 4: ALGER, BARAGA, CHIPPEWA, DELTA, DICKINSON, GOGEBIC, HOUGHTON, IRON, KEWEENAW, LUCE, MACKINAC, MARQUETTE, MENOMINEE, ONTONAGON AND SCHOOLCRAFT COUNTIES

	Rates	Fringes
LABORER (AREA 1)		
GROUP 1.....	\$ 29.67	13.45
GROUP 2.....	\$ 29.88	13.45
GROUP 3.....	\$ 30.17	13.45
GROUP 4.....	\$ 30.61	13.45
GROUP 5.....	\$ 30.23	13.45
GROUP 6.....	\$ 30.66	13.45
LABORER (AREA 2)		
GROUP 1.....	\$ 26.92	12.90
GROUP 2.....	\$ 27.12	12.90
GROUP 3.....	\$ 27.36	12.90
GROUP 4.....	\$ 27.71	12.90
GROUP 5.....	\$ 27.58	12.90

GROUP 6.....	\$ 27.92	12.90
LABORER (AREA 3)		
GROUP 1.....	\$ 26.22	12.90
GROUP 2.....	\$ 26.43	12.90
GROUP 3.....	\$ 26.72	12.90
GROUP 4.....	\$ 27.16	12.90
GROUP 5.....	\$ 26.78	12.90
GROUP 6.....	\$ 27.21	12.90
LABORER (AREA 4)		
GROUP 1.....	\$ 26.22	12.90
GROUP 2.....	\$ 26.43	12.90
GROUP 3.....	\$ 26.72	12.90
GROUP 4.....	\$ 27.16	12.90
GROUP 5.....	\$ 26.78	12.90
GROUP 6.....	\$ 27.21	12.90

LABORER CLASSIFICATIONS

GROUP 1: Asphalt shoveler or loader; asphalt plant misc.; burlap person; yard person; dumper (wagon, truck, etc.); joint filling laborer; miscellaneous laborer; unskilled laborer; sprinkler laborer; form setting laborer; form stripper; pavement reinforcing; handling and placing (e.g., wire mesh, steel mats, dowel bars); mason's tender or bricklayer's tender on manholes; manhole builder; headwalls, etc.; waterproofing, (other than buildings) seal coating and slurry mix, shoring, underpinning; pressure grouting; bridge pin and hanger removal; material recycling laborer; horizontal paver laborer (brick, concrete, clay, stone and asphalt); ground stabilization and modification laborer; grouting; waterblasting; top person; railroad track and trestle laborer; carpenters' tender; guard rail builders' tender; earth retention barrier and wall and M.S.E. wall installer's tender; highway and median installer's tender (including sound, retaining, and crash barriers); fence erector's tender; asphalt raker tender; sign installer; remote control operated equipment.

GROUP 2: Mixer operator (less than 5 sacks); air or electric tool operator (jackhammer, etc.); spreader; boxperson (asphalt, stone, gravel); concrete paddler; power chain saw operator; paving batch truck dumper; tunnel mucker (highway work only); concrete saw (under 40 h.p.) and dry pack machine; roto-mill grounds person.

GROUP 3: Tunnel miner (highway work only); finishers tenders; guard rail builders; highway and median barrier installer; earth retention barrier and wall and M.S.E. wall

installer's (including sound, retaining and crash barriers); fence erector; bottom person; powder person; wagon drill and air track operator; diamond and core drills; grade checker; certified welders; curb and side rail setter's tender.

GROUP 4: Asphalt raker

GROUP 5: Pipe layers, oxy-gun

GROUP 6: Line-form setter for curb or pavement; asphalt screed checker/screw man on asphalt paving machines.

LABO1076-005 04/01/2023

MICHIGAN STATEWIDE

	Rates	Fringes
LABORER (DISTRIBUTION WORK)		
Zone 1.....	\$ 25.17	13.32
Zone 2.....	\$ 24.22	13.45
Zone 3.....	\$ 21.60	13.45
Zone 4.....	\$ 20.97	13.43
Zone 5.....	\$ 21.00	13.40

DISTRIBUTION WORK - The construction, installation, treating and reconditioning of distribution pipelines transporting coal, oil, gas or other similar materials, vapors or liquids, including pipelines within private property boundaries, up to and including the meter settings on residential, commercial, industrial, institutional, private and public structures. All work covering pumping stations and tank farms not covered by the Building Trades Agreement. Other distribution lines with the exception of sewer, water and cable television are included.

Underground Duct Layer Pay: \$.40 per hour above the base pay rate.

- Zone 1 - Macomb, Oakland and Wayne
- Zone 2 - Monroe and Washtenaw
- Zone 3 - Bay, Genesee, Lapeer, Midland, Saginaw, Sanilac, Shiawassee and St. Clair
- Zone 4 - Alger, Baraga, Chippewa, Delta, Dickinson, Gogebic, Houghton, Iron, Keweenaw, Luce, Mackinac, Marquette, Menominee, Ontonagon and Schoolcraft
- Zone 5 - Remaining Counties in Michigan

PAIN0022-002 07/01/2008

HILLSDALE, JACKSON AND LENAWEE COUNTIES; LIVINGSTON COUNTY (east of the eastern city limits of Howell, not including the city of Howell, north to the Genesee County line and south to the Washtenaw County line); MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE COUNTIES:

	Rates	Fringes
PAINTER.....	\$ 25.06	14.75

FOOTNOTES: For all spray work and journeyman rigging for spray work, also blowing off, \$0.80 per hour additional (applies only to workers doing rigging for spray work on off the floor work. Does not include setting up or moving rigging on floor surfaces, nor does it apply to workers engaged in covering up or tending spray equipment. For all sandblasting and spray work performed on highway bridges, overpasses, tanks or steel, \$0.80 per hour additional. For all brushing, cleaning and other preparatory work (other than spraying or steeplejack work) at scaffold heights of fifty (50) feet from the ground or higher, \$0.50 per hour additional. For all preparatorial work and painting performed on open steel under forty (40) feet when no scaffolding is involved, \$0.50 per hour additional. For all swing stage work-window jacks and window belts-exterior and interior, \$0.50 per hour additional. For all spray work and sandblaster work to a scaffold height of forty (40) feet above the floor level, \$0.80 per hour additional. For all preparatorial work and painting on all highway bridges or overpasses up to forty (40) feet in height, \$0.50 per hour additional. For all steeplejack work performed where the elevation is forty (40) feet or more, \$1.25 per hour additional.

PAIN0312-001 06/01/2018

EXCLUDES: ALLEGAN COUNTY (Townships of Dorr, Fillmore, Heath, Hopkins, Laketown, Leighton, Manlius, Monterey, Overisel, Salem, Saugatuck and Wayland); INCLUDES: Barry, Berrien, Branch, Calhoun, Cass, Hillsdale, Kalamazoo, St. Joseph, Van Buren

	Rates	Fringes
PAINTER		
Brush and roller.....	\$ 23.74	13.35

Spray, Sandblast, Sign
 Painting.....\$ 24.94 13.35

 PAIN0845-003 05/10/2018

CLINTON COUNTY; EATON COUNTY (does not include the townships of Bellevue and Olivet); INGHAM COUNTY; IONIA COUNTY (east of Hwy. M 66); LIVINGSTON COUNTY (west of the eastern city limits of Howell, including the city of Howell, north to the Genesee County line and south to the Washtenaw County line); AND SHIAWASSEE COUNTY (Townships of Bennington, Laingsbury and Perry):

	Rates	Fringes
PAINTER.....	\$ 25.49	13.74

 PAIN0845-015 05/10/2018

MUSKEGON COUNTY; NEWAYGO COUNTY (except the Townships of Barton, Big Prairie, Brooks, Croton, Ensley, Everett, Goodwell, Grant, Home, Monroe, Norwich and Wilcox); OCEANA COUNTY; OTTAWA COUNTY (except the townships of Allendale, Blendone, Chester, Georgetown, Holland, Jamestown, Olive, Park, Polkton, Port Sheldon, Tallmadge, Wright and Zeeland):

	Rates	Fringes
PAINTER.....	\$ 25.49	13.74

 PAIN0845-018 05/10/2018

ALLEGAN COUNTY (Townships of Dorr, Fillmore, Heath, Hopkins, Laketown, Leighton, Manlius, Monterey, Overisel, Salem, Saugatuck and Wayland); IONIA COUNTY (west of Hwy. M-66); KENT, MECOSTA AND MONTCALM COUNTIES; NEWAYGO COUNTY (Townships of Barton, Big Prairie, Brooks, Croton, Ensley, Everett, Goodwell, Grant, Home, Monroe, Norwich and Wilcox); OSCEOLA COUNTY (south of Hwy. #10); OTTAWA COUNTY (Townships of Allendale, Blendone, Chester, Georgetown, Holland, Jamestown, Olive, Park, Polkton, Port Sheldon, Tallmadge, Wright and Zeeland):

	Rates	Fringes
PAINTER.....	\$ 25.49	13.74

FOOTNOTES: Lead abatement work: \$1.00 per hour additional.

 PAIN1011-003 06/02/2022

ALGER, BARAGA, CHIPPEWA, DELTA, DICKINSON, GOGEBIC, HOUGHTON,

IRON, KEWEENAW, LUCE, MACKINAC, MARQUETTE, MENOMINEE, ONTONAGON
AND SCHOOLCRAFT COUNTIES:

	Rates	Fringes
PAINTER.....	\$ 24.66	14.99

FOOTNOTES: High pay (bridges, overpasses, watertower): 30 to
80 ft.: \$.65 per hour additional. 80 ft. and over: \$1.30
per hour additional.

PAIN1474-002 06/01/2010

HURON COUNTY; LAPEER COUNTY (east of Hwy. M-53); ST. CLAIR,
SANILAC AND TUSCOLA COUNTIES:

	Rates	Fringes
PAINTER.....	\$ 23.79	12.02

FOOTNOTES: Lead abatement work: \$1.00 per hour additional.
Work with any hazardous material: \$1.00 per hour
additional. Sandblasting, steam cleaning and acid cleaning:
\$1.00 per hour additional. Ladder work at or above 40 ft.,
scaffold work at or above 40 ft., swing stage, boatswain
chair, window jacks and all work performed over a falling
height of 40 ft.: \$1.00 per hour additional. Spray gun
work, pick pullers and those handling needles, blowing off
by air pressure, and any person rigging (setting up and
moving off the ground): \$1.00 per hour additional.
Steeplejack, tanks, gas holders, stacks, flag poles, radio
towers and beacons, power line towers, bridges, etc.: \$1.00
per hour additional, paid from the ground up.

PAIN1803-003 06/01/2019

ALCONA, ALPENA, ANTRIM, ARENAC, BAY, BENZIE, CHARLEVOIX,
CHEBOYGAN, CLARE, CRAWFORD, EMMET, GLADWIN, GRAND TRAVERSE,
GRATIOT, IOSCO, ISABELLA, KALKASKA, LAKE, LEELANAU, MANISTEE,
MASON, MIDLAND, MISSAUKEE, MONTMORENCY AND OGEMAW COUNTIES;
OSCEOLA COUNTY (north of Hwy. #10); OSCODA, OTSEGO, PRESQUE
ISLE, ROSCOMMON, SAGINAW AND WEXFORD COUNTIES:

	Rates	Fringes
PAINTER		
Work performed on water, bridges over water or moving traffic, radio and		

powerline towers, elevated tanks, steeples, smoke stacks over 40 ft. of falling heights, recovery of lead-based paints and any work associated with industrial plants, except maintenance of industrial plants.....\$ 25.39 14.68
 All other work, including maintenance of industrial plant.....\$ 25.39 14.68

FOOTNOTES: Spray painting, sandblasting, blowdown associated with spraying and blasting, water blasting and work involving a swing stage, boatswain chair or spider: \$1.00 per hour additional. All work performed inside tanks, vessels, tank trailers, railroad cars, sewers, smoke stacks, boilers or other spaces having limited egress not including buildings, opentop tanks, pits, etc.: \$1.25 per hour additional.

PLAS0514-001 06/01/2018

ZONE 1: GENESEE, LIVINGSTON, MACOMB, MONROE, OAKLAND, SAGINAW, WASHTENAW AND WAYNE COUNTIES

ZONE 2: ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX, CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA, DICKINSON, EATON, EMMET, GLADWIN, GOGEBIC, GRAND TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA, IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT, KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LUCE, MACKINAC, MANISTEE, MARQUETTE, MASON, MECOSTA, MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MUSKEGON, NEWAYGO, OCEANA, OGEMAW, ONTONAGON, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SANILAC, SCHOOLCRAFT, SHIAWASSEE, ST. CLAIR, ST. JOSEPH, TUSCOLA, VAN BUREN AND WEXFORD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
ZONE 1.....	\$ 31.47	13.81
ZONE 2.....	\$ 29.97	13.81

PLUM0190-003 05/01/2015

ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY,
 BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX,
 CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA,
 DICKINSON, EATON, EMMET, GENESEE, GLADWIN, GOGEBIC, GRAND
 TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA,
 IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT,
 KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LIVINGSTON, LUCE,
 MACKINAC, MACOMB, MANISTEE, MARQUETTE, MASON, MECOSTA,
 MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MONROE,
 MUSKEGON, NEWAYGO, OAKLAND, OCEANA, OGEMAW, ONTONAGON, OSCEOLA,
 OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SAGINAW, ST.
 CLARE, ST. JOSEPH, SANILAC, SCHOOLCRAFT, SHIAWASSEE, TUSCOLA,
 VAN BUREN, WASHTENAW, WAYNE AND WEXFORD COUNTIES

	Rates	Fringes
lumber/Pipefitter - gas distribution pipeline: Welding in conjunction with gas distribution pipeline work.....	\$ 33.03	20.19
All other work:.....	\$ 24.19	12.28

 TEAM0007-004 06/01/2020

AREA 1: ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA,
 BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX,
 CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA,
 DICKINSON, EATON, EMMET, GLADWIN, GOGEBIC, GRAND TRAVERSE,
 GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA, IOSCO,
 IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT, KEWEENAW,
 LAKE, LAPEER, LEELANAU, LENAWEE, LUCE, MACKINAC, MANISTEE,
 MARQUETTE, MASON, MECOSTA, MENOMINEE, MIDLAND, MISSAUKEE,
 MONTCALM, MONTMORENCY, MUSKEGON, NEWAYGO, OCEANA, OGEMAW,
 ONTONAGON, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE,
 ROSCOMMON, SAGINAW, SANILAC, SCHOOLCRAFT, SHIAWASSEE, ST.
 CLAIR, ST. JOSEPH, TUSCOLA, VAN BUREN AND WEXFORD COUNTIES

AREA 2: GENESEE, LIVINGSTON, MACOMB, MONROE, OAKLAND, WASHTENAW
 AND WAYNE COUNTIES

	Rates	Fringes
TRUCK DRIVER AREA 1 Euclids, double bottoms and lowboys.....	\$ 28.05	.50 + a+b
Trucks under 8 cu. yds.....	\$ 27.80	.50 + a+b
Trucks, 8 cu. yds. and over.....	\$ 27.90	.50 + a+b

AREA 2

Euclids, double bottomms and lowboys.....	\$ 24.895	.50 + a+b
Euclids, double bottoms and lowboys.....	\$ 28.15	.50 + a+b
Trucks under 8 cu. yds.....	\$ 27.90	.50 + a+b
Trucks, 8 cu. yds. and over.....	\$ 28.00	.50 + a+b

Footnote:

- a. \$470.70 per week
- b. \$68.70 daily

TEAM0247-004 04/01/2013

AREA 1: ALCONA, ALGER, ALLEGAN, ALPENA, ANTRIM, ARENAC, BARAGA, BARRY, BAY, BENZIE, BERRIEN, BRANCH, CALHOUN, CASS, CHARLEVOIX, CHEBOYGAN, CHIPPEWA, CLARE, CLINTON, CRAWFORD, DELTA, DICKINSON, EATON, EMMET, GLADWIN, GOGEBIC, GRAND TRAVERSE, GRATIOT, HILLSDALE, HOUGHTON, HURON, INGHAM, IONIA, IOSCO, IRON, ISABELLA, JACKSON, KALAMAZOO, KALKASKA, KENT, KEWEENAW, LAKE, LAPEER, LEELANAU, LENAWEE, LUCE, MACKINAC, MANISTEE, MARQUETTE, MASON, MECOSTA, MENOMINEE, MIDLAND, MISSAUKEE, MONTCALM, MONTMORENCY, MUSKEGON, NEWAYGO, OCEANA, OGEMAW, ONTONAGON, OSCEOLA, OSCODA, OTSEGO, OTTAWA, PRESQUE ISLE, ROSCOMMON, SANILAC, SCHOOLCRAFT, SHIAWASSEE, SAGINAW, ST. CLAIR, ST. JOSEPH, TUSCOLA, VAN BUREN AND WEXFORD COUNTIES

AREA 2: GENESEE, LIVINGSTON, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE COUNTIES

	Rates	Fringes
Sign Installer		
AREA 1		
GROUP 1.....	\$ 21.78	11.83
GROUP 2.....	\$ 25.27	11.8375
AREA 2		
GROUP 1.....	\$ 22.03	11.83
GROUP 2.....	\$ 25.02	11.8375

FOOTNOTE:

- a. \$132.70 per week, plus \$17.80 per day.

SIGN INSTALLER CLASSIFICATIONS:

GROUP 1: performs all necessary labor and uses all tools

required to construct and set concrete forms required in the installation of highway and street signs

GROUP 2: performs all miscellaneous labor, uses all hand and power tools, and operates all other equipment, mobile or otherwise, required for the installation of highway and street signs

TEAM0247-010 04/01/2018

AREA 1: LAPEER AND SHIAWASSEE COUNTIES

AREA 2: GENESEE, MACOMB, MONROE, OAKLAND, ST. CLAIR, WASHTENAW AND WAYNE COUNTIES

	Rates	Fringes
TRUCK DRIVER (Underground construction)		
AREA 1		
GROUP 1.....	\$ 23.82	19.04
GROUP 2.....	\$ 23.91	19.04
GROUP 3.....	\$ 24.12	19.04
AREA 2		
GROUP 1.....	\$ 24.12	19.04
GROUP 2.....	\$ 24.26	19.04
GROUP 3.....	\$ 24.45	19.04

PAID HOLIDAYS: New Year's Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day and Christmas Day.

SCOPE OF WORK: Excavation, site preparation, land balancing, grading, sewers, utilities and improvements; also including but not limited to, tunnels, underground piping, retention, oxidation, flocculation facilities, conduits, general excavation and steel sheeting for underground construction. Underground construction work shall not include any structural modifications, alterations, additions and repairs to buildings or highway work, including roads, streets, bridge construction and parking lots or steel erection.

TRUCK DRIVER CLASSIFICATIONS

GROUP 1: Truck driver on all trucks (EXCEPT dump trucks of 8 cubic yards capacity or over, pole trailers, semis, low boys, Euclid, double bottom and fuel trucks)

GROUP 2: Truck driver on dump trucks of 8 cubic yards capacity or over, pole trailers, semis and fuel trucks

GROUP 3: Truck driver on low boy, Euclid and double bottom

 * SUMI2002-001 05/01/2002

	Rates	Fringes
Flag Person.....	\$ 10.10 **	0.00
LINE PROTECTOR (ZONE 1: GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE)....	\$ 22.89	13.45
LINE PROTECTOR (ZONE 2: STATEWIDE (EXCLUDING GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE).....	\$ 20.19	13.45
Pavement Marking Machine (ZONE 1: GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE COUNTIES) Group 1.....	\$ 30.52	13.45
Pavement Marking Machine (ZONE 1: GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE) Group 2.....	\$ 27.47	13.45
Pavement Marking Machine (ZONE 2: STATEWIDE (EXCLUDING GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE COUNTIES) Group 1.....	\$ 26.92	13.45
Pavement Marking Machine (ZONE 2: STATEWIDE (EXCLUDING GENESEE, MACOMB, MONROE, OAKLAND, WASHTENAW AND WAYNE) Group 2.....	\$ 24.23	13.45

WORK CLASSIFICATIONS:

PAVEMENT MARKER GROUP 1: Drives or operates a truck mounted

striper, grinder, blaster, groover, or thermoplastic melter for the placement or removal of temporary or permanent pavement markings or markers.

PAVEMENT MARKER GROUP 2: Performs all functions involved for the placement or removal of temporary or permanent pavement markings or markers not covered by the classification of Pavement Marker Group 1 or Line Protector.

LINE PROTECTOR: Performs all operations for the protection or removal of temporary or permanent pavement markings or markers in a moving convoy operation not performed by the classification of Pavement Marker Group 1. A moving convoy operation is comprised of only Pavement Markers Group 1 and Line Protectors.

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.
=====

** Workers in this classification may be entitled to a higher minimum wage under Executive Order 14026 (\$16.20) or 13658 (\$12.15). Please see the Note at the top of the wage determination for more information.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at <https://www.dol.gov/agencies/whd/government-contracts>.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after

award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the

wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour National Office because National Office has responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division

U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION"