

MIDLAND COUNTY ROAD COMMISSION

BID FORM

Sealed Proposals will be received at the office of Board of Road Commissioners, County of Midland, at 2334 N. Meridian Road, Sanford, Michigan, until:

DATE: Monday, March 7th, 2016 at 1:00 p.m.

**Item No. 26 – Cold Milling
Estimated Quantity, 5000 Syd**

Cold Milling.....\$ _____/SYD

DESCRIPTION:

This work shall consist of cold milling existing asphalt and base material to the depth and cross section shown on the log or plans. Includes all equipment, materials, and labor required to remove the material and haul it to MCRC's Clay Pit located in Sanford, MI. The projects sites will require removing HMA overlaying a concrete bridge deck and the associated road approaches to the limits shown on the log or plans.

LOCATIONS:

Three locations identified include Sasse Road over Fleming Drain in Ingersoll Twp. (est. 2400 syd, 0-7" +/- depth), Laporte Road over Fleming Drain in Ingersoll Twp. (est. 2400 syd, 0-7" +/- depth), and Barden Road over Howard Drain in Geneva Twp. (est. 200 syd., 0.5" +/- depth).

COMPANY BIDDING _____

CONTACT PERSON _____

ADDRESS _____

PHONE & FAX _____

AUTHORIZED SIGNATURE

TITLE

INDICATE ON ENVELOPE: Company Name, Item Number, Bid Item, Time and Date

MIDLAND COUNTY ROAD COMMISSION

SPECIAL PROVISION
FOR
COLD-MILLING

MCRC:ALB

1 of 1

02-08-16

a. Description. This work consists of removing the HMA pavement and base material to the depth and cross section shown on the log or plans (not to exceed 12”), and as directed by the Engineer.

b. Equipment. Use cold-milling machine(s) equipped with positive depth control adjustments and a positive means for controlling the cross slope. The cold-milling equipment must be capable of removing the chips from the pavement and preventing dust from escaping into the air.

c. Construction. Cold-mill the existing HMA pavement and base material to the depth and cross section indicated on the log or plans, and as directed by the Engineer. Collect and load material resulting from the operations as specified in subsections 104.07.D of the Standard Specifications for Construction. All millings are to be delivered by the contractor to one of 4 locations provided by MCRC based on the project location.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Cold Milling	Square Yard

Cold Milling includes removing, loading, and hauling of the material. This work will be measured by area in square yards regardless of the number of passes required to remove the HMA and associated base material to the required depth.