

MIDLAND COUNTY ROAD COMMISSION

BID FORM

Sealed Proposals will be received at the office of the Board of Road Commissioners, County of Midland, at 2334 N. Meridian Road, Sanford, Michigan 48657 until:

DATE: Monday, March 7th, 2016, at 1:00 P.M.

Item No. 28 – DITCH CLEANOUT

PAY ITEM

PRICE PER UNIT

DITCH CLEANOUT

\$ _____/Foot

DESCRIPTION

This work consists of completing earth excavation and embankment required to reshape or move a ditch to restore or establish positive drainage as set forth in the attached special provision.

PROGRESS SCHEDULE

Schedule will be determined by agreement between Contractor, MCRC, Township, or other agency that will share interest in the specific project.

COMPANY BIDDING _____

CONTACT PERSON _____

ADDRESS _____

PHONE/FAX _____

AUTHORIZED SIGNATURE

TITLE

INDICATE ON ENVELOPE: Company Name, Item Number, Bid Item, Time and Date

MIDLAND COUNTY ROAD COMMISSION

SPECIAL PROVISION
FOR
DITCH CLEANOUT

MCRC:ALB

1 of 1

02-11-16

a. Description. This work consists of completing earth excavation and embankment required to reshape or move a ditch to restore or establish positive drainage. The Engineer will provide the grade, shape and location of the ditch. This work also includes disposing of excess material and providing all traffic control necessary. Ditch Cleanout will take place county wide on rural county roads, and generally be segments of one half mile minimum lengths. The depth of Ditch Cleanout will be 2' or less on average.

b. Construction. Complete this work in accordance with section 205 of the Standard Specifications for Construction, details shown on the plans and this special provision. Soil erosion measures to be directed and materials provided by MCRC, installation by contractor.

Ditch Cleanout may include, but is not limited to, the following work:

1. Reshape and move existing ditch.
2. Remove cattails, brush and miscellaneous debris.
3. Remove trees less than 6 inches in diameter.
4. Flatten fill slopes around culvert extensions.
5. Blend ditch profile to match existing ditch.

Excavated earth may be used to fill existing ditches and to flatten fill slopes at culvert extensions, as approved by the Engineer. Otherwise all excess material to be removed to a site determined on a project by project basis.

Contractor will be responsible for notification of Miss Dig and all utility preservation as required under Michigan law.

c. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Ditch Cleanout.....	Foot

Ditch Cleanout includes all labor, equipment and materials required to complete the work as described and will be measured along the ditch centerline.