



MIDLAND
COUNTY ROAD COMMISSION
2334 N. MERIDIAN ROAD
SANFORD, MI 48657

Phone (989) 687-9060
Fax (989) 687-9121
www.midlandroads.com

Bid Form

7 MILE ROAD BRIDGE RECONSTRUCTION OVER THE BULLOCK CREEK

Deadline for Submittal: August 8, 2018 at 10:00 a.m.

Project Description:

The following bid covers all associated costs with the reconstruction of 7 Mile Road bridge over the Bullock Creek. The structure is a pre-cast deck panel structure on GRS abutments. Project includes, but is not limited to, soil erosion and sedimentation control, removal of existing structure and road bed, excavation for GRS abutments, under cutting unsuitable soils if necessary, construct abutments, setting MCRC owned deck panels, installing guardrail, rebuilding roadway, and installing aggregate base, **HMA road surface** and slope restoration.

Construction may begin within 5 days of award notification. All work including clean-up must be completed by November 9, 2018.

Contractor _____

Address _____

Contact _____

Telephone Number _____

Sealed Bids must be delivered to:

Midland County Road Commission
2334 North Meridian Road
Sanford, Michigan 48657

Please fill out and include the attached sheet with your bid when submitted.

The Midland County Road Commission reserves the right to reject any bid that appears to be unqualified.

Signature: _____

Date: _____

Pay Item	Description	Quantity	Units	Unit Price		Bid Amount	
				Dollars	Cts	Dollars	Cts
2040060	Structures, Rem	1	LSUM				
2050041	Subgrade Undercutting, Type II	50	Cyd				
2057002	_ Machine Grading, Modified	2	Sta				
2057021	_ Granular Embankment, AASHTO #89 Stone	758	Cyd				
2060010	Excavation, Fdn	2,054	Cyd				
2080036	Erosion Control, Silt Fence	400	Ft				
2080044	Erosion Control, Turbidity Curtain, Shallow	50	Ft				
3010002	Subbase, CIP	173	Cyd				
3020020	Aggregate Base, 8 inch	691	Syd				
3027021	_ RSF, MDOT 21AA. CIP, Crushed Limestone	116	Cyd				
3070028	Approach, CI II, 6 inch	88	Syd				
3070125	Shoulder, CI II, 3 inch	178	Syd				
3087011	_ High Strength Woven Polypropylene Fabric	5,195	Syd				
5010005	HMA Surface, Rem	585	Syd				
7040007	Cofferdams	1	LSUM				
7067001	_ Concrete Cap	73	Ft				
7067001	_ Reinforcement, Steel, Epoxy Coated Dowel	559	Ft				
7067050	_ Solid Concrete Masonry Block	970	Ea				
7067050	_ Splitface Concrete Masonry Block	1,260	Ea				

Pay Item	Description	Quantity	Units	Unit Price		Bid Amount		
				Dollars	Cts	Dollars	Cts	
7117001	_ Bridge Railing	60	Ft					
8077050	_ Guardrail Anch, Bridge, Nested	4	Ea					
8070000	Guardrail, Type B	50	Ft					
870040	Guardrail Approach Terminal, Type 1B	4	Ea					
8137011	_ Riprap, Heavy, Modified	200	Syd					
8167011	_ Slope Restoration, Modified	445	Syd					
1500001	Mobilization__ Addendum #1	1	LS					
7087051	Precast Concrete Panels, Installation Addendum #1	1	LS					
5010033	HMA, 13A__ Addendum #1	240	Ton					
Total Bid								